

TYLER COUNTY COMMISSIONERS COURT
REGULAR MEETING
February 24, 2020 ---- 11:00 a.m.

THE STATE OF TEXAS ON THIS THE 24th day of February, 2020 the Commissioners' Court in and for Tyler County, Texas convened in a Regular Meeting at the Commissioners' Courtroom in Woodville, Texas, the following members of the Court present, to wit:

JACQUES L. BLANCHETTE	COUNTY JUDGE, presiding
STEVAN STURROCK	COMMISSIONER, PCT. #2
MIKE MARSHALL	COMMISSIONER, PCT. #3
BUCK HUDSON	COMMISSIONER, PCT. #4
DEAN RIVERS	Chief-Deputy, COUNTY CLERK, Ex-Officio

The following were absent: Commissioner Nash thereby constituting a quorum. In addition to the above were: JACKIE SKINNER COUNTY AUDITOR
LEANN MONK COUNTY TREASURER
LYNNETTE CRUSE TAX ASSESSOR/COLLECTOR
SONDRA WILLIAMS TYLER COUNTY HOSPITAL ADMINISTRATOR
TINA CLEBERG VETERANS SERVICE OFFICER

After calling the meeting to order, Judge Blanchette invited anyone offended by the court's practice of an invocation and pledge of allegiance to step out in the hall and return after the conclusion. The invocation was delivered by Commissioner Sturrock. He then led in the Pledge of Allegiance to the Texas flag.

Public Comments: Sharon Andrus spoke to conditions of CR 3550

Commissioner Sturrock motioned to receive the minutes of February 10th, 2020. Commissioner Hudson seconded the motion. All voted yes and none no.

Budget amendments and line item transfers were not presented by the County Auditor.

The County Auditor brought attention to a bill from Everest on a radio tower. She stated the county should only be paying \$700.00. The remainder is not county responsibility. She recommended the refurbishment of courtroom benches be paid from the furnishings line item. A motion was made by **Commissioner Sturrock** and seconded by **Commissioner Marshall** to approve paying the **accounts payable**. All voted yes and none no. SEE ATTACHED

A motion was made by **Commissioner Sturrock** and seconded by **Commissioner Marshall** to approve the **District Clerk's monthly report**. All voted yes and none no.

Commissioner Marshall motioned to approve the **Bond** for the **Tax Assessor Collector**. **Commissioner Sturrock** seconded the motion. All voted yes and none no. SEE ATTACHED BOND. The court encouraged Lynette to have her chief-deputy also bonded.

Judge Blanchette motioned to suspend architectural services pending court review of construction documents. **Commissioner Marshall** seconded the motion. All voted yes and none no.

Judge Blanchette motioned to amend the Articles of Incorporation for the **Southeast Texas Flood Control District and appointing directors for that local government corporation**. **Commissioner Sturrock** seconded the motion. All voted yes and none no.

Judge Blanchette made a motion to appoint the **2020 Tyler County Census Complete County Committee** for the intended purpose of assuring complete count of all Tyler County residents for the **April 2020 Census**, as nominated by Commissioner Sturrock. **Commissioner Marshall** seconded the motion. All voted yes and none no. Those members are **Chris Edwards, Kathy Weaver, James Stephens, Casey and Betty Ann Whitworth, Frank Helm, Melanie Calhoun, Jimmy Tucker, Matt O'Neal, Kelly and Ken Jobe, Scott Vaughn, Gordon McClusky, Jerry Springfield, Kendall Coleman and Lisa Meysemborg**.

A motion was made by **Commissioner Sturrock** to appoint Donald Calhoun as the **Cybersecurity Information Technology Administrator**. **Commissioner Marshall** seconded the motion. All voted yes and none no.

A motion was made by **Commissioner Hudson** to renew the **postage meter** for the Tyler County Clerk, as requested by the County Auditor. The motion was seconded by **Commissioner Marshall**. All voted yes and none no. SEE ATTACHED

Commissioner Marshall motioned to renew the Sharp copier leases for county offices; new copiers will replace the older models. **Commissioner Hudson** seconded the motion. All voted yes and none no. SEE ATTACHED

Commissioner Sturrock motioned to appoint replace, rather than splice, the **fiber optic line** to the Sheriff's department at a cost of \$9890.86 from the contingency fund. **Commissioner Marshall** seconded the motion. All voted yes and none no. SEE ATTACHED

A motion was made by **Commissioner Marshall** to table consideration of subdivision regulations, manufactured home rental communities, RV parks, including establishing a calendar for further hearings and/or action on the topic, authorizing a takings impact assessment and authorizing publication of notice for public hearings on this topic. **Commissioner Hudson** seconded the motion. All voted yes and none no.

A motion was made by **Judge Blanchette** and seconded by **Commissioner Sturrock** to purchase an air conditioner for Room C in the nutrition center. All voted yes and none no.

Commissioner Hudson motioned to lease/purchase a 2021 Mack Haul Truck from Bruckner's Truck Sales to be financed with First National Leasing, Wichita Falls, TX. **Commissioner Marshall** seconded the motion. All voted yes and none no. SEE ATTACHED

Commissioner Hudson motioned to purchase a 2021 Belly Dump Trailer from Bruckner's Truck Sales to be financed with First National Leasing, Wichita Falls, TX. **Commissioner Marshall** seconded the motion. All voted yes and none no.

JUDGE'S REPORT – Courthouse remediation update: Judge Blanchette reported any additional work is being suspended. The roof is moving forward as much as possible working around inclement weather. The Veteran's Service Officer presented her report of two events and the numbers of veterans served. Mrs. Cleberg has completed her training for certification.

Executive Session was not held.



A motion was made by Commissioner Marshall and seconded by Commissioner Hudson that the meeting adjourn. All voted yes.

THERE BEING NO FURTHER BUSINESS, THE MEETING ADJOURNED: 11:34 a.m.

I, Donece Gregory, County Clerk and ex officio member of the Tyler County Commissioners Court, do hereby certify to the fact that the above is a true and correct record of the Tyler County Commissioners Court session held on February 24, 2020.

Witness my hand and seal of office on this the 9th day of March, 2020.

Attest:
Donece Gregory, County Clerk





COMMISSIONERS COURT

Public Comment Participation Form

To make public comments either for or against a topic or item which may or may not appear on a Commissioners Court Agenda, individual(s) should be aware of the following:

1. **This completed form must be submitted to the County Clerk prior to the start of Court!**
Public comments in Court will only be allowed at the designated place on the Agenda (unless a member of the Court requests otherwise).
2. Each individual will be limited to a *maximum of five (5) minutes* to address the Court. Maximum discussion on any Agenda item, regardless of the number of members of the public wishing to address the Court on any specific Agenda item (or items), shall be limited to thirty (30) minutes. In matters of exceptional interest to the Court, the Court, by a majority vote, may shorten or lengthen the time allocated for any or all Agenda items. Time for each speaker shall be maintained by the County Clerk or such other designated representative of the Commissioners Court.
3. Profane, insulting, or threatening language directed toward the Court and/or any person in the Court's presence and/or racial, ethnic, or gender slurs or epithets will not be tolerated.

Instructions: Please PRINT all appropriate blanks.

NAME: SHARON Andrus TELEPHONE: 409-382-5727
HOME ADDRESS: 408 Oak Street Colmesneer TX 75938
(Street) (City/State/Zip)

If you are speaking on behalf of a group or organization, please state its name, address and telephone number.

Which agenda item(s) do you wish to address? County Road 3550

Please state if you support or oppose such item(s)? OPPOSE

SIGNATURE: Sharon Andrus



Accounts Payable
January 27, 2020 – February 24, 2020



Tyler County, TX

CHECK REGISTER

By Fund

Payable Dates 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
Fund: 010 - GENERAL FUND							
HOKE, STEVEN		02/14/2020	185596/CDA	010-419-42100		02/14/2020	171.96
HOKE, STEVEN		02/14/2020	185596/CDA	010-419-42100		02/14/2020	-171.96
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-401-42111		01/28/2020	12.70
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-419-42222		01/28/2020	76.00
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-421-42189		01/28/2020	370.00
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-426-42182		01/28/2020	143.96
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-426-42659		01/28/2020	15.00
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-427-42659		01/28/2020	175.00
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	010-440-42101		01/28/2020	1,282.10
AFLAC INSURANCE	135773	01/29/2020	ADJUSTMENT/LEJUNE, DANA	010-401-40150		01/29/2020	-56.06
NATIONWIDE RETIREMENT S	135771	01/30/2020	Deferred Comp	010-21300		01/30/2020	62.50
US DEPARTMENT OF EDUCAT	135772	01/30/2020	STUDENT LOAN	010-21300		01/30/2020	253.33
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	010-21300		01/30/2020	16,223.54
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	010-21300		01/30/2020	10,711.50
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	010-21300		01/30/2020	3,794.22
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	010-29999		01/29/2020	100,587.84
CRUSE, LYNNETTE/TYLER CO	135779	01/29/2020	WHEAT BLOCK / 2019 TAX	010-453-43604		01/29/2020	2,506.09
CYPHER COMPUTERS	135798	01/31/2020	INV#0002258/ CO OFFICES	010-440-42353		01/31/2020	1,040.00
WEST BLUFF EMERGENCY PH	135829	01/31/2020	ACCT#10071394001ABO/TC	010-401-42231		01/31/2020	260.72
WEST BLUFF EMERGENCY PH	135830	01/31/2020	ACCT#10071403001ABO/TC	010-401-42231		01/31/2020	909.30
A T & T - 019 DATA PROC.	135790	01/31/2020	7328/CO OFFICES	010-440-42350		01/31/2020	1,094.95
GIBBS, PAULA	135804	01/31/2020	MILEAGE REIMB/ CDA	010-419-42222		01/31/2020	121.90
U.S. POSTAL SERVICE (POSTA	135821	01/31/2020	49892169/COAUD	010-401-42111		01/31/2020	1,200.00
WEST BLUFF EMERGENCY PH	135831	01/31/2020	ACCT#RAB206000/TC	010-401-42231		01/31/2020	32.34
DELL MARKETING L.P.	135800	01/31/2020	6789522/ TCSO & JPS	010-440-42101		01/31/2020	2,934.02
SYSTEM ACCESS	135818	01/31/2020	INV#1040/JP1	010-440-42353		01/31/2020	65.00
WEST BLUFF EMERGENCY PH	135826	01/31/2020	ACCT#10069553001ABO/TC	010-401-42231		01/31/2020	441.00
POLK COUNTY SHERIFF'S OFF	135811	01/31/2020	DEC 2019/TCSO	010-401-42231		01/31/2020	2,211.41
WEST BLUFF EMERGENCY PH	135825	01/31/2020	ACCT#1007044100ABO/TC	010-401-42231		01/31/2020	604.53
ALL NEEDZ DENTAL/WORSLE	135792	01/31/2020	INV#144279/TCSO	010-401-42231		01/31/2020	253.00
RISINGER, JAMES MICHAEL A	135814	01/31/2020	CAUSE NO 12923& 12922	010-408-42634		01/31/2020	1,500.00
CROSSIN MOVING & STORA	135797	12/31/2019	INV#1341/TAX	010-453-43152		12/31/2019	2,000.00
CROSSIN MOVING & STORA	135797	01/31/2020	INV#1341/TAX	010-453-43152		01/31/2020	500.00
MCDONOUGH, TIMOTHY R.	135810	01/31/2020	CAUSE NO 13435	010-408-42634		01/31/2020	450.00
WRIGHT, RUSSELL J.	135832	01/31/2020	CAUSE NO 13498	010-401-42628		01/31/2020	7,550.00
DAWSON, MARTHA	135799	01/31/2020	PER DIEM / JP1	010-411-42661		01/31/2020	150.00
GREGORY, DONECE	135806	01/31/2020	MILEAGE & PER DIEM / CO C	010-402-42659		01/31/2020	530.90

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
RIVERS, DEAN (GERALDINE)	135815	01/31/2020	PER DIEM / CO CLK	010-402-42659		01/31/2020	225.00
DAWSON, MARTHA	135799	01/31/2020	MILEAGE REIMB/NEW CLERK	010-411-42661		01/31/2020	220.80
LEAL-HUDSON, RACHEL ATTY	135809	01/31/2020	CAUSE NO 24908	010-408-42637		01/31/2020	697.50
POUNDS, CHYRL/DISTRICT CL	135812	01/31/2020	JURY MONEY / DSCLK	010-408-42700		01/31/2020	3,220.00
INDOFF OFFICE SUPPLIES	135808	01/31/2020	186597/ VET SRV	010-405-42100		01/31/2020	49.94
INDOFF OFFICE SUPPLIES	135808	01/31/2020	183748/MAINT	010-442-42106		01/31/2020	119.96
INDOFF OFFICE SUPPLIES	135808	01/31/2020	183747/COAUD	010-440-42101		01/31/2020	189.75
INDOFF OFFICE SUPPLIES	135808	01/31/2020	185084/TAX	010-421-42100		01/31/2020	41.99
INDOFF OFFICE SUPPLIES	135808	01/31/2020	185084/TAX	010-440-42101		01/31/2020	389.50
ABLES- LAND, INC.	135791	01/31/2020	INV#372014-0/COCLK	010-402-42100		01/31/2020	42.05
SAM HOUSTON STATE UNIVE	135817	01/31/2020	REGIS NEWLY ELECTED CONS	010-426-42659		01/31/2020	295.00
QUILL CORPORATION	135813	01/31/2020	6222074/TREAS	010-423-42100		01/31/2020	228.10
DIRECT SOLUTIONS	135801	01/31/2020	INV#49594/MAINT	010-442-42106		01/31/2020	83.21
DIRECT SOLUTIONS	135801	01/31/2020	INV#49730/ MAINT	010-442-42106		01/31/2020	923.44
DIRECT SOLUTIONS	135801	01/31/2020	INV#49828	010-442-42106		01/31/2020	87.94
TEXAS DOCUMENT SOLUTIO	135819	01/31/2020	997956/DSCLK	010-440-42350		01/31/2020	215.62
FEDEX	135802	01/31/2020	2212-3061-2/CDA	010-401-42111		01/31/2020	83.37
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086	010-442-42412		01/31/2020	155.00
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086/COCLK	010-442-42418		01/31/2020	67.00
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086/TAX OFFICES	010-442-42417		01/31/2020	67.00
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086/TC COMPLEX	010-442-42419		01/31/2020	100.00
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086/TCSO	010-442-42411		01/31/2020	75.00
WEST BLUFF EMERGENCY PH	135828	01/31/2020	100671098DVI/TCSO	010-401-42231		01/31/2020	98.98
WEST BLUFF EMERGENCY PH	135827	01/31/2020	ACCT#100672674DVI/TCSO	010-401-42231		01/31/2020	98.98
VERIZON WIRELESS	135823	01/31/2020	2033-00002/JP4	010-414-42500		01/31/2020	25.97
DELTA DENTAL	135781	01/30/2020	ADJUSTMENT/LEJUNE, DANA	010-401-40150		01/30/2020	-11.06
MASA Medical Transport Sol	135786	01/30/2020	ADJUSTMENT/LEJUNE, DANA	010-401-40150		01/30/2020	-7.00
WELLS, JOHN EARL III	135824	01/31/2020	CAUSE NO CR 13453	010-408-42634		01/31/2020	450.00
OFFICE OF THE A.G. CHILD S	DFT0002254	01/30/2020	CS	010-21300		01/30/2020	139.96
OFFICE OF THE A.G. CHILD S	DFT0002255	01/30/2020	CS	010-21300		01/30/2020	151.96
TYLER COUNTY PAYROLL	135788	01/30/2020	FICA	010-21300		01/30/2020	16.36
TYLER COUNTY PAYROLL	135788	01/30/2020	Medicare	010-21300		01/30/2020	3.82
TYLER COUNTY PAYROLL	135789	01/30/2020	PAYROLL TRANSFER	010-29999		01/30/2020	112.67
WRIGHT, RUSSELL J.	135832	01/31/2020	12235,633,13322,13,507 PR	010-401-42628		01/31/2020	1,850.00
TEXAS ASSOCIATION OF COU	135833	01/31/2020	2020 TAC DUES/ TYLER COU	010-422-42650		01/31/2020	325.00
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	010-21320		01/30/2020	17,697.45
TEXAS COUNTY & DISTRICT R	DFT0002257	01/30/2020	Tyler County, TX Retirement	010-21320		01/30/2020	18.33
CYPHER COMPUTERS	135845	02/07/2020	INV#0002259/CO OFFICE	010-440-42353		02/07/2020	975.00
TRANS UNION RISK AND ALT	135858	02/07/2020	3859110/TCSO	010-440-42350		02/07/2020	164.49
SYSTEM ACCESS	135855	02/07/2020	INV#1041/ JP 1	010-440-42353		02/07/2020	65.00
NARVAEZ, PAMMY	135849	02/07/2020	MILEAGE/PER DIEM	010-423-42659		02/07/2020	439.80
LEJUNE, DANA	135848	02/07/2020	REIMB/COAUD	010-401-40150		02/07/2020	74.12
RELIABLE COURT REPORTING	135852	02/07/2020	INV#20LK0115/COJUD	010-415-42635		02/07/2020	412.00
HATTON, DONNA	135863	02/06/2020	UNIFORM LOGOS/ COAUD	010-422-42150		02/06/2020	92.00

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
COLLINS, ANGELA	135844	02/07/2020	ELECTION WORK/ COCLK	010-401-42158		02/07/2020	400.00
SYSTEM ACCESS	135855	02/07/2020	INV#475/TCSO	010-440-42353		02/07/2020	130.00
VERIZON WIRELESS	135860	02/07/2020	3400-00001/TCSO	010-426-42500		02/07/2020	736.97
SYSTEM ACCESS	135855	02/07/2020	INV#CJ134/CO OFFICES	010-440-42353		02/07/2020	65.00
TAC HEALTH BENEFITS POOL	135835	02/06/2020	DEATON, BAILEY/ADJUSTME	010-401-40150		02/06/2020	-384.01
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LEJUNE, DANA/ADJUSTMENT	010-401-40150		02/06/2020	-384.01
TAC HEALTH BENEFITS POOL	135835	02/06/2020	NALLEY, GARRETT/ADJUSTM	010-401-40150		02/06/2020	-768.02
TAC HEALTH BENEFITS POOL	135835	02/06/2020	BROWN, JANET/ADJUSTMEN	010-401-40150		02/06/2020	-0.88
WILSON INSURANCE AGENC	135862	02/07/2020	NOTARY BOND/ MCGINTY, M	010-439-42100		02/07/2020	71.00
BANKNOTE CORPORATION O	135841	02/07/2020	153/COCLK	010-440-42101		02/07/2020	858.60
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	010-401-40150		02/06/2020	2,096.72
TAC HEALTH BENEFITS POOL	135835	02/06/2020	FREEMAN, ARTIE DALE/ADJU	010-401-40150		02/06/2020	6.80
TAC HEALTH BENEFITS POOL	135835	02/06/2020	ADJUSTMENT ON BILL	010-401-40150		02/06/2020	7.39
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LEJUNE, DANA/RETIREE	010-401-40150		02/06/2020	761.82
TAC HEALTH BENEFITS POOL	135835	02/06/2020	MURPHY, JOANNA/RETIREE	010-401-40150		02/06/2020	761.82
TEXAS DEPT. PARKS & WILDLI	135856	02/07/2020	TICKET#A8300728/ GAME W	010-401-42178		02/07/2020	157.25
CASHIER	135843	02/07/2020	PO # 30015/JP1	010-453-43210		02/07/2020	423.10
CITY OF WOODVILLE	135866	02/10/2020	01024002/TAX OFFICE	010-442-42517		02/10/2020	172.72
NEW WAVE COMMUNICATIO	135870	02/10/2020	127500668/TAX	010-440-42353		02/10/2020	141.98
WALLING SIGNS & GRAPHICS	135881	02/10/2020	SIGN/COCLK	010-401-42158		02/10/2020	36.00
CITY OF WOODVILLE	135866	02/10/2020	00001903/COCLK	010-442-42516		02/10/2020	34.00
CITY OF WOODVILLE	135866	02/10/2020	00002592/ANNEX2	010-442-42518		02/10/2020	183.71
CITY OF WOODVILLE	135866	02/10/2020	00002804/ANNEX	010-442-42518		02/10/2020	88.84
CITY OF WOODVILLE	135866	02/10/2020	05119001/JUSTICE CENTER	010-442-42511		02/10/2020	2,138.77
CITY OF WOODVILLE	135866	02/10/2020	07152002/ COURTHOUSE &	010-442-42515		02/10/2020	204.01
INDOFF OFFICE SUPPLIES	135869	02/10/2020	187474/DSCLK	010-440-42101		02/10/2020	614.99
DIRECTV	135867	02/10/2020	035535115/ NUTR CTR	010-440-42353		02/10/2020	166.99
TEXAS DOCUMENT SOLUTIO	135874	02/10/2020	681242/ JP1	010-440-42350		02/10/2020	88.06
TEXAS DOCUMENT SOLUTIO	135876	02/10/2020	1369625/ COMM OFFICES	010-440-42350		02/10/2020	90.65
TEXAS DOCUMENT SOLUTIO	135875	02/10/2020	997956/DSCLK	010-440-42353		02/10/2020	199.83
VERIZON WIRELESS	135878	02/10/2020	1963-00001/COAUD,PCT2,JP	010-419-42500		02/10/2020	80.26
VERIZON WIRELESS	135878	02/10/2020	1963-00001/COAUD,PCT2,JP	010-440-42101		02/10/2020	160.70
VERIZON WIRELESS	135878	02/10/2020	1963-00001/COAUD,PCT2,JP	010-440-42677		02/10/2020	80.26
SIRCHIE FINGERPRINT LABOR	135968	02/14/2020	00-A75979/TCSO	010-426-42182		02/14/2020	321.70
POLK COUNTY SHERIFF'S OFF	135951	02/14/2020	JAN 2020/TCSO	010-401-42231		02/14/2020	1,240.00
HARDIN COUNTY JAIL	135924	02/14/2020	JAN 2020/TCSO	010-401-42231		02/14/2020	1,240.00
A T & T PHONES - ATLANTA,	135894	02/14/2020	4545/DPS & VET SRV.	010-440-42350		02/14/2020	126.00
LAKEWAY TIRE & SERVICE-JA	135936	02/14/2020	1063/TCSO .	010-426-42400		02/14/2020	310.81
WEST BLUFF EMERGENCY PH	136001	02/14/2020	10071860001ABO/ TCSO	010-401-42231		02/14/2020	46.20
O'REILLY AUTOMOTIVE, INC.	135947	02/14/2020	596507/TCSO	010-426-42413		02/14/2020	72.99
WALLING SIGNS & GRAPHICS	135999	02/14/2020	TYCOJE/COJUD	010-442-42397		02/14/2020	30.00
TIMBERMAN'S SUPPLY	135986	02/14/2020	12032/MAINT.	010-442-42400		02/14/2020	220.45
U PUMP IT - GARDNER OIL	135994	02/14/2020	1910/MAINT.	010-442-42400		02/14/2020	45.97
U PUMP IT - GARDNER OIL	135994	02/14/2020	1920/TCSO	010-426-42400		02/14/2020	6,408.87

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
PARKER'S BUILDING SUPPLY -	135948	02/14/2020	22725/MAINT.	010-442-42419		02/14/2020	57.02
BROWN, TOMMY J. D.O.	135903	02/14/2020	CAUSEW NO 13498/ CDA	010-419-42222		02/14/2020	732.24
PELTIER, J.D.,MAUREEN	135949	02/14/2020	INV,#10038COJUD	010-401-42628		02/14/2020	987.50
DELL MARKETING L.P.	135916	02/14/2020	6789522/EOC & DPS	010-440-42101		02/14/2020	1,174.70
HARDIN COUNTY JAIL	135924	12/31/2019	NOV 2019/TCSO	010-401-42231		12/31/2019	920.00
HARDIN COUNTY JAIL	135924	12/31/2019	DEC 2019/TCSO	010-401-42231		12/31/2019	1,240.00
JEFFERSON COUNTY CLERK	135932	02/14/2020	CAUSE NO.122677/COJUD	010-415-42623		02/14/2020	457.00
WEST BLUFF EMERGENCY PH	136002	02/14/2020	10071840001ABO/TCSO	010-401-42231		02/14/2020	46.20
WRIGHT, RUSSELL J.	136004	02/14/2020	CAUSE NO 13292 MBB	010-408-42634		02/14/2020	400.00
VOTACALL, INC.	135998	02/14/2020	INV#132944/TAX	010-420-42500		02/14/2020	63.00
VOTACALL, INC.	135998	02/14/2020	INV#133631/ TAX	010-440-42350		02/14/2020	57.00
TYLER COUNTY CONSTRUCTI	135992	02/14/2020	INV#1475/COJUD	010-442-42412		02/14/2020	150.00
SHEFFIELD LANDSCAPING	135967	02/14/2020	INV#1510/COJUD	010-442-42397		02/14/2020	705.00
RATCLIFF, MICHAEL S., ATTY	135961	02/14/2020	CAUSE NO 17-249 DSAH	010-415-42634		02/14/2020	200.00
THE LABICHE ARCHITECTURA	135984	02/14/2020	INV#1902204/COJUD	010-442-42412		02/14/2020	90.00
TEXAS ASSOCIATION OF COU	135976	02/14/2020	INV#193757/TAX	010-420-42650		02/14/2020	125.00
ALLAN SHIVERS LIBRARY AN	135897	02/14/2020	1ST QTR/ COAUD	010-401-42649		02/14/2020	31,925.00
EAST TEXAS SUPPORT SERVI	135919	02/14/2020	1ST QTR 2020/ NUT CTR	010-401-42352		02/14/2020	3,750.00
NEW WAVE COMMUNICATIO	135944	02/14/2020	127316123/TCSO	010-440-42350		02/14/2020	163.10
NEW WAVE COMMUNICATIO	135945	02/14/2020	126541762/ COAUD	010-440-42350		02/14/2020	863.95
WALLING SIGNS & GRAPHICS	135999	02/14/2020	02/10/2020/ CO OFFICES	010-442-42417		02/14/2020	240.80
TRITECH FORENSICS	135990	02/14/2020	215817/TCSO	010-426-42182		02/14/2020	318.85
TEXAS ASSOCIATION OF COU	135973	02/14/2020	INV#237827/TAX	010-420-42650		02/14/2020	50.00
TEXAS ASSOCIATION OF COU	135975	02/14/2020	INV#241398/TAX	010-420-42650		02/14/2020	50.00
TEXAS ASSOCIATION OF COU	135977	02/14/2020	INV#242994/TAX	010-420-42650		02/14/2020	50.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 24314	010-408-42637		02/14/2020	37.50
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 24385	010-408-42637		02/14/2020	450.00
TEXAS ASSOCIATION OF COU	135974	02/14/2020	INV#246406/ TAX	010-420-42650		02/14/2020	50.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.24749	010-408-42637		02/14/2020	37.50
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 24785	010-408-42637		02/14/2020	90.00
HOLLIER, BONNIE	135926	02/14/2020	CAUSE NO 24785	010-408-42637		02/14/2020	75.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.24785	010-408-42637		02/14/2020	75.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 24809	010-408-42637		02/14/2020	262.50
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.24894	010-408-42637		02/14/2020	75.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 24897	010-408-42637		02/14/2020	302.50
HOLLIER, BONNIE	135926	02/14/2020	CAUSE NO 24897	010-408-42637		02/14/2020	272.03
THE PRINTERY	135985	02/14/2020	INV#24916/COAUD	010-440-42101		02/14/2020	334.54
HOLLIER, BONNIE	135926	02/14/2020	CAUSE NO 24939	010-408-42637		02/14/2020	500.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 24939	010-408-42637		02/14/2020	75.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.24992	010-408-42637		02/14/2020	112.50
TEXAS ASSOCIATION OF COU	135978	02/14/2020	INV#249971/TAX	010-420-42650		02/14/2020	50.00
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25045	010-408-42637		02/14/2020	157.50
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.25004	010-408-42637		02/14/2020	337.50
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25022	010-408-42637		02/14/2020	82.50

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.25022	010-408-42637		02/14/2020	75.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.25034	010-408-42637		02/14/2020	187.50
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25034	010-408-42637		02/14/2020	232.50
HOLLIER, BONNIE	135926	02/14/2020	CAUSE NO 25045	010-408-42637		02/14/2020	225.00
KEATING, DUANE F. ATTORN	135934	02/14/2020	CAUSE NO 25045	010-408-42637		02/14/2020	187.50
KEATING, DUANE F. ATTORN	135934	02/14/2020	CAUSE NO 25048	010-408-42637		02/14/2020	195.00
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25088	010-408-42637		02/14/2020	157.50
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 25100	010-408-42637		02/14/2020	562.50
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25114	010-408-42637		02/14/2020	180.00
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO.25114	010-408-42637		02/14/2020	93.75
KEATING, DUANE F. ATTORN	135934	02/14/2020	CAUSE NO 25127	010-408-42637		02/14/2020	82.50
KEATING, DUANE F. ATTORN	135934	02/14/2020	CAUSE NO 25133	010-408-42637		02/14/2020	172.50
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25144	010-408-42637		02/14/2020	285.00
MANN, ROBERT H. ATTY.	135939	02/14/2020	CAUSE NO 25263	010-408-42637		02/14/2020	307.50
BYTHEWOOD LEGAL SERVICE	135904	02/14/2020	CAUSE NO 25263	010-408-42637		02/14/2020	225.00
HOLLIER, BONNIE	135926	02/14/2020	CAUSE NO 25263	010-408-42637		02/14/2020	281.25
REGION 10 CTAT	135962	02/14/2020	MEMBERSHIP DUES / TREAS	010-423-42650		02/14/2020	25.00
TEXAS ASSOCIATION OF COU	135980	02/14/2020	250108/COCLK	010-402-42659		02/14/2020	125.00
TEXAS ASSOCIATION OF COU	135982	02/14/2020	252129/COCLK	010-402-42659		02/14/2020	125.00
INDOFF OFFICE SUPPLIES	135928	02/14/2020	183750/COCLK	010-440-42101		02/14/2020	221.99
INDOFF OFFICE SUPPLIES	135928	02/14/2020	183747/COAUD	010-440-42101		02/14/2020	151.80
BEN E.KEITH FOODS	135901	02/14/2020	781863/TCSO	010-427-42157		02/14/2020	5,281.87
ABLES-LAND, INC.	135896	02/14/2020	INV#373799-0/TCSO	010-440-42101		02/14/2020	189.99
QUILL CORPORATION	135954	02/14/2020	6076298/CSCD	010-420-42100		02/14/2020	24.36
QUILL CORPORATION	135953	02/14/2020	6076298/CSCD	010-420-42100		02/14/2020	91.99
QUILL CORPORATION	135957	02/14/2020	5421407/DPS	010-430-42100		02/14/2020	134.64
QUILL CORPORATION	135956	02/14/2020	6076298/TAX	010-420-42100		02/14/2020	43.98
DIRECT SOLUTIONS	135917	02/14/2020	INV.#49594,49730,49828/M	010-442-42106		02/14/2020	1,094.59
DIRECT SOLUTIONS	135917	02/14/2020	INV#49717/ TCSO	010-427-42108		02/14/2020	2,610.22
INNOVATIVE LEASING	135929	02/14/2020	603-0130197-000/TAX	010-440-42677		02/14/2020	867.99
TOLAR'S FEED & OUTDOOR S	135988	02/14/2020	INV.#639338/MAINT.	010-442-42397		02/14/2020	47.80
TEXAS ASSOCIATION OF COU	135981	02/14/2020	249751/TREAS.	010-423-42650		02/14/2020	25.00
TEXAS DOCUMENT SOLUTIO	135983	02/14/2020	997956/DSCLK	010-440-42350		02/14/2020	233.38
CLINICAL SOLUTIONS	135908	02/14/2020	INV.#68712/TCSO	010-401-42231		02/14/2020	710.56
VERIZON WIRELESS	135996	02/14/2020	3400-0001/TCSO	010-426-42500		02/14/2020	736.97
VERIZON WIRELESS	135995	02/14/2020	3400-00002/TREAS	010-440-42350		02/14/2020	37.99
SOUTHERN HEALTH PARTNE	135970	02/14/2020	TYL-7353/TCSO	010-401-42231		02/14/2020	6,858.32
TYLER COUNTY PAYROLL	135885	02/10/2020	FICA	010-21300		02/10/2020	-169.84
TYLER COUNTY PAYROLL	135885	02/10/2020	Federal Withholding	010-21300		02/10/2020	-102.60
TYLER COUNTY PAYROLL	135885	02/10/2020	Medicare	010-21300		02/10/2020	-39.72
TYLER COUNTY SOFTBALL AS	135993	02/14/2020	REIMBURSEMENT/ TCYS	010-401-42204		02/14/2020	6,000.00
PILGRIM INSURANCE	135950	02/14/2020	BOND#68998376/TAX	010-420-42900		02/14/2020	117.50
TEXAS ASSOCIATION OF COU	135979	02/14/2020	ASSOC DUES / KNIGHT, RHO	010-420-42650		02/14/2020	50.00
CHESTER VOLUNTEER FIRE D	135906	02/14/2020	Monthly Allowance	010-401-42701		02/14/2020	150.00

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
SHADY GROVE VOLUNTEER F	135966	02/14/2020	Monthly Allowance	010-401-42701		02/14/2020	150.00
WOODVILLE VOLUNTEER FIR	136003	02/14/2020	Monthly Allowance	010-401-42701		02/14/2020	150.00
NATIONWIDE RETIREMENT S	135889	02/13/2020	Deferred Comp	010-21300		02/13/2020	62.50
TYLER COUNTY TAX ASSESSO	135891	02/13/2020	Tyler County Property Tax	010-21300		02/13/2020	100.00
US DEPARTMENT OF EDUCAT	135892	02/13/2020	STUDENT LOAN	010-21300		02/13/2020	280.91
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	010-21300		02/13/2020	14,638.72
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	010-21300		02/13/2020	9,146.43
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	010-21300		02/13/2020	3,423.64
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	010-29999		02/12/2020	87,348.38
CANDY CLEANERS	135905	02/14/2020	JAN 2020/TCSO	010-426-42150		02/14/2020	392.11
SULLIVAN'S HARDWARE	135972	02/14/2020	JAN 2020	010-427-42108		02/14/2020	30.73
SULLIVAN'S HARDWARE	135972	02/14/2020	JAN 2020	010-442-42412		02/14/2020	59.84
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	010-401-42500		02/14/2020	2,730.57
SPIVEY, JACOB	135971	02/14/2020	MILEAGE & REIMB./AG.EXT.	010-439-42224		02/14/2020	897.00
HARDIN COUNTY JAIL	135924	12/31/2019	PRESCRIPTIONS/ TCSO	010-401-42231		12/31/2019	22.77
COUNTY INFORMATION RES	135914	02/14/2020	INV#SOP011920/COJUD	010-440-42600		02/14/2020	317.00
COUNTY INFORMATION RES	135914	02/14/2020	INV#SOP012038/COJUD	010-440-42600		02/14/2020	800.00
ICS JAIL SUPPLIES INC.	135927	02/14/2020	W34326-00/TCSO	010-427-42108		02/14/2020	1,161.79
JASPER COUNTY	136016	02/14/2020	JAN 2020/ TCSO	010-401-42231		02/14/2020	5,861.93
ENTERGY	136006	02/13/2020	133941435/TCSO	010-442-42511		02/13/2020	47.93
LAKEWAY TIRE & SERVICE-JA	136019	02/14/2020	1/26/2020-TYLER CO MAINT	010-442-42413		02/14/2020	7.00
BROOKSHIRE BRO. FOOD & P	136009	02/14/2020	18005/TCSO	010-427-42157		02/14/2020	69.00
PITNEY BOWES - PURCHASE	136025	02/14/2020	8000-9090-0771-2750	010-401-42111		02/14/2020	2,017.51
KEATING, DUANE F. ATTORN	136018	02/14/2020	CAUSE NO 24886	010-408-42637		02/14/2020	37.50
MANN, ROBERT H. ATTY.	136021	02/14/2020	CAUSE NO 24992	010-408-42637		02/14/2020	742.50
MCPHERSON, MICHELLE	136023	02/14/2020	CAUSE NO 24992	010-408-42637		02/14/2020	457.50
KEATING, DUANE F. ATTORN	136018	02/14/2020	CAUSE NO 25114	010-408-42637		02/14/2020	180.00
KEATING, DUANE F. ATTORN	136018	02/14/2020	CAUSE NO 25127	010-408-42637		02/14/2020	97.50
KEATING, DUANE F. ATTORN	136018	02/14/2020	CAUSE NO 25133	010-408-42637		02/14/2020	960.00
MCPHERSON, MICHELLE	136023	02/14/2020	CAUSE NO 25045	010-408-42637		02/14/2020	292.50
TYLER COUNTY TAX OFFICE	136036	02/13/2020	REFUND OF BOAT AND MOT	010-32103		02/13/2020	2,185.01
TYLER COUNTY BOOSTER	136033	02/14/2020	INV#29657/TCSO	010-401-42616		02/14/2020	156.75
INDOFF OFFICE SUPPLIES	136015	02/14/2020	185596/CDA	010-419-42100		02/14/2020	510.11
INDOFF OFFICE SUPPLIES	136035	02/14/2020	185596/ CDA	010-419-42100		02/14/2020	171.96
LANGFORD COMMUNITY M	136020	02/14/2020	INV#3923/COAUD	010-401-42178		02/14/2020	4,005.00
QUILL CORPORATION	136028	02/14/2020	6222074/TREAS	010-440-42101		02/14/2020	695.96
QUILL CORPORATION	136026	02/14/2020	6222074/TREAS	010-440-42101		02/14/2020	347.98
QUILL CORPORATION	136027	02/14/2020	6222074/TREAS	010-423-42100		02/14/2020	61.98
QUILL CORPORATION	136027	02/14/2020	6222074/TREAS	010-440-42101		02/14/2020	355.98
SOUTHERN HEALTH PARTNE	136030	02/14/2020	TYL-7353/TCSO	010-401-42231		02/14/2020	41.85
MODICA BROS.	136005	02/13/2020	CREDIT FOR OVER PAYMENT/	010-426-42400		02/13/2020	-217.79
MODICA BROS.	136005	02/13/2020	CREDIT FOR OVER PAYMENT/	010-426-42401		02/13/2020	-766.98
HARRIS REPORTING SERVICE	136013	02/14/2020	JOB NO GH19028	010-408-42638		02/14/2020	400.00
OFFICE OF THE A.G. CHILD S	DFT0002262	02/13/2020	CS	010-21300		02/13/2020	139.96

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
OFFICE OF THE A.G. CHILD S	DFT0002263	02/13/2020	CS	010-21300		02/13/2020	151.96
MODICA BROS.	136005	02/13/2020	JAN2020/TCSO	010-426-42400		02/13/2020	62.45
MODICA BROS.	136005	02/13/2020	JAN2020/TCSO	010-426-42401		02/13/2020	948.30
MODICA BROS.	136005	02/13/2020	JAN2020/TCSO	010-426-42413		02/13/2020	679.27
CYPHER COMPUTERS	136037	02/14/2020	INV#0002261/ CO OFFICES	010-440-42353		02/14/2020	520.00
QUILL CORPORATION	136039	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	78.98
QUILL CORPORATION	136041	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	209.95
QUILL CORPORATION	136048	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	17.48
QUILL CORPORATION	136053	12/31/2019	6076298/TAX	010-440-42101		12/31/2019	172.97
QUILL CORPORATION	136043	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	8.58
QUILL CORPORATION	136052	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	43.86
QUILL CORPORATION	136047	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	34.99
QUILL CORPORATION	136047	12/31/2019	6076298/TAX	010-442-42106		12/31/2019	23.18
QUILL CORPORATION	136051	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	92.33
QUILL CORPORATION	136040	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	89.95
QUILL CORPORATION	136049	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	44.98
QUILL CORPORATION	136046	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	36.98
QUILL CORPORATION	136042	02/18/2020	6076298/TAX	010-440-42101		02/18/2020	299.95
QUILL CORPORATION	136050	02/18/2020	6076298/TAX	010-420-42100		02/18/2020	26.42
QUILL CORPORATION	136045	02/18/2020	6076298/TAX	010-420-42100		02/18/2020	39.97
QUILL CORPORATION	136044	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	29.48
QUILL CORPORATION	136038	12/31/2019	6076298/TAX	010-420-42100		12/31/2019	32.98
TEXAS COUNTY & DISTRICT R	DFT0002259	02/10/2020	Tyler County, TX Retirement	010-21320		02/10/2020	-190.26
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	010-21320		02/13/2020	16,704.76
Fund 010 - GENERAL FUND Total:							448,279.35

Fund: 021 - ROAD & BRIDGE I

BIG TEX TRAILER WORLD	135759	01/27/2020	INV.#22255/PCT1	021-000-43200		01/27/2020	10,512.00
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	021-000-42425		01/28/2020	184.45
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	021-21300		01/30/2020	1,595.62
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	021-21300		01/30/2020	1,157.01
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	021-21300		01/30/2020	373.18
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	021-29999		01/29/2020	9,835.53
ARD, MELINDA	135794	01/31/2020	CLEANING PCT 1 BARN	021-000-42998		01/31/2020	250.00
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	021-21320		01/30/2020	1,768.14
JR'S TRUCKING , HEAVY EQUI	135847	02/07/2020	INV#17256/PCT 1	021-000-42425		02/07/2020	458.99
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	021-000-40120		02/06/2020	193.61
SENECA WATER SUPPLY CORP	135873	02/10/2020	166/ PCT 1 BARN	021-000-42510		02/10/2020	41.21
VERIZON WIRELESS	135879	02/10/2020	6997-00002/PCT 1	021-000-42500		02/10/2020	211.27
LOCAL SANITATION, LLC	135938	02/14/2020	3423/PCT 1	021-000-42510		02/14/2020	60.00
LAKEWAY TIRE & SERVICE-JA	135936	02/14/2020	TYLER CO PCT 1	021-000-42401		02/14/2020	44.90
O'REILLY AUTOMOTIVE, INC.	135947	02/14/2020	591681/PCT 1	021-000-42425		02/14/2020	116.06
TIMBERMAN'S SUPPLY	135986	02/14/2020	12023/ PCT 1	021-000-42425		02/14/2020	150.73
GARDNER OIL, INC.	135921	02/14/2020	1638/ PCT 1	021-000-42400		02/14/2020	1,676.39

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
U PUMP IT - GARDNER OIL	135994	02/14/2020	1914/PCT 1	021-000-42400		02/14/2020	369.79
PARKER'S BUILDING SUPPLY -	135948	02/14/2020	22700/PCT 1	021-000-42425		02/14/2020	188.91
LAKES AREA SEPTIC & SLUDG	135935	02/14/2020	INV#25702/PCT1	021-000-42510		02/14/2020	60.00
LAKES AREA SEPTIC & SLUDG	135935	02/14/2020	INV#25749/PCT.1	021-000-42510		02/14/2020	60.00
INDOFF OFFICE SUPPLIES	135928	02/14/2020	INV#3331759/ PCT 1	021-000-42998		02/14/2020	113.96
BLUE TARP FINANCIAL/NORT	135902	02/14/2020	123728/PCT 1	021-000-42425		02/14/2020	169.96
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	021-21300		02/13/2020	1,573.74
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	021-21300		02/13/2020	1,133.24
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	021-21300		02/13/2020	368.04
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	021-29999		02/12/2020	9,474.83
EAST TEXAS ASPHALT CO.	135918	02/14/2020	TRC1/PCT1	021-000-42160		02/14/2020	1,081.20
EAST TEXAS ASPHALT CO.	135918	02/14/2020	TRC1/PCT 1	021-000-42160		02/14/2020	1,100.58
MODICA BROS.	135940	02/14/2020	JAN 2020/PCT 1	021-000-42401		02/14/2020	10.02
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	021-000-42500		02/14/2020	9.44
WALMART COMMUNITY/GE	136000	02/14/2020	5379/PCT.1	021-000-42998		02/14/2020	56.74
BEAUMONT TRACTOR COMP	135900	02/14/2020	TYLEOO/PCT1	021-000-42425		02/14/2020	2,990.00
ENTERGY	136006	02/13/2020	133941435/PCT.1	021-000-42150		02/13/2020	186.83
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	021-21320		02/13/2020	1,812.10

Fund 021 - ROAD & BRIDGE I Total: 49,388.47

Fund: 022 - ROAD & BRIDGE II

CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	022-000-42425		01/28/2020	41.88
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	022-000-42998		01/28/2020	120.44
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	022-21300		01/30/2020	1,306.68
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	022-21300		01/30/2020	902.63
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	022-21300		01/30/2020	305.60
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	022-29999		01/29/2020	8,101.10
UNIFIRST HOLDING, INC.	135822	01/31/2020	1526777/PCT2	022-000-42150		01/31/2020	61.83
HUGHES DOZER & DUMP TR	135807	01/31/2020	INV#869258,869259,869260	022-000-42160		01/31/2020	4,121.80
ARD, MELINDA	135794	01/31/2020	CLEANING PCT 2 BARN	022-000-42998		01/31/2020	187.50
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	022-21320		01/30/2020	1,444.46
STURROCK, STEVAN	135854	02/07/2020	MILEAGE/ PER DIEM	022-000-42659		02/07/2020	347.00
WALMART COMMUNITY/GE	135861	02/07/2020	5557/PCT 2	022-000-42998		02/07/2020	23.89
JR'S TRUCKING , HEAVY EQUI	135847	02/07/2020	INV#17291/ PCT 2	022-000-42425		02/07/2020	3,028.91
JR'S TRUCKING , HEAVY EQUI	135847	02/07/2020	INV#17297/PCT 2	022-000-42425		02/07/2020	450.00
UNIFIRST HOLDING, INC.	135859	02/10/2020	945626/PCT2	022-000-42150		02/10/2020	61.83
UNIFIRST HOLDING, INC.	135859	02/07/2020	1526777/PCT 2	022-000-42150		02/07/2020	51.52
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	022-000-40120		02/06/2020	212.80
CHESTER GAS SYSTEM	135864	02/10/2020	134/PCT 2 BARN	022-000-42510		02/10/2020	99.03
CHESTER WATER SUPPLY CO	135865	02/10/2020	31/PCT 2 BARN	022-000-42510		02/10/2020	20.10
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	1833151/PCT 2	022-000-42510		02/10/2020	95.32
EASTEX TELEPHONE COOP., I	135868	02/10/2020	70024893/PCT 2	022-000-42500		02/10/2020	40.41
VERIZON WIRELESS	135878	02/10/2020	1963-00001/COAUD,PCT2,,JP	022-000-42500		02/10/2020	120.39
GEO. P. BANE, INC.	135922	02/14/2020	91529M/ PCT 2	022-000-43200		02/14/2020	2,504.09

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
LOCAL SANITATION, LLC	135938	02/14/2020	2015/PCT 2	022-000-42510		02/14/2020	60.00
TRACTOR SUPPLY CREDIT PL	135989	02/14/2020	6035-3012-0347-0107/PCT.2	022-000-42998		02/14/2020	704.90
O'REILLY AUTOMOTIVE, INC.	135947	02/14/2020	591682/PCT.2	022-000-42425		02/14/2020	15.39
TIMBERMAN'S SUPPLY	135986	02/14/2020	12024/PCT 2	022-000-42425		02/14/2020	1,642.20
TIMBERMAN'S SUPPLY	135986	02/14/2020	12024/PCT 2	022-000-42998		02/14/2020	734.22
GARDNER OIL, INC.	135921	02/14/2020	1639/PCT 2	022-000-42400		02/14/2020	3,618.75
U PUMP IT - GARDNER OIL	135994	02/14/2020	1918/PCT 2	022-000-42400		02/14/2020	1,186.09
PARKER'S BUILDING SUPPLY -	135948	02/14/2020	22705/PCT.2	022-000-42998		02/14/2020	1,238.18
COASTAL WELDING SUPPLY	135912	02/14/2020	30355/PCT 2	022-000-42998		02/14/2020	140.20
RURAL PIPE & SUPPLY	135964	02/14/2020	TYLCO2/PCT 2	022-000-42161		02/14/2020	4,135.60
GULF COAST	135923	02/14/2020	210161/PCT 2	022-000-42160		02/14/2020	1,527.12
GULF COAST	135923	02/14/2020	210161/PCT.2	022-000-42160		02/14/2020	1,533.92
ROBBINS HEAVY HAUL	135963	02/14/2020	MOVED MAINTAINER/ PCT 2	022-000-42425		02/14/2020	400.00
TOLAR'S FEED & OUTDOOR S	135988	02/14/2020	INV#639541/PCT 2	022-000-42998		02/14/2020	83.70
COASTAL WELDING SUPPLY	135910	02/14/2020	30355/ PCT 2	022-000-42425		02/14/2020	119.35
ATTOYAC ROCK, LLC	135899	02/14/2020	INV#8282/PCT 2	022-000-42160		02/14/2020	1,217.87
ATTOYAC ROCK, LLC	135899	02/14/2020	INV#8294/ PCT 2	022-000-42160		02/14/2020	541.75
ATTOYAC ROCK, LLC	135899	02/14/2020	INV#8317/PCT 2	022-000-42160		02/14/2020	1,585.88
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	022-21300		02/13/2020	1,229.66
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	022-21300		02/13/2020	822.62
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	022-21300		02/13/2020	287.62
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	022-29999		02/12/2020	7,486.53
MODICA BROS.	135940	02/14/2020	JAN 2020/ PCT 2	022-000-42401		02/14/2020	39.40
SULLIVAN'S HARDWARE	135972	02/14/2020	JAN 2020/ PCT 2	022-000-42998		02/14/2020	39.96
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	022-000-42500		02/14/2020	9.43
MUSTANG CAT	135942	02/14/2020	0792910/PCT 2	022-000-42425		02/14/2020	11.54
MUSTANG RENTAL SERVICES	135943	02/14/2020	598085/PCT 2	022-000-43200		02/14/2020	1,216.89
EAST TEXAS MACHINE	136012	02/14/2020	INV#35280/ PCT 2	022-000-42425		02/14/2020	340.00
UNIFIRST HOLDING, INC.	136034	02/14/2020	1526777/PCT 2	022-000-42150		02/14/2020	63.33
UNIFIRST HOLDING, INC.	136034	02/14/2020	1526777/PCT 2	022-000-42150		02/14/2020	63.33
ATTOYAC ROCK, LLC	136008	02/14/2020	197/PCT 2	022-000-42160		02/14/2020	600.84
CONSOLIDATED COMMUNIC	136011	02/14/2020	2645/O-PCT 2	022-000-42500		02/14/2020	23.12
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	022-21320		02/13/2020	1,390.27
Fund 022 - ROAD & BRIDGE II Total:							57,758.87
Fund: 023 - ROAD & BRIDGE III							
JACK ALEXANDER, LTD.	135760	01/27/2020	TYLCO3/PCT3	023-000-42160		01/27/2020	490.80
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	023-21300		01/30/2020	2,208.40
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	023-21300		01/30/2020	1,077.64
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	023-21300		01/30/2020	516.52
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	023-29999		01/29/2020	14,213.10
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	023-21320		01/30/2020	2,295.39
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	023-000-40120		02/06/2020	228.73
WINDSTREAM	135882	02/10/2020	1-2020/5237	023-000-42500		02/10/2020	179.58

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
VERIZON WIRELESS	135880	02/10/2020	6997-00003/PCT 3	023-000-42500		02/10/2020	110.56
LOCAL SANITATION, LLC	135938	02/14/2020	3299/ PCT 3	023-000-42510		02/14/2020	120.00
SEXTON, MATTIE M.	135965	02/14/2020	CLEANING PCT 3 BARN	023-000-42998		02/14/2020	45.00
LAKEWAY TIRE & SERVICE-JA	135936	02/14/2020	917/PCT3	023-000-42401		02/14/2020	114.92
TIMBERMAN'S SUPPLY	135986	02/14/2020	12025/PCT 3	023-000-42998		02/14/2020	19.95
GARDNER OIL, INC.	135921	02/14/2020	1640/PCT 3	023-000-42400		02/14/2020	5,717.50
COASTAL WELDING SUPPLY	135911	02/14/2020	30416/PCT 3	023-000-42425		02/14/2020	77.70
COASTAL WELDING SUPPLY	135909	02/14/2020	10358151	023-000-42425		02/14/2020	71.80
DEBBIE'S HARDWARE	135915	02/14/2020	INV#16606	023-000-42425		02/14/2020	33.06
SEXTON, MATTIE M.	135965	02/14/2020	CLEANING PCT 3 BARN	023-000-42998		02/14/2020	45.00
JACK ALEXANDER, LTD.	135931	02/14/2020	TYLCO3/PCT3	023-000-42160		02/14/2020	792.45
INDOFF OFFICE SUPPLIES	135928	02/14/2020	375204/ PCT 3 & 4	023-000-42998		02/14/2020	10.00
CINTAS CORPORATION #048	135907	02/14/2020	10698531/PCT.3	023-000-42998		02/14/2020	84.19
TOLAR'S FEED & OUTDOOR S	135988	02/14/2020	INV#638025,638849,639441	023-000-42998		02/14/2020	149.85
ATTOYAC ROCK, LLC	135899	02/14/2020	153/PCT 3	023-000-42160		02/14/2020	3,815.89
ATTOYAC ROCK, LLC	135899	02/14/2020	153/PCT 3	023-000-42160		02/14/2020	3,174.47
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	023-21300		02/13/2020	2,386.16
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	023-21300		02/13/2020	1,225.47
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	023-21300		02/13/2020	558.06
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	023-29999		02/12/2020	15,218.70
POWERPLAN/DOGGETT MA	135952	02/14/2020	8850494392/PCT 3	023-000-42425		02/14/2020	6,015.05
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	023-000-42500		02/14/2020	9.43
INTERSTATE BILLING SERVICE	135930	02/14/2020	120677/PCT 3	023-000-42425		02/14/2020	440.74
ENTERGY	136006	02/13/2020	133941435/PCT.3	023-000-42510		02/13/2020	209.17
JR'S TRUCKING , HEAVY EQUI	136017	02/14/2020	INV#17308/ PCT 3	023-000-42425		02/14/2020	491.98
COASTAL WELDING SUPPLY	136010	02/14/2020	30416/PCT 3	023-000-42425		02/14/2020	95.00
ATTOYAC ROCK, LLC	136008	02/14/2020	153/PCT 3	023-000-42160		02/14/2020	3,108.64
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	023-21320		02/13/2020	2,534.56
Fund 023 - ROAD & BRIDGE III Total:							67,885.46
Fund: 024 - ROAD & BRIDGE IV							
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	024-000-42998		01/28/2020	31.95
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	024-21300		01/30/2020	1,614.14
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	024-21300		01/30/2020	965.91
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	024-21300		01/30/2020	377.54
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	024-29999		01/29/2020	10,159.02
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	024-21320		01/30/2020	1,779.28
ALLIED FENCE COMPANY	135834	12/31/2019	FENCE @ PCT 4 BARN	024-000-16900		12/31/2019	7,355.00
SHIRLEY, J.P.	135853	02/07/2020	PCT 4 BARN/PCT 4	024-000-43605		02/07/2020	3,390.59
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	024-000-40120		02/06/2020	250.93
TYLER COUNTY WATER SUPP	135877	02/10/2020	00583/PCT 4 BARN	024-000-42510		02/10/2020	30.82
LOCAL SANITATION, LLC	135938	02/14/2020	3365/ PCT 4	024-000-42510		02/14/2020	120.00
TIMBERMAN'S SUPPLY	135986	02/14/2020	12026/PCT 4	024-000-42425		02/14/2020	298.18
TMS INTERNATIONAL, LLC.	135987	02/14/2020	CO4558/PCT4	024-000-42160		02/14/2020	576.61

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
GARDNER OIL, INC.	135921	02/14/2020	1641/PCT 4	024-000-42400		02/14/2020	3,318.00
U PUMP IT - GARDNER OIL	135994	02/14/2020	1916/PCT 4	024-000-42400		02/14/2020	205.28
KAT EXCAVATION & CONSTR	135933	02/14/2020	INV#211461/ PCT 4	024-000-42160		02/14/2020	1,452.97
KAT EXCAVATION & CONSTR	135933	02/14/2020	INV#211513/PCT4	024-000-42160		02/14/2020	2,204.10
INDOFF OFFICE SUPPLIES	135928	02/14/2020	375204/ PCT 3 & 4	024-000-42998		02/14/2020	10.06
MOTT WHOLESALE, INC.	135941	02/14/2020	INV#465992/PCT4	024-000-42425		02/14/2020	758.03
TYCO GENERAL FEED & RAN	135991	02/14/2020	INV#532364/ PCT 4	024-000-42150		02/14/2020	1,044.00
VERIZON WIRELESS	135997	02/14/2020	5093-00001/PCT 4	024-000-42500		02/14/2020	26.37
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	024-21300		02/13/2020	1,727.96
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	024-21300		02/13/2020	1,030.78
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	024-21300		02/13/2020	404.12
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	024-29999		02/12/2020	10,588.30
SMART'S TRUCK & TRAILER E	135969	02/14/2020	INV#IW	024-000-42425		02/14/2020	140.49
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	024-000-42500		02/14/2020	9.43
ENTERGY	136006	02/13/2020	133941435/PCT.4 BARN	024-000-42510		02/13/2020	53.82
MARTIN CONSTRUCTION	136022	02/14/2020	INV#100/PCT 4	024-000-43605		02/14/2020	4,800.00
SHIRLEY, J.P.	136029	02/14/2020	LABOR/ MATERIALS - PCT 4 B	024-000-43605		02/14/2020	8,495.34
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	024-21320		02/13/2020	1,931.33
Fund 024 - ROAD & BRIDGE IV Total:							65,150.35
Fund: 025 - TYLER CO AIRPORT							
CRUSE, LYNNETTE/TYLER CO	135780	01/29/2020	AIRPORT HANGER / 2019 TA	025-000-43202		01/29/2020	1,692.29
ARD, MELINDA	135794	01/31/2020	CLEANING AIRPORT	025-000-42410		01/31/2020	80.00
SAM HOUSTON ELECTRIC CO	135816	01/31/2020	2782325/AIRPORT	025-000-42510		01/31/2020	24.60
SAM HOUSTON ELECTRIC CO	135816	01/31/2020	2708881/AIRPORT	025-000-42510		01/31/2020	20.50
CITY OF WOODVILLE	135866	02/10/2020	00002090/AIRPORT	025-000-42510		02/10/2020	25.00
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	342683/AIRPORT	025-000-42510		02/10/2020	20.98
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	35055/ AIRPORT	025-000-42510		02/10/2020	119.58
Fund 025 - TYLER CO AIRPORT Total:							1,982.95
Fund: 026 - TYLER CO. RODEO ARENA/FAIRGRND							
CITY OF WOODVILLE	135866	02/10/2020	00002496/RODEO ARENA	026-000-42510		02/10/2020	0.56
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	1313576/RODEO ARENA	026-000-42510		02/10/2020	30.70
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	140061/RODEO ARENA	026-000-42510		02/10/2020	163.58
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	1807510/RODEO ARENA	026-000-42510		02/10/2020	20.50
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	1807528/RODEO ARENA	026-000-42510		02/10/2020	20.50
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	2749173/ RODEO ARENA	026-000-42510		02/10/2020	32.29
SAM HOUSTON ELECTRIC CO	135872	02/10/2020	55988/ RODEO ARENA	026-000-42510		02/10/2020	51.40
Fund 026 - TYLER CO. RODEO ARENA/FAIRGRND Total:							319.53
Fund: 031 - COUNTY CLERK RMP							
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	031-21300		01/30/2020	75.64
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	031-21300		01/30/2020	17.70
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	031-29999		01/29/2020	520.63
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	031-21320		01/30/2020	84.73
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	031-21300		02/13/2020	94.24

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	031-21300		02/13/2020	22.04
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	031-29999		02/12/2020	648.66
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	031-21320		02/13/2020	105.56
Fund 031 - COUNTY CLERK RMP Total:							1,569.20
Fund: 036 - LIBRARY FUND							
THOMSON REUTERS - WEST	135820	01/31/2020	1000705398/CDA	036-000-48007		01/31/2020	222.00
THOMSON REUTERS - WEST	135857	02/07/2020	1002036909/TREAS	036-000-48007		02/07/2020	77.00
LEXIS NEXIS	135937	02/14/2020	422MPTRMW/COJUD	036-000-48007		02/14/2020	333.66
THOMSON REUTERS - WEST	136031	02/14/2020	1000705398/CDA	036-000-48007		02/14/2020	393.23
Fund 036 - LIBRARY FUND Total:							1,025.89
Fund: 039 - TXCDBG SMALL BUSINESS LOAN PRJ							
TEXAS DEPT. OF AGRICULTUR	1113	01/29/2020	CONTRACT NO. 726192 TYLE	039-000-44300		01/29/2020	557.50
Fund 039 - TXCDBG SMALL BUSINESS LOAN PRJ Total:							557.50
Fund: 044 - COURTHOUSE SECURITY							
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	044-21300		01/30/2020	155.14
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	044-21300		01/30/2020	127.10
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	044-21300		01/30/2020	36.28
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	044-29999		01/29/2020	942.69
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	044-21320		01/30/2020	169.71
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	044-21300		02/13/2020	125.94
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	044-21300		02/13/2020	118.41
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	044-21300		02/13/2020	29.46
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	044-29999		02/12/2020	750.09
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	044-21320		02/13/2020	137.87
Fund 044 - COURTHOUSE SECURITY Total:							2,592.69
Fund: 053 - ADULT PROBATION							
CARD SERVICE CENTER/MAS	135761	01/28/2020	DEC.2019-JAN.2020/0321	053-461-42664		01/28/2020	178.63
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	053-21300		01/30/2020	1,121.48
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	053-21300		01/30/2020	435.10
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	053-21300		01/30/2020	262.26
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	053-29999		01/29/2020	7,284.05
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	053-21320		01/30/2020	1,256.23
BELT HARRIS PECHACEK, LLP	135842	02/07/2020	INV#14290/ ADULT PROB	053-000-42602		02/07/2020	7,700.00
O'NEAL, MATT	135851	02/07/2020	PER DIEM / CSCD	053-000-42664		02/07/2020	91.50
ASTERIS, MARK	135898	02/14/2020	JAN.2020/CSCD	053-461-42647		02/14/2020	200.00
QUILL CORPORATION	135959	02/14/2020	2772734/CSCD	053-000-42104		02/14/2020	0.83
QUILL CORPORATION	135959	02/14/2020	2772734/CSCD	053-000-42170		02/14/2020	249.99
QUILL CORPORATION	135955	02/14/2020	2772734/CSCD	053-000-42104		02/14/2020	16.84
QUILL CORPORATION	135960	02/14/2020	2772734/CSCD	053-000-42104		02/14/2020	88.66
CORRECTIONS SOFTWARE S	135913	02/14/2020	INV#47797/CSCD	053-000-42602		02/14/2020	995.00
TYLER CO. COMMUNITY SUP	135890	02/13/2020	State Health Insurance	053-21300		02/13/2020	830.62
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	053-21300		02/13/2020	1,034.34

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	053-21300		02/13/2020	390.60
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	053-21300		02/13/2020	241.90
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	053-29999		02/12/2020	6,655.54
OCEAN BREEZE OCCUPATION	135946	02/14/2020	INV.#TCAP12020/CSCD	053-000-42647		02/14/2020	136.00
O'NEAL, MATT	136024	02/14/2020	REIMB/ STRATEGIC PLAN ME	053-000-42664		02/14/2020	230.76
SOUTHEAST TEXAS POLYGRA	136007	02/14/2020	2/6/2020- CSCD	053-461-42647		02/14/2020	200.00
TIPTON, JEREMY	136032	02/14/2020	INV#254/CSCD	053-000-42602		02/14/2020	150.00
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	053-21320		02/13/2020	1,284.39

Fund 053 - ADULT PROBATION Total: 31,034.72

Fund: 054 - JUVENILE PROBATION

NATIONWIDE RETIREMENT S	135771	01/30/2020	Deferred Comp	054-21300		01/30/2020	75.00
TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	054-21300		01/30/2020	1,471.54
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	054-21300		01/30/2020	1,609.61
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	054-21300		01/30/2020	344.14
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	054-29999		01/29/2020	8,450.71
FERTITTA, CINDY	135803	01/31/2020	MILEAGE REIMB/ JUPRO	054-451-42356		01/31/2020	46.92
ALLEN, TERRY	135793	01/31/2020	PER DIEM & HOTEL/33RD AN	054-451-42659		01/31/2020	555.35
GREGORCYK, SCOTT	135805	01/31/2020	RESTITUTION PID#1659	054-457-42907		01/31/2020	104.58
CELESTINE, GODWIN	135796	01/31/2020	RESTITUTION PID 1659/JUPR	054-457-42907		01/31/2020	157.92
FERTITTA, CINDY	135803	01/31/2020	JAN TRAVEL	054-451-42356		01/31/2020	125.00
FERTITTA, CINDY	135803	01/31/2020	JAN TRAVEL	054-455-42112		01/31/2020	50.00
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	054-21320		01/30/2020	1,635.57
D. SCOTT HUGHES CENTER F	135846	02/07/2020	INV#0000338/JUPRO	054-451-42356		02/07/2020	400.00
D. SCOTT HUGHES CENTER F	135846	02/07/2020	INV#0000338/JUPRO	054-455-42112		02/07/2020	250.00
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	054-455-40120		02/06/2020	78.40
FERTITTA, CINDY	135920	02/14/2020	PARENTING SESSIONS/JUPR	054-451-42356		02/14/2020	315.00
FERTITTA, CINDY	135920	02/14/2020	PARENTING SESSIONS/JUPR	054-455-42112		02/14/2020	50.00
FERTITTA, CINDY	135920	02/14/2020	MILEAGE REIMB. FOR PAREN	054-451-42356		02/14/2020	15.07
NATIONWIDE RETIREMENT S	135889	02/13/2020	Deferred Comp	054-21300		02/13/2020	75.00
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	054-21300		02/13/2020	861.00
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	054-21300		02/13/2020	698.16
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	054-21300		02/13/2020	201.38
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	054-29999		02/12/2020	5,091.52
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	054-21320		02/13/2020	972.06

Fund 054 - JUVENILE PROBATION Total: 23,633.93

Fund: 073 - JUSTICE COURT TECHNOLOGY FUND

VERIZON WIRELESS	135878	02/10/2020	1963-00001/COAUD,PCT2,JP	073-000-42101		02/10/2020	160.52
------------------	--------	------------	--------------------------	---------------	--	------------	--------

Fund 073 - JUSTICE COURT TECHNOLOGY FUND Total: 160.52

Fund: 076 - EMERGENCY OPERATIONS CENTER

TYLER COUNTY PAYROLL	135768	01/30/2020	FICA	076-21300		01/30/2020	495.02
TYLER COUNTY PAYROLL	135768	01/30/2020	Federal Withholding	076-21300		01/30/2020	327.55
TYLER COUNTY PAYROLL	135768	01/30/2020	Medicare	076-21300		01/30/2020	115.76
TYLER COUNTY PAYROLL	135770	01/29/2020	PAYROLL TRANSFER	076-29999		01/29/2020	3,084.70

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Vendor Name	Payment Number	Post Date	Description (Item)	Account Number	Project Account Key	Post Date	Amount
TEXAS COUNTY & DISTRICT R	DFT0002253	01/30/2020	Tyler County, TX Retirement	076-21320		01/30/2020	544.41
TAC HEALTH BENEFITS POOL	135835	02/06/2020	LIFE INSURANCE FEBRUARY	076-000-40120		02/06/2020	78.08
A-1 WRECKER SERVICE - REB	135895	02/14/2020	INV#034552/EOC	076-000-42416		02/14/2020	130.00
U PUMP IT - GARDNER OIL	135994	02/14/2020	1911/EOC	076-000-42416		02/14/2020	326.57
QUILL CORPORATION	135958	02/14/2020	7309806/EOC	076-000-42100		02/14/2020	76.16
TYLER COUNTY PAYROLL	135885	02/13/2020	FICA	076-21300		02/13/2020	487.06
TYLER COUNTY PAYROLL	135885	02/13/2020	Federal Withholding	076-21300		02/13/2020	318.94
TYLER COUNTY PAYROLL	135885	02/13/2020	Medicare	076-21300		02/13/2020	113.92
TYLER COUNTY PAYROLL	135888	02/12/2020	PAYROLL TRANSFER	076-29999		02/12/2020	3,001.36
A T & T PHONES - ATLANTA,	135893	02/14/2020	4542/COUNTY PHONES	076-000-42500		02/14/2020	246.57
TEXAS COUNTY & DISTRICT R	DFT0002261	02/13/2020	Tyler County, TX Retirement	076-21320		02/13/2020	544.41
Fund 076 - EMERGENCY OPERATIONS CENTER Total:							9,890.51
Fund: 089 - TYLER COUNTY NUTRITION CENTER							
BILL CLARK PEST CONTROL, I	135795	01/31/2020	119086/EOC	089-000-42410		01/31/2020	88.00
CITY OF WOODVILLE	135866	02/10/2020	07087601/NUTR CENTER	089-000-42510		02/10/2020	72.88
Fund 089 - TYLER COUNTY NUTRITION CENTER Total:							160.88
Fund: 093 - PAYROLL ACCOUNT							
UNITED STATES TREASURY-IR		01/29/2020	JANUARY FEDERAL TAXES PP	093-11000		01/29/2020	49,724.45
UNITED STATES TREASURY-IR		01/29/2020	JANUARY FEDERAL TAXES PP	093-11000		01/29/2020	-49,724.45
UNITED STATES TREASURY-IR	DFT0002256	01/29/2020	JANUARY FEDERAL TAXES PP	093-11000		01/29/2020	49,724.45
UNITED STATES TREASURY-IR	DFT0002258	01/30/2020	JANUARY FEDERAL TAXES CO	093-11000		01/30/2020	20.18
UNITED STATES TREASURY-IR	DFT0002264	02/12/2020	FEBRUARY FEDERAL TAXES P	093-11000		02/12/2020	44,381.49
Fund 093 - PAYROLL ACCOUNT Total:							94,126.12
Fund: 095 - STATE- APPELLATE JUDICIAL FUND							
NINTH COURT OF APPEALS	135850	02/07/2020	SB-325/CH22 COCLK	095-000-49000		02/07/2020	35.00
NINTH COURT OF APPEALS	135850	02/07/2020	SB-325/CH22 DSCLK	095-000-49000		02/07/2020	115.00
Fund 095 - STATE- APPELLATE JUDICIAL FUND Total:							150.00
Fund: 097 - CHILD SAFETY FUND							
HARRIS, KATHY	135925	02/14/2020	REIMB.FOOD FOR MEETNG/J	097-000-42655		02/14/2020	27.16
Fund 097 - CHILD SAFETY FUND Total:							27.16
Fund: 111 - COURTHOUSE RESTORATION							
THE LABICHE ARCHITECTURA	135984	02/14/2020	INV#190207/COJUD	111-000-42412		02/14/2020	2,185.30
THE LABICHE ARCHITECTURA	135984	02/14/2020	INV#19020A.03/COJUD	111-000-48011		02/14/2020	6,219.72
Fund 111 - COURTHOUSE RESTORATION Total:							8,405.02
Fund: 113 - CIVIL FEES - ADULT PROBATION							
O'NEAL, MATT	135871	02/10/2020	REIMB FOR TRAINING MEAL	113-000-42104		02/10/2020	84.06
Fund 113 - CIVIL FEES - ADULT PROBATION Total:							84.06
Grand Total:							864,183.18

Report Summary

Fund Summary

Fund	Payment Amount
010 - GENERAL FUND	448,279.35
021 - ROAD & BRIDGE I	49,388.47
022 - ROAD & BRIDGE II	57,758.87
023 - ROAD & BRIDGE III	67,885.46
024 - ROAD & BRIDGE IV	65,150.35
025 - TYLER CO AIRPORT	1,982.95
026 - TYLER CO. RODEO ARENA/FAIRGRND	319.53
031 - COUNTY CLERK RMP	1,569.20
036 - LIBRARY FUND	1,025.89
039 - TXCDBG SMALL BUSINESS LOAN PRJ	557.50
044 - COURTHOUSE SECURITY	2,592.69
053 - ADULT PROBATION	31,034.72
054 - JUVENILE PROBATION	23,633.93
073 - JUSTICE COURT TECHNOLOGY FUND	160.52
076 - EMERGENCY OPERATIONS CENTER	9,890.51
089 - TYLER COUNTY NUTRITION CENTER	160.88
093 - PAYROLL ACCOUNT	94,126.12
095 - STATE- APPELLATE JUDICIAL FUND	150.00
097 - CHILD SAFETY FUND	27.16
111 - COURTHOUSE RESTORATION	8,405.02
113 - CIVIL FEES - ADULT PROBATION	84.06
Grand Total:	864,183.18

Account Summary

Account Number	Account Name	Payment Amount
010-21300	PAYROLL LIABILITIES	58,989.15
010-21320	RETIREMENT	34,230.28
010-29999	Due To Other Funds	188,048.89
010-32103	AUTO REGISTRATION FE	2,185.01
010-401-40150	CONTINGENCY/HOSPITA	2,097.63
010-401-42111	POSTAGE FOR POSTAGE	3,313.58
010-401-42158	ELECTION EXPENSE	436.00
010-401-42178	CONTINGENCY FOR MIS	4,162.25
010-401-42204	TYLER COUNTY YOUTH P	6,000.00
010-401-42231	HOUSING OF TCSO INM	23,138.09
010-401-42352	TC NUTRITION SERVICES	3,750.00
010-401-42500	COUNTY TELEPHONES	2,730.57
010-401-42616	ADVERTISING	156.75
010-401-42628	CONTINGENCY FOR LEG	10,387.50
010-401-42649	ALLAN SHIVERS LIBRARY	31,925.00

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Account Summary

Account Number	Account Name	Payment Amount
010-401-42701	RURAL FIRE PROTECTIO	450.00
010-402-42100	OFFICE SUPPLIES	42.05
010-402-42659	TRAVEL & EDUCATION	1,005.90
010-405-42100	OFFICE SUPPLIES	49.94
010-408-42634	COURT APPOINTED ATT	2,800.00
010-408-42637	CPS COURT APPOINTED	9,857.03
010-408-42638	CPS COURT REPORTER	400.00
010-408-42700	PETIT JURORS	3,220.00
010-411-42661	TRAINING & EDUCATION	370.80
010-414-42500	TELEPHONE	25.97
010-415-42623	COMMITMENTS	457.00
010-415-42634	COURT APPOINTED ATT	200.00
010-415-42635	COURT REPORTER	412.00
010-419-42100	OFFICE SUPPLIES	682.07
010-419-42222	WITNESS EXPENSE	930.14
010-419-42500	TELEPHONE	80.26
010-420-42100	OFFICE SUPPLIES	947.26
010-420-42500	TELEPHONE	63.00
010-420-42650	ASSOCIATION DUES	425.00
010-420-42900	BONDS	117.50
010-421-42100	OFFICE SUPPLIES	41.99
010-421-42189	EDUCATION,GOVERNME	370.00
010-422-42150	UNIFORMS	92.00
010-422-42650	ASSOCIATION DUES	325.00
010-423-42100	OFFICE SUPPLIES	290.08
010-423-42650	ASSOCIATION DUES	50.00
010-423-42659	TRAVEL & EDUCATION	439.80
010-426-42150	UNIFORMS	392.11
010-426-42182	DEPUTIES SUPPLIES	784.51
010-426-42400	GAS, OIL, GREASE	6,564.34
010-426-42401	TIRES, TUBES	181.32
010-426-42413	REPAIRS TO VEHICLES	752.26
010-426-42500	TELEPHONE	1,473.94
010-426-42659	TRAVEL & EDUCATION	310.00
010-427-42108	JAIL SUPPLIES	3,802.74
010-427-42157	PRISONER MEALS	5,350.87
010-427-42659	TRAVEL & EDUCATION	175.00
010-430-42100	OFFICE SUPPLIES	134.64
010-439-42100	OFFICE SUPPLIES	71.00
010-439-42224	OUT-OF-COUNTY TRAVE	897.00
010-440-42101	SUPPLIES	10,375.52
010-440-42350	SERVICE CONTRACTS	3,135.19

Account Summary		
Account Number	Account Name	Payment Amount
010-440-42353	SUPPORT SERVICES	3,368.80
010-440-42600	PROFESSIONAL SERVICE	1,117.00
010-440-42677	EQUIPMENT LEASE	948.25
010-442-42106	JANITORS SUPPLIES	2,332.32
010-442-42397	GROUNDS MAINTENAN	782.80
010-442-42400	GAS, OIL, GREASE	266.42
010-442-42411	REPAIRS & MAINTENAN	75.00
010-442-42412	REPAIRS & MAINTENAN	454.84
010-442-42413	REPAIRS TO VEHICLES	7.00
010-442-42417	REPAIRS & MAINTENAN	307.80
010-442-42418	REPAIRS & MAINTENAN	67.00
010-442-42419	REPAIRS & MAINTENAN	157.02
010-442-42511	UTILITIES-JUSTICE CENTE	2,186.70
010-442-42515	UTILITIES-COURTHOUSE	204.01
010-442-42516	UTILITIES-COUNTY	34.00
010-442-42517	UTILITIES-TAX OFFICE	172.72
010-442-42518	UTILITIES - TYLER CO. CO	272.55
010-453-43152	RENOVATIONS - TAX OFF	2,500.00
010-453-43210	OFFICE EQUIPMENT	423.10
010-453-43604	TYLER COUNTY OFFICE C	2,506.09
021-000-40120	HOSPITALIZATION	193.61
021-000-42150	UNIFORMS	186.83
021-000-42160	ROAD MATERIAL	2,181.78
021-000-42400	GAS, OIL, GREASE	2,046.18
021-000-42401	TIRES, TUBES	54.92
021-000-42425	MACHINERY MAINTENA	4,259.10
021-000-42500	TELEPHONE	220.71
021-000-42510	UTILITIES	221.21
021-000-42998	MISCELLANEOUS SUPPLI	420.70
021-000-43200	PURCHASE OF EQUIPME	10,512.00
021-21300	PAYROLL LIABILITIES	6,200.83
021-21320	RETIREMENT	3,580.24
021-29999	Due To Other Funds	19,310.36
022-000-40120	HOSPITALIZATION	212.80
022-000-42150	UNIFORMS	301.84
022-000-42160	ROAD MATERIAL	11,129.18
022-000-42161	CULVERTS	4,135.60
022-000-42400	GAS, OIL, GREASE	4,804.84
022-000-42401	TIRES, TUBES	39.40
022-000-42425	MACHINERY MAINTENA	6,049.27
022-000-42500	TELEPHONE	193.35
022-000-42510	UTILITIES	274.45

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Account Summary

Account Number	Account Name	Payment Amount
022-000-42659	TRAVEL & EDUCATION	347.00
022-000-42998	MISCELLANEOUS SUPPLI	3,272.99
022-000-43200	PURCHASE OF EQUIPME	3,720.98
022-21300	PAYROLL LIABILITIES	4,854.81
022-21320	RETIREMENT	2,834.73
022-29999	Due To Other Funds	15,587.63
023-000-40120	HOSPITALIZATION	228.73
023-000-42160	ROAD MATERIAL	11,382.25
023-000-42400	GAS, OIL, GREASE	5,717.50
023-000-42401	TIRES, TUBES	114.92
023-000-42425	MACHINERY MAINTENA	7,225.33
023-000-42500	TELEPHONE	299.57
023-000-42510	UTILITIES	329.17
023-000-42998	MISCELLANEOUS SUPPLI	353.99
023-21300	PAYROLL LIABILITIES	7,972.25
023-21320	RETIREMENT	4,829.95
023-29999	Due To Other Funds	29,431.80
024-000-16900	CONSTRUCTION IN PRO	7,355.00
024-000-40120	HOSPITALIZATION	250.93
024-000-42150	UNIFORMS	1,044.00
024-000-42160	ROAD MATERIAL	4,233.68
024-000-42400	GAS, OIL, GREASE	3,523.28
024-000-42425	MACHINERY MAINTENA	1,196.70
024-000-42500	TELEPHONE	35.80
024-000-42510	UTILITIES	204.64
024-000-42998	MISCELLANEOUS SUPPLI	42.01
024-000-43605	CONSTRUCTION OF PCT.	16,685.93
024-21300	PAYROLL LIABILITIES	6,120.45
024-21320	RETIREMENT	3,710.61
024-29999	Due To Other Funds	20,747.32
025-000-42410	REPAIRS & MAINTENAN	80.00
025-000-42510	UTILITIES	210.66
025-000-43202	BUILDINGS & PROPERTY	1,692.29
026-000-42510	UTILITIES	319.53
031-21300	PAYROLL LIABILITIES	209.62
031-21320	RETIREMENT	190.29
031-29999	Due To Other Funds	1,169.29
036-000-48007	LIBRARY BOOKS & SUPP	1,025.89
039-000-44300	LOAN REPAYMENT	557.50
044-21300	PAYROLL LIABILITIES	592.33
044-21320	RETIREMENT	307.58
044-29999	Due To Other Funds	1,692.78

CHECK REGISTER

Payable Dates: 01272020 - 02242020

Account Summary

Account Number	Account Name	Payment Amount
053-000-42104	SUPPLIES & OPERATING	106.33
053-000-42170	EQUIPMENT	249.99
053-000-42602	PROFESSIONAL FEES	8,845.00
053-000-42647	CONTRACT SERVICES FO	136.00
053-000-42664	TRAVEL/FURNISHED TRA	322.26
053-21300	PAYROLL LIABILITIES	4,316.30
053-21320	RETIREMENT	2,540.62
053-29999	Due To Other Funds	13,939.59
053-461-42647	CONTRACT SERVICES FO	400.00
053-461-42664	TRAVEL/FURNISHED TRA	178.63
054-21300	PAYROLL LIABILITIES	5,335.83
054-21320	RETIREMENT	2,607.63
054-29999	Due To Other Funds	13,542.23
054-451-42356	MHS/COMMUNITY BASE	901.99
054-451-42659	TRAVEL & TRAINING (DI	555.35
054-455-40120	HOSPITALIZATION	78.40
054-455-42112	LOCAL MONEY (DETCO	350.00
054-457-42907	RESTITUTION	262.50
073-000-42101	SUPPLIES	160.52
076-000-40120	HOSPITALIZATION	78.08
076-000-42100	OFFICE SUPPLIES	76.16
076-000-42416	VEHICLE OPERATIONS/M	456.57
076-000-42500	TELEPHONE	246.57
076-21300	PAYROLL LIABILITIES	1,858.25
076-21320	RETIREMENT	1,088.82
076-29999	Due To Other Funds	6,086.06
089-000-42410	REPAIRS & MAINTENAN	88.00
089-000-42510	UTILITIES	72.88
093-11000	Due From Other Funds	94,126.12
095-000-49000	PAYMENT TO 9TH COUR	150.00
097-000-42655	CHILD SAFETY PROGRA	27.16
111-000-42412	COURTHOUSE REHABILIT	2,185.30
111-000-48011	COURTHOUSE REMEDIA	6,219.72
113-000-42104	SUPPLIES & OPERATING	84.06
	Grand Total:	864,183.18

Project Account Summary

Project Account Key	Payment Amount
None	864,183.18
Grand Total:	864,183.18



Date: 2/14/2020
 Invoice # 2142020-1

EIP Holdings II, LLC.
 Two Allegheny Center
 Nova Tower 2, Suite 703
 Pittsburgh, PA 15212
 412-482-3429

Tyler County Sheriff &
 Tyler County Fire
 Attn: Tressa Redden

 Email:
 tredden.aud@co.tyler.tx.us

<i>Purpose</i>	<i>Due Date</i>
Woodville Communication Tower HWY 190 E 1.6093 KM, Woodville, TX 75979	Due Upon Receipt

<i>Description</i>	<i>Total</i>
January and February 2020 rent - Woodville County Sheriff	\$700.00
January and February 2020 rent - Woodville County Fire	\$266.66

July - December 2020 rent due July 1, 2020 (1,100.00)

Subtotal	\$966.66
Sales Tax	0.00
Total	\$966.66

Payment Address:
 Two Allegheny Center
 Nova Tower 2, Suite 703
 Pittsburgh, PA 15212

ACH/Wire Instructions:
 PNC Bank
 916 Fifth Avenue
 Pittsburgh, PA 15219

Beneficiary: EIP Holdings II, LLC
 ABA: 043000096
 Account: 1069977906

Make all checks payable to EIP Holdings II, LLC



Texas Department of Criminal Justice

Texas Correctional Industries
P.O. Box 4013

E-mail tci@tdcj.texas.gov
Phone # 800-833-4302

Invoice

Table with invoice details: Date (2/14/2020), Invoice # (UI 465397), S.O. No. (52424), P.O. No. (01152020), Customer Ref No.

Bill To: Tyler County Auditor's Office, 100 W Bluff, Room 110, Woodville, TX 75979. Account # B399103

Ship To: Tyler County Auditor's Office, 100 W Bluff, Room 110, Woodville, TX 75979

Main invoice table with columns: Item Code, Description, QTY, Price, U/M, Amount. Includes handwritten notes: AMOUNT 3,000.00, CODE NO., VENDOR NO. 013213, APPROVED, and Auditor's Office signature.

Summary row: Your feedback is important. Please complete our customer service survey at www.tci.tdcj.texas.gov. Total \$3,000.00

Remit To: TDCJ Cashier, P.O. Box 4015, Huntsville, Texas 77342-4015

RTI# 090120, Interest # 033101, Vendor # 36966966966007, Terms: Net 45 Days from Date of Invoice

Resale of any item on the open market is a violation of §497.010, Texas Government Code.

FEE CODE	FEE DESCRIPTION	GL ACCOUNT	COLLECTED	REVERSL	LIABILITY	OFFENSES					AFTER 1-01-04
						PRIOR TO 9-01-91	9-01-91 THRU 8-31-97	9-01-97 THRU 8-30-99	8-31-99 THRU 8-31-01	9-01-01 THRU 12-31-03	
LF	LIBRARY FEE	036-363-032	380.00		380.00						
	TOTAL DEPT				380.00						
	TOTAL FUND				380.00						
CRCSF	COURTHOUSE SECURITY	044-363-033	11.00		11.00						11.00
CSF	COURTHOUSE SECURITY	044-363-033	110.00		110.00						
	TOTAL DEPT				121.00						11.00
	TOTAL FUND				121.00						11.00
CRRMP	RECORDS MANAGEMENT	045-361-013	67.50		67.50						67.50
RMP	RECORDS MANAGEMENT	045-361-013	125.00		125.00						
	TOTAL DEPT				192.50						67.50
	TOTAL FUND				192.50						67.50
TPF	TIME PAYMENT FEE	068-363-028	75.00		75.00						75.00
	TOTAL DEPT				75.00						75.00
	TOTAL FUND				75.00						75.00
CCC	CONSOLIDATED COURT COST	070-363-028	236.00		236.00						236.00
	TOTAL DEPT				236.00						236.00
	TOTAL FUND				236.00						236.00
BMS	BMS TRAUMA FUND	080-363-030	100.00		100.00						100.00
	TOTAL DEPT				100.00						100.00
	TOTAL FUND				100.00						100.00

FEE CODE	FEE DESCRIPTION	GL ACCOUNT	COLLECTED	REVERSL	LIABILITY	OFFENSES					AFTER 1-01-04
						PRIOR TO 9-01-91	9-01-91 THRU 8-31-97	9-01-97 THRU 8-30-99	8-31-99 THRU 8-31-01	9-01-01 THRU 12-31-03	
SB727	DNA DATABASE	083 363 031	34.00		34.00						34.00
	TOTAL DEPT				34.00						34.00
	TOTAL FUND				34.00						34.00
DNA	DNA TESTING	083-363-030	25.00		25.00						25.00
	TOTAL DEPT				25.00						25.00
	TOTAL FUND				25.00						25.00
CCAPF	COUNTY CHILD ABUSE PREVENTION FUND	084-363-032	35.00		35.00						35.00
	TOTAL DEPT				35.00						35.00
	TOTAL FUND				35.00						35.00
SJP	STATE JUDICIAL FUND	085-363-031	924.00		924.00						
CRSJF	CRIMINAL STATE JUDICIAL FUND	085-363-032	18.00		18.00						18.00
	TOTAL DEPT				942.00						18.00
	TOTAL FUND				942.00						18.00
HB530	DRUG COURT COST FEE	090-363-025	60.00		60.00						60.00
	TOTAL DEPT				60.00						60.00
	TOTAL FUND				60.00						60.00
CRIDF	CRIMINAL INDIGENT DEPOSE FUND	094 363 032	6.00		6.00						6.00
	TOTAL DEPT				6.00						6.00
	TOTAL FUND				6.00						6.00

FEE CODE	FEE DESCRIPTION	GL ACCOUNT	COLLECTED	REVERSL	LIABILITY	OFFENSES					AFTER 1-01-04	
						PRIOR TO 9-01-91	9-01-91 THRU 8-31-97	9-01-97 THRU 8-30-99	8-31-99 THRU 8-31-01	9-01-01 THRU 12-31-03		
JSSF	NINTH COURT OF APPEALS FEE	095 363 032	97.72		97.72							
	TOTAL DEPT				97.72							
	TOTAL FUND				97.72							
TECH	DC COURT TECHNOLOGY	103-363-033	220.00		220.00							
RTECH	CRIMINAL RECORD TECHNOLOGY	103-363-034	12.00		12.00							12.00
	TOTAL DEPT				232.00							12.00
	TOTAL FUND				232.00							12.00
	TOTAL COLLECTED		10,359.00		10,359.00					5.00		1,052.50
	LESS MONEY WITHOUT A GL ACCT NBR				60.00-							
	TOTAL MONEY WITH A GL ACCT NBR				10,299.00					5.00		1,052.50

RECEIPT	DATE	CASE NUMBER	NAME	DESCRIPTION	PAID BY	TYPE	CHECK #	CLERK	TOTAL PAID	RVSL
040268	01/02/2020	B-2638	LANDAVAZO, JIMMY, AKA JIMMY	PMT IN FULL ON COURT COST	TITLE COMPANY	K	017787	AC	252.50	
040269	01/02/2020	CR11221	BENTZ, JEREMY PAUL	PARTIAL PMT ON COURT COST	BENTZ, JEREMY PAUL	O	19-058409702	AC	30.00	
040270	01/02/2020	08020		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025617	AC	5.00	
040271	01/02/2020	08021		PMT FOR PASSPORT/AC	SUSAN PRICE	C		AC	35.00	
040272	01/02/2020	08022		TWO APPLICATIONS FOR PASS	KYLE LEWIS	K	1053	DH	70.00	
040273	01/03/2020	08023		PMT FOR FINAL DECREE/AC	IDA BOUDREAUX	C		AC	44.00	
040274	01/03/2020	25271	ROBINSON, ELWANDA CHARLES	PMT FOR FILING PETITION F	ROBINSON, ELWANDA CHA	C		AC	263.00	
040275	01/06/2020	08024		DECEMBER REPORT/DH	TYLER CO TITLE	C		DH	2.00	
040276	01/06/2020	CR12924	COLEMAN, REBEKAH ROSE	PMT IN FULL ON COURT COST	COLEMAN, REBEKAH ROSE	K	000803478	AC	349.00	
040277	01/06/2020	08025		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025635	AC	5.00	
040278	01/06/2020	24285	FILLINGIM, KATIE E	EFILING FEE FOR PETITION	ATTY SHIPLEY	D	12491092940	AC	31.00	
040279	01/06/2020	08026		EFILING FEE FOR COPIES 24	ATTY SHIPLEY	D	12491092940	AC	14.00	
040283	01/07/2020	25255	BOTTOM LINE EQUIPMENT, LLC	EFILING FEE FOR CITATION/	ATTY RICHEY	D	12492301265	AC	8.00	
040284	01/07/2020	25255	BOTTOM LINE EQUIPMENT, LLC	EFILING FEE FOR CITATION/	ATTY RICHEY	D	12492301265	AC	12.00	
040285	01/08/2020	08028		PMT FOR PASSPORT/AC	CHERYL ESHLIMAN	K	8439	AC	35.00	
040286	01/08/2020	CR13197	HARVEY, JENNIFER ANNE	PARTIAL PMT ON COURT COST	HARVEY, JENNIFER ANNE	O	17-912169765	AC	100.00	
040287	01/08/2020	25274	BROWN, MICHAEL BUTCH	FILING FEE/ORIGINAL PETIT	ATTY BRAD ELROD	D	FT#12495945219	DH	271.00	
040288	01/08/2020	25258	HEISELBETZ, RYAN GORDON	EFILING FEE TO ISSUED TRO	ATTY LAINE	D	12495945219	AC	8.00	
040289	01/09/2020	08029		PMT FOR COPIES CR13,097/A	BRANDON STUART	O	19-016370814	AC	15.00	
040290	01/09/2020	08030		PMT FOR COPIES 23,296/AC	DARLEAN LEE	C		AC	18.00	
040291	01/09/2020	B-2618	ODOM, LARRY, ET AL	PARTIAL PMT ON COURT COST	LINEBARGER	K	326563	AC	650.00	
040292	01/09/2020	08031		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025741	AC	5.00	
040293	01/09/2020	25275	U.S. BANK NATIONAL ASSOCIATES	FILING FEE/PLAINTIFF'S OR	ATTY BROGAN	D	FT#12497172073	DH	265.00	
040294	01/09/2020	08032		FILING FEE/COPIES/DH	ATTY BROGAN	D	FT#12497172073	DH	9.00	
040295	01/09/2020	25226	CITIZENS STATE BANK	EFILING FEE FOR CIT, WRIT	ATTY FORTENBERRY	D	12497172073	AC	36.00	
040296	01/09/2020	25276	GARLASKA, MICHAEL LER	E-FILING FEE FOR ORIGINAL	ATTY GARY BUTLER	D	12497172073	LB	279.00	
040297	01/09/2020	08033		E-FILING FEE FOR COPIES F	ATTY GARY BUTLER	D	12497172073	LB	8.00	
040298	01/09/2020	25277	BLAM, AIMEE BURKS	E-FILING FEE FOR ORIGINAL	ATTY RISINGER	D	12497172073	LB	271.00	

RECEIPT	DATE	CASE NUMBER	NAME	DESCRIPTION	PAID BY	TYPE	CHECK #	CLERK	TOTAL PAID	RVSL
040299	01/09/2020	08034		E-FILING FEE FOR COPIES P	ATTY RISINGER	D	12497172073	LB	5.00	
040300	01/10/2020	08035		PMT FOR COPIES CR9505/AC	ANGELA PRIDE	C		AC	6.00	
040301	01/10/2020	CR13543	MURRAY,JAMES RANDALL	PARTIAL PMT ON COURT COST	MURRAY,JAMES RANDALL	O	26261511221	AC	45.00	
040302	01/13/2020	08036		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025745	AC	5.00	
040303	01/13/2020	21452	TAYLOR,CHARLIE J.	PARTIAL PMT ON COURT COST	TDCJ INMATE TRUST	K	434286	AC	5.00	
040304	01/13/2020	CR9757	COLLINS,DAVID BRANDON	PARTIAL PMT ON COURT COST	TDCJ INMATE TRUST	K	434286	AC	5.00	
040305	01/13/2020	CR12112	BROOKS,JAMES ALLEN	PARTIAL PMT ON COURT COST	TDCJ INMATE TRUST	K	434286	AC	12.50	
040306	01/13/2020	CR11773	ADAMS,CLINTON	PARTIAL PMT ON COURT COST	TDCJ INMATE TRUST	K	434286	AC	13.00	
040307	01/13/2020	24083	PATTERSON,MARLA	EFILING FEE FOR M/NEW TRA	ATTY BYTHEWOOD	D	12499637352	AC	70.00	
040308	01/14/2020	B-3276	ROGERS,MICHAEL A.	COURT COST PAID IN FULL/D	ROGERS,MICHAEL A.	O	60902	DH	305.00	
040309	01/14/2020	25280	SECOND ROUND SUB, LLC	FILING FEE/PLAINTIFF'S OR	ATTY ADDISON	D	FT#12500873418	DH	265.00	
040310	01/14/2020	08037		FILING FEE/COPIES #25,280	ATTY ADDISON	D	FT#12500873418	DH	9.00	
040311	01/14/2020	25262	BROMLEY,ROBERT CHAD	EFILING FEE FOR COUNTERCL	ATTY GREEN	D	12500873418	AC	75.00	
040312	01/14/2020	A-18609		E-FILING FEE FOR ORIGINAL	ATTY BRAD ELROD	D	12500873418	LB	255.00	
040313	01/14/2020	25279	WIGGINS,MATTHEW	E-FILING FEE FOR ORIGINAL	ATTY BRAD ELROD	D	12500873418	LB	263.00	
040314	01/15/2020	08038		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025821	AC	10.00	
040315	01/15/2020	08039		APPLICATION FOR PASSPORT/	TOMMY BELL	K	1741	DH	35.00	
040316	01/15/2020	08040		PMT FOR COPIES 25,207/AC	ATTY RISINGER	K	12094	AC	33.00	
040317	01/16/2020	25281	SECOND ROUND SUB, LLC	EFILING FEE FOR PETITION	ATTY ADDISON	D	12504563424	AC	265.00	
040317	01/16/2020	25281	SECOND ROUND SUB, LLC	REVERSAL OF RECEIPT # 040		D	12504563424	AC	265.00	
040318	01/16/2020	08041		EFILING FEE FOR COPIES 25	ATTY ADDISON	D	12504563424	AC	9.00	
040318	01/16/2020	08041		REVERSAL OF RECEIPT # 040		D	12504563424	AC	9.00	
040319	01/15/2020	08041		EFILING FEE FOR COPIES 25	ATTY ADDISON	D	12504563424	AC	9.00	
040320	01/15/2020	25281	SECOND ROUND SUB, LLC	EFILING FEE FOR PETITION	ATTY ADDISON	D	12504563424	AC	265.00	
040321	01/15/2020	25284	CALLEY,TAMMY	PLAINTIFF'S ORIGINAL PETI	ATTY R TODD	D	FT#12504563424	DH	265.00	
040322	01/15/2020	08042		FILING FEE/COPIES/25,284/	ATTY R TODD	D	FT#12504563424	DH	19.00	
040323	01/16/2020	CR13503	WHITTEMORE,MARK DAVID	PARTIAL PMT ON COURT COST	WHITTEMORE,MARK DAVI	C		AC	50.00	
040324	01/16/2020	B-2935	CLEMENT,PATSY GEORGE	PMT IN FULL ON COURT COST	LINEBARGER	K	326593	AC	544.00	

RECEIPT	DATE	CASE NUMBER	NAME	DESCRIPTION	PAID BY	TYPE	CHECK #	CLERK	TOTAL PAID	RVSL
040325	01/16/2020	08043		PMT FOR COPIES 24,212/AC	MICHAEL LEE	C		AC	30.00	
040326	01/16/2020	25285	THOMPSON, SHERRY	FILING FEE/ORIGIANL PETIT	ATTY RISINGER	D	FT#12505802654	DH	263.00	
040327	01/17/2020	08044		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025685	AC	5.00	
040328	01/17/2020	08045		PMT FOR COPIES 24,596/AC	Z. CRAWFORD	C		AC	33.00	
040329	01/21/2020	08046		PMT FOR PASSPORT/AC	COSMOS V. DINH	C		AC	35.00	
040330	01/21/2020	08047		PAYMENT FOR ISSUANCE OF P	LAURANT PINGREE II	K	6013	LB	35.00	
040331	01/21/2020	CR13277	TAYLOR, MICHAEL JEROME JR	PARTIAL PMT ON COURT COST	TAYLOR, MICHAEL JEROM	O	17-907560778	AC	10.00	
040332	01/21/2020	08048		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	025961	AC	5.00	
040333	01/21/2020	25290	MARTIN, AMBER NICOLE	FILING FEE FOR ORIGINAL P	MARTIN, AMBER NICOLE	C		LB	263.00	
040334	01/21/2020	08049		PMT FOR PASSPORTS/AC	CHARLYA FAIRCLOTH	K	443	AC	70.00	
040335	01/17/2020	08050		E-FILING FEE FOR COPIES P	ATTY BRAD ELROD	D	12507044951	LB	12.00	
040336	01/17/2020	25226	CITIZENS STATE BANK	EFILING FEE FOR WRIT/AC	ATTY FORTENBERRY	D	12507044951	AC	158.00	
040340	01/21/2020	25286	JOHNSTON, JILL	EFILING FEE FOR PETITION/	ATTY WALTON	D	12508287915	AC	263.00	
040341	01/21/2020	25287	TYLER COUNTY TITLE, LLC	EFILING FEE FOR PETITION	ATTY FORTENBERRY	D	12508287915	AC	525.00	
040342	01/21/2020	25288	TYLER COUNTY TITLE, LLC	EFILING FEE FOR PETITION	ATTY FORTENBERRY	D	12508287915	AC	521.00	
040343	01/22/2020	08051		PAYMENT FOR ISSUANCE OF P	SHEWANA SPENCER	C		LB	35.00	
040344	01/22/2020	08052		PAYMENT FOR ISSUANCE OF P	JOHNNIE WHITTAKER	C		LB	35.00	
040344	01/22/2020	08052		REVERSAL OF RECEIPT # 040		R		LB	35.00	
040345	01/22/2020	08053		PAYMENT FOR ISSUANCE OF P	JOHNNIE WHITTAKER	C		LB	35.00	
040346	01/22/2020	08054		PMT FOR PASSPORTS/AC	DENISE BAINBRIDGE	C		AC	35.00	
040347	01/22/2020	08055		PAYMENT FOR COPY OF PETIT	MIRANDA CRAWFORD	C		LB	13.00	
040348	01/22/2020	08056		PMT FOR PASSPORT/AC	WILLIAM BAINBRIDGE	C		AC	35.00	
040349	01/22/2020	24941	ROGERS, SHEENA SARIE	FILING FEE/CITATION FEE/D	ATTY ELROD	D	FT#12509543404	DH	8.00	
040350	01/22/2020	24395	BAVES, TROY ALLEN	FILING FEE/PETITION TO MO	ATTY ELROD	D	FT#12509543404	DH	23.00	
040351	01/22/2020	24154	PAYTON, ANN	FILING FEE/COUNTERPETITIO	AMY BYTHEWOOD	D	FT#12509543404	DH	70.00	
040352	01/22/2020	25258	HBEISELBETZ, RYAN GORDON	EFILING FEE FOR TRO/AC	ATTY LAINE	D	12509543404	AC	96.00	
040353	01/23/2020	08057		TWO APPLICATION FOR PASSP	MICHAEL MCCOLLUM	C		DH	70.00	
040354	01/23/2020	08058		PMT FOR PASSPORT/AC	LAURANT PINGREE	K	1716	AC	35.00	

RECEIPT	DATE	CASE NUMBER	NAME	DESCRIPTION	PAID BY	TYPE	CHECK #	CLERK	TOTAL PAID	RVSL
040355	01/23/2020	25289	21ST MORTGAGE CORPORATION	E-FILING FEE FOR PLAINTIF	ATTY LITTLEFIELD	D	12514538576	LB	265.00	
040356	01/23/2020	08059		E-FILING FEE FOR COPIES F	ATTY LITTLEFIELD	D	12514538576	LB	14.00	
040357	01/24/2020	08060		APPLICATION FOR PASSPORT/	WILMA GRAY	K	1290	DH	35.00	
040358	01/24/2020	08061		PMT FOR RESEARCH REQUESST	TRUE CORDIS	K	025997	AC	5.00	
040359	01/24/2020	23679	COOPER, DAMEYEN D	EFILING FEE FOR PET. TO M	ATTY RISINGER	D	12515795546	AC	23.00	
040360	01/24/2020	08063		EFILING FEE FOR COPIES/AC	ATTY RISINGER	D	12515795546	AC	4.00	
040361	01/27/2020	CR12188	MORRIS, JAMIE CHARLES	PMT FOR COURT COST IN FUL	MORRIS, JAMIE CHARLES	O	20907600786	AC	368.00	
040362	01/27/2020	08064		PMT FOR COPY OF DIVORCE D	CAROL SOLTYS	C		AC	11.00	
040363	01/28/2020	08065		PMT FOR COPIES 23,768/AC	MASON WILLIAMS	C		AC	15.00	
040364	01/28/2020	08066		PMT FOR RESEARCH REQUEST	TRUE CORDIS	K	026018	AC	30.00	
040365	01/28/2020	B-2851	WILLIS, CHARLES A.	PARTIAL PAYMENT ON COURT	WILLIS, CHARLES A.	C		RC	20.00	
040366	01/28/2020	08067		(2) APPLICATION FOR PASSEPO	JOHN COOLEY JR	C		DH	70.00	
040367	01/28/2020	25054	LOCY, CODY LEE	FILING FEE/PETITION TO MO	ATTY TRAVIS EATON	D	FT#12518317817	DH	31.00	
040368	01/28/2020	08068		FILING FEE/COPIES/#25,054	ATTY TRAVIS EATON	D	FT#12518317817	DH	13.00	
040369	01/29/2020	CR11221	BENTE, JEREMY PAUL	PARTIAL OMT ON COURT COST	BENTE, JEREMY PAUL	O	20890421048	AC	30.00	
040370	01/29/2020	25253	FIVE POINT CREDIT UNION	E-FILING FEE FOR ISSUANCE	ATTY T BRENT	D	12522102275	LB	176.00	
040371	01/30/2020	08069		PAYMENT FOR PASSPORT/LB	CECELIA PARKER	K	950	LB	35.00	
040372	01/30/2020	08070		COPIES/#21,816/DH	LINDSEY BERGSTROM	C		DH	25.00	
040373	01/30/2020	25294	CURBELLIO, BEVERLY JUNE	E-FILING FEE FOR ORIGINAL	ATTY BRAD ELROD	D	12523369895	LB	271.00	
040374	01/30/2020	25295	DISCOVER BANK	E-FILING FEE FOR PLAINTIF	ATTY CHIDI OHA	D	12523369895	LB	265.00	
040375	01/30/2020	08071		E-FILING FEE FOR COPIES F	ATTY CHIDI OHA	D	12523369895	LB	3.00	
040376	01/31/2020	25298	GILMORE, WILLIAM RAY JR.	PMT FOR ORIGINAL PETITION	GILMORE, WILLIAM RAY	C		AC	263.00	
040377	01/31/2020	CR13543	MURRAY, JAMES RANDALL	PARTIAL PMT ON COURT COST	MURRAY, JAMES RANDALL	O	26261513820	AC	45.00	
									TOTAL COLLECTED	10,359.00
									LESS REFUNDS	.00
									TOTAL LIABILITY	10,359.00
TOTAL RECEIPTS COUNT		107								

CAS123 RUN ON 02/10/2020 14:15
01/01/2020 THRU 01/31/2020

COLLECTIONS + DIRECT DEPOSIT FOR DISTRICT CLERK

PAGE 4
REPORT FORMAT: ALL

PAYMENT TYPE		POSTING CLERK	
K	2,289.00	AC	5,713.00
O	948.00	DH	2,123.00
C	1,441.00	LB	2,503.00
D	5,716.00	RC	20.00
R	35.00		00

Texas



Western Surety Company

OFFICIAL BOND AND OATH

THE STATE OF TEXAS }
County of Tyler } ss

KNOW ALL PERSONS BY THESE PRESENTS: BOND No. 68998376

That we, Lynnette Cruse, as Principal, and WESTERN SURETY COMPANY, a corporation duly licensed to do business in the State of Texas, as Surety, are held and bound unto ¹Commissioners Court, his successors in office, in the sum of ²Twenty-Three Thousand Five Hundred and 00/100 DOLLARS (\$23,500.00), for the payment of which we hereby bind ourselves and our heirs, executors and administrators, jointly and severally, by these presents.

Dated this 13th day of January, 2020

THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, That whereas, the above bounden Principal was on the _____ day of _____, _____, duly elected (Elected—Appointed) to the office of Tax Assessor/Collector in and for ³Tyler County, State of Texas, for a term of one year commencing on the 20th day of April, 2020

NOW THEREFORE, if the said Principal shall well and faithfully perform and discharge all the duties required of him by law as the aforesaid officer, and shall ⁴ faithful performance of the person's duties as assessor-collector.

then this obligation to be void, otherwise to remain in full force and effect.

PROVIDED, HOWEVER, that regardless of the number of years this bond may remain in force and the number of claims which may be made against this bond, the liability of the Surety shall not be cumulative and the aggregate liability of the Surety for any and all claims, suits, or actions under this bond shall not exceed the amount stated above. Any revision of the bond amount shall not be cumulative.

PROVIDED, FURTHER, that this bond may be cancelled by the Surety by sending written notice to the party to whom this bond is payable stating that, not less than thirty (30) days thereafter, the Surety's liability hereunder shall terminate as to subsequent acts of the Principal.

Lynnette Cruse Principal
WESTERN SURETY COMPANY
By Paul T. Buflat
Paul T. Buflat, Vice President

ACKNOWLEDGMENT OF PRINCIPAL

THE STATE OF TEXAS


County of TYLER

} ss

Before me, Diana Rasberry LYNNETTE CRUSE on this day, personally appeared

the foregoing instrument and acknowledged to me that he executed the same for the purposes and consideration therein expressed.

Given under my hand and seal of office at Tyler County, Texas, this 20th day of February, 2020.



SEAL

Diana Rasberry

TYLER County, Texas

OATH OF OFFICE (COUNTY COMMISSIONERS and COUNTY JUDGE)

I, do solemnly swear (or affirm) that I will faithfully execute the duties of the office of, of the State of Texas, and will to the best of my ability preserve, protect, and defend the Constitution and laws of the United States and of this State; and I furthermore solemnly swear (or affirm) that I have not directly nor indirectly paid, offered, or promised to pay, contributed, nor promised to contribute any money, or valuable thing, or promised any public office or employment, as a reward for the giving or withholding a vote at the election at which I was elected; and I furthermore solemnly swear (or affirm) that I will not be, directly or indirectly, interested in any contract with or claim against the County, except such contracts or claims as are expressly authorized by law and except such warrants as may issue to me as fees of office. So help me God.

Signed

Sworn to and subscribed before me at, Texas, this day of

SEAL

County, Texas


OATH OF OFFICE (General)

I, LYNNETTE CRUSE, do solemnly swear (or affirm) that I will faithfully execute the duties of the office of TAX ASSESSOR/COLLECTOR, of the State of Texas, and will to the best of my ability preserve, protect, and defend the Constitution and laws of the United States and of this State; and I furthermore solemnly swear (or affirm) that I have not directly nor indirectly paid, offered, or promised to pay, contributed, nor promised to contribute any money, or valuable thing, or promised any public office or employment, as a reward for the giving or withholding a vote at the election at which I was elected. So help me God.

Signed Lynnette Cruse

Sworn to and subscribed before me at Tyler County, Texas, this 20th day of February, 2020.

Diana Rasberry



SEAL

TYLER County, Texas

Western Surety Company

POWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS:

That WESTERN SURETY COMPANY, a corporation organized and existing under the laws of the State of South Dakota, and authorized and licensed to do business in the States of Alabama, Alaska, Arizona, Arkansas, California, Colorado, Connecticut, Delaware, District of Columbia, Florida, Georgia, Hawaii, Idaho, Illinois, Indiana, Iowa, Kansas, Kentucky, Louisiana, Maine, Maryland, Massachusetts, Michigan, Minnesota, Mississippi, Missouri, Montana, Nebraska, Nevada, New Hampshire, New Jersey, New Mexico, New York, North Carolina, North Dakota, Ohio, Oklahoma, Oregon, Pennsylvania, Rhode Island, South Carolina, South Dakota, Tennessee, Texas, Utah, Vermont, Virginia, Washington, West Virginia, Wisconsin, Wyoming, and the United States of America, does hereby make, constitute and appoint

Paul T. Bruflat of Sioux Falls,
State of South Dakota, its regularly elected Vice President,
as Attorney-in-Fact, with full power and authority hereby conferred upon him to sign, execute, acknowledge and deliver for and on its behalf as Surety and as its act and deed, the following bond:

One Tax Assessor/Collector County of Tyler

bond with bond number 68998376

for Lynnette Cruse

as Principal in the penalty amount not to exceed: \$23,500.00

Western Surety Company further certifies that the following is a true and exact copy of Section 7 of the by-laws of Western Surety Company duly adopted and now in force, to-wit:

Section 7. All bonds, policies, undertakings, Powers of Attorney, or other obligations of the corporation shall be executed in the corporate name of the Company by the President, Secretary, any Assistant Secretary, Treasurer, or any Vice President, or by such other officers as the Board of Directors may authorize. The President, any Vice President, Secretary, any Assistant Secretary, or the Treasurer may appoint Attorneys-in-Fact or agents who shall have authority to issue bonds, policies, or undertakings in the name of the Company. The corporate seal is not necessary for the validity of any bonds, policies, undertakings, Powers of Attorney or other obligations of the corporation. The signature of any such officer and the corporate seal may be printed by facsimile.

In Witness Whereof, the said WESTERN SURETY COMPANY has caused these presents to be executed by its Vice President with the corporate seal affixed this 13th day of January, 2020.

ATTEST

A. Vietor

A. Vietor, Assistant Secretary


WESTERN SURETY COMPANY

By

Paul T. Bruflat

Paul T. Bruflat, Vice President

STATE OF SOUTH DAKOTA }
COUNTY OF MINNEHAHA } ss



On this 13th day of January, 2020, before me, a Notary Public, personally appeared Paul T. Bruflat and A. Vietor

who, being by me duly sworn, acknowledged that they signed the above Power of Attorney as Vice President and Assistant Secretary, respectively, of the said WESTERN SURETY COMPANY, and acknowledged said instrument to be the voluntary act and deed of said Corporation.



P. Dahl

My Commission Expires June 18, 2025

Notary Public



OFFICIAL BOND REQUIREMENTS - continue

County Assessor-Collector (County Bond)	Equal to 10% of the total amount of county taxes imposed in the preceeding tax year, \$100,000 maximum	Commissioners Court	Commissioners Court	Tax Code 6.28	"faithful performance of the person's duties as assessor-collector."
County Commissioner	\$3,000.	County Treasurer	County Judge	Local Gov't Code 81.002	"faithfully perform the commissioner's official duties and reimburse the county for all county funds illegally paid to him and will not vote or consent to make a payment of county funds except for a lawful purpose."
Justice of the Peace	\$5,000 maximum	County Judge	Not Specified	Gov't Code 27.001	"faithfully and impartially discharge the duties required by law and promptly pay to the entitled party all money that comes into his hands during the term of office."
Constable	Set by the Commissioners Court \$500 minimum — \$1,500 maximum	The Governor and the Governor's successors in office	Commissioners Court	Local Gov't Code 86.002	"faithfully perform the duties imposed by law."
County Public Weigher and Deputies	\$2,500	County Judge	Department of Agriculture	Agric. Code 13.256	"accurately weigh or measure commodities reflected on certificates issued by him, protect the commodities that he is registered to weigh or measure, and comply with all laws and rules governing public weighers."
State Public Weigher	\$10,000	State of Texas	Department of Agriculture	Agric. Code 13.256	"accurately weigh or measure commodities reflected on certificates issued by him, protect the commodities that he is registered to weigh or measure, and comply with all laws and rules governing public weighers."

3. If precinct insert the number.
4. Conditions.

OFFICIAL BOND REQUIREMENTS - continue

County Assessor-Collector (County Bond)	Equal to 10% of the total amount of county taxes imposed in the preceeding tax year, \$100,000 maximum	Commissioners Court	Commissioners Court	Tax Code 6.28	"faithful performance of the person's duties as assessor-collector."
County Commissioner	\$3,000.	County Treasurer	County Judge	Local Gov't Code 81.002	"faithfully perform the commissioner's official duties and reimburse the county for all county funds illegally paid to him and will not vote or consent to make a payment of county funds except for a lawful purpose."
Justice of the Peace	\$5,000 maximum	County Judge	Not Specified	Gov't Code 27.001	"faithfully and impartially discharge the duties required by law and promptly pay to the entitled party all money that comes into his hands during the term of office."
Constable	Set by the Commissioners Court \$500 minimum — \$1,500 maximum	The Governor and the Governor's successors in office	Commissioners Court	Local Gov't Code 86.002	"faithfully perform the duties imposed by law."
County Public Weigher and Deputies	\$2,500	County Judge	Department of Agriculture	Agric. Code 13.256	"accurately weigh or measure commodities reflected on certificates issued by him, protect the commodities that he is registered to weigh or measure, and comply with all laws and rules governing public weighers."
State Public Weigher	\$10,000	State of Texas	Department of Agriculture	Agric. Code 13.256	"accurately weigh or measure commodities reflected on certificates issued by him, protect the commodities that he is registered to weigh or measure, and comply with all laws and rules governing public weighers."

3. If precinct insert the number.
4. Conditions.

THE STATE OF TEXAS }
County of TYLER } ss

The foregoing bond of LYNNETTE CRUSE as
TAX ASSESSOR/COLLECTOR in and for TYLER County and State of Texas, this day
approved in open Commissioner's Court.

ATTEST:

Date 02-24-20

Donece Gregory
By *Dean Lewis* Chief Deputy
County Court TYLER County

Jacqueline B. Blanchette
County Judge,
TYLER County, Texas

THE STATE OF TEXAS }
County of TYLER } ss

I, DONECE GREGORY, County Clerk, in and for said County, do hereby certify
that the foregoing Bond dated the 13th day of January, 2020, with its certificates of
authentication, was filed for record in my office the 24th day of February, 2020, at
12:00 o'clock P. M., and duly recorded the 24th day of February, 2020, at
4:00 o'clock P. M., in the Records of Official Bonds of said County in Volume _____, on page
_____.

WITNESS my hand and the seal of the County Court of said County, at office in Woodville
Texas, the day and year last above written.

DONECE GREGORY Clerk

By *Dean Lewis* Deputy
County Court Tyler County

County Court Tyler County

ACKNOWLEDGMENT OF SURETY
(Corporate Officer)

STATE OF SOUTH DAKOTA }
County of Minnehaha } ss

Before me, a Notary Public, in and for said County and State on this 13th day of January,
2020, personally appeared Paul T. Bruflat to me known to be the identical
person who subscribed the name of WESTERN SURETY COMPANY, Surety, to the foregoing instrument as the
aforesaid officer and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the
free and voluntary act and deed of such corporation for the uses and purposes therein set forth.



P. Dahl
Notary Public

My Commission Expires June 18, 2025


OFFICIAL BOND REQUIREMENTS

OFFICIAL	2. AMOUNT	1. TO WHOM PAYABLE	APPROVED BY	Sec. of Statutes	4. CONDITIONS
District Attorney	\$5,000.	Governor	District Judge	Gov't Code 43.002	" , in the manner prescribed by law, faithfully pay over all money that he collects or that comes into his hands for the state or a county."
County Attorney	\$2,500.	Governor	Commissioners Court	Gov't Code 45.001	"faithfully pay over in the manner prescribed by law all money that he collects or receives for any county or the state."
County Judge	\$1,000.- 10,000.	County Treasurer	Commissioners Court	Gov't Code 26.001	"pay all money that comes into his hands as county judge to the person or officer entitled to it; pay to the county all money illegally paid to him out of county funds; and not vote or consent to pay out county funds for other than lawful purposes."
County Clerk	At least 20% of the maximum amount of fees collected in any year during the term of office preceding the term for which the bond is given — \$5,000 minimum, \$500,000 maximum	County	Commissioners Court	Local Gov't Code 82.001	"faithfully perform the duties of office."
Deputy County Clerk	At least 20% of the maximum amount of fees collected in any year during the term of office preceding the term for which the bond is given — \$5,000 minimum, \$500,000 maximum	County for the use and benefit of the County Clerk	Commissioners Court	Local Gov't Code 82.002	"faithfully perform the duties of office."
County Auditor	\$5,000 minimum	District Judge(s)	District Judge(s)	Local Gov't Code 84.007	"faithfully perform the duties of county auditor."
County Treasurer	Established by the commissioners court not to exceed one-half of one percent of the largest amount budgeted for general county maintenance and operations for any fiscal year of the county beginning during the term of office preceding the term for which the bond is to be given — \$5,000 minimum, \$500,000 maximum	County Judge	Commissioners Court	Local Gov't Code 83.002	"faithfully execute the duties of office."
District Clerk	Not less than 20% of the maximum amount of fees collected in any year during the term of office immediately preceding the term for which the bond is given — \$5,000 minimum, \$100,000 maximum	Governor	Commissioners Court	Gov't Code 51.302	"faithfully perform the duties of the office."
Deputy District Clerk	Not less than 20% of the maximum amount of fees collected in any year during the term of office immediately preceding the term for which the bond is given — \$5,000 minimum, \$100,000 maximum	Governor for the use and benefit of the District Clerk	Commissioners Court	Gov't Code 51.309	"faithfully perform the duties of the office."
County School Superintendent	\$1,000.	County governing board unless a county-wide independent school district has been created, in which event the bond is payable to and approved by the County Commissioners Court		Educ. Code 17.49	"faithfully perform his duties."
County Surveyor	Fixed by the Commissioners Court — \$500 minimum, \$10,000 maximum	Not Specified		Nat. Res. Code 23.013	"faithfully perform the duties of the office."
Deputy County Surveyor	Not less than \$500 nor more than \$10,000 (Fixed by the County Surveyor)	County Surveyor		Nat. Res. Code 23.014	"faithfully perform the duties of the office."
Sheriff	Set by the Commissioners Court \$5,000 minimum, \$30,000 maximum	Governor	Commissioners Court	Local Gov't Code 85.001	"faithfully perform the duties of office established by law; account for and pay to the person authorized by law to receive them the fines, forfeitures, and penalties the sheriff collects for the use of the state or a county; execute and return when due the process and precepts lawfully directed to the sheriff, and pay to the person to whom they are due or to the person's attorney the funds collected by virtue of the process or precept; and pay to the county any funds illegally paid, voluntarily or otherwise, to the sheriff from county funds."
County Assessor-Collector (State Bond)	Equal to 5% of the net state collections from motor vehicle sales and use taxes and motor vehicle registration fees in the county during the year ending August 31 preceding the date the bond is given — \$2,500 minimum, \$100,000 maximum	The Governor and the Governor's successors in office	Commissioners Court and the State Comptroller of Public Accounts	Tax Code 6.28	"faithful performance of the person's duties as assessor-collector."

From: Eckels, Robert <Robert.Eckels@huschblackwell.com>
Sent: Wednesday, February 12, 2020 3:25 PM
To: judge@co.tyler.tx.us
Cc: David, Kate; De Leon, Elizabeth
Subject: SE TX Flood Control District Revised Articles of Incorporation
Attachments: SE TX Flod Control Dist C Clerk VERIFICATION Tyler County.docx; SE TX Flood Control Dist Revised Resolution- Tyler County.docx; SETFCD Articles of Incorporation 02072020.docx; Agenda Item for posting creating SE Texas Flood Control District Inc 4811-8127-5309 v.1.docx

Judge

Attached are revised Articles of Incorporation based on our discussions at the meeting. The drainage and other district board appointments are moved from the commissioners courts to be "ex officio" appointments by the board. This will allow more flexibility for the Board to add or replace members as needed. Other changes include listing the incorporators in the form of the Articles of Incorporation and removal of IRS Code Sec 103 language relating to bond issuance we did not need. We also added language to address the comments of the TWDB relating to representing the sponsors in finance and grant applications.

 This will need to be approved at your earliest convenience at a meeting of the commissioners court as was done for the earlier version.

Attached are copies as Word Documents of the Articles of Incorporation, Resolution of the Commissioners Court, County Clerk Verification and Posting Notice.

We can use the earlier signature pages from the incorporators.

As always, please let me know if you need additional information.

RAE

Robert A. Eckels

HUSCH BLACKWELL LLP
600 Travis Street,
Suite 2350
Houston, TX 77002
Direct: 713.525.6223
Fax: 713.647.6884
Robert.Eckels@huschblackwell.com
huschblackwell.com
[View Bio](#) | [View VCard](#)

obligation of the Corporation shall constitute an obligation of the Commissioners Court or the Sponsor or a pledge of the faith or credit of the Sponsor; and

WHEREAS, the meeting at which the Commissioners Court adopted the Articles of Incorporation was open to the public as required and that public notice of the time, place, and purpose of said meeting was given as required by the Open Meetings Act, Chapter 551, Texas Government Code; and

WHEREAS, the Commissioners Court finds that formation of the Corporation in accordance with the articles approved by the Commissioners Court serves a public purpose of Tyler County, Texas;

NOW, THEREFORE, BE IT RESOLVED BY THE TYLER COUNTY COMMISSIONERS COURT, THAT:

1. The Tyler County Commissioners Court hereby APPROVES the formation of the 'Southeast Texas Flood Control District, LGC' under authority of Subchapter D, Texas Transportation Corporation Act, TEX. TRANSP. CODE ANN. § 431.101 *et seq.* and Texas Local Government Code Ann § 394.001 *et seq.* and the Texas Nonprofit Corporation Act Article § 1396-101 *et seq.*, TEXAS REV. CIV. STAT. ANN., as amended, to act on behalf of the Sponsor and other Texas local governments; and

2. The Tyler County Commissioners Court hereby APPROVES and authorizes the form of the Articles of Incorporation of the Corporation attached hereto and incorporated herein for all purposes, and has determined that the approval of these forms is wise, expedient, necessary and desirable;

3. The County Judge is hereby authorized to execute the Articles of Incorporation of the Corporation and all related documents on behalf of Tyler County, Texas. The County Clerk is hereby authorized to attest to all such signatures, affix the seal of the County to all such documents and verify that the Tyler County Commissioners Court has approved same;

4. The Tyler County Commissioners Court hereby grants the authority necessary for the County Judge, as a director of the Corporation, to approve the adoption of the Articles of Incorporation in the form attached hereto; and

5. The Tyler County Commissioners Court hereby appoints the director of the Corporation for which Tyler County, Texas is the sponsor, as set forth in the Articles of Incorporation of the Corporation.

Upon Motion Duly Made and Seconded, the above Resolution is hereby ADOPTED,
by the Commissioners Court of Tyler County, on this, the 24th day of February, 2019.
2020


COUNTY OF TYLER, TEXAS, By:


JACQUES L. BLANCHETTE
COUNTY JUDGE

MARTIN NASH
COMMISSIONER, PRECINCT NO.1



STEVAN STURROCK
COMMISSIONER, PRECINCT NO.2




MIKE MARSHALL
COMMISSIONER, PRECINCT NO.3



CHARLES "BUCK" HUDSON
COMMISSIONER, PRECINCT NO.4

ATTEST:



DONECE GREGORY *Chief Deputy*
COUNTY CLERK OF TYLER COUNTY, TEXAS

VERIFICATION

BEFORE ME, the undersigned authority, personally appeared Donece Gregory, Tyler County Clerk, known to me to be the person whose name is subscribed below, who, after being by me duly sworn, upon her oath, did depose and say that she is the County Clerk of Tyler County, Texas; that she has examined the foregoing Articles of Incorporation of Southeast Texas Flood Control District, LGC and that the same was approved by a majority of the Commissioners Court members in office by Resolution _____, at a meeting of the Commissioners Court of Tyler County, Texas, held on February 24, 2020, and as such she is duly authorized to make this verification.


Donece Gregory by her hand
Donece Gregory, Tyler County Clerk

STATE OF TEXAS §
 §
COUNTY OF TYLER §

SUBSCRIBED AND SWORN TO BEFORE ME by Donece Gregory, Tyler County Clerk on this 24th day of February, 2020.

Carolyn J. Davis
Notary Public in and for the State of Texas

Carolyn J. Davis
(Stamped or Printed Name of Notary)



08-28-2023
My Commission Expires:

**ARTICLES OF INCORPORATION
OF
SOUTHEAST TEXAS FLOOD CONTROL DISTRICT, LGC**

Pursuant to Texas Local Government Code § 394.014, the Texas Nonprofit Corporation Act Article § 1396-101 *et seq.*, and Subchapter D of Chapter 431, Texas Transportation Code (The Act), with the approval of a majority vote of the governing body's members in office of the Texas counties of Jefferson County, Hardin County, Orange County, Jasper County, Newton County, Chambers County, Tyler County, and Liberty County (the "Sponsors"), We, the undersigned natural persons, each of whom is at least 18 years of age and a resident and qualified voter of his respective Sponsor and a citizen of the State of Texas, acting as incorporators of a corporation do adopt these Articles of Incorporation of the Southeast Texas Flood Control District, LGC.

ARTICLE ONE

NAME

The name of the Corporation is the Southeast Texas Flood Control District, LGC.

ARTICLE TWO

CHARACTER

The Corporation is a public, nonprofit local government corporation.

ARTICLE THREE

DURATION

The period of duration of the Corporation is perpetual.

ARTICLE FOUR

PURPOSE

The Corporation is formed solely to carry out the purposes of the authorizing Act and is created pursuant to Subchapter D, Texas Transportation Corporation Act, TEX. TRANSP. CODE ANN. § 431.101 *et seq.* and Texas Local Government Code Ann § 394.001 *et seq.* and the Texas Nonprofit Corporation Act Article § 1396-101 *et seq.*, TEXAS REV. CIV. STAT. ANN., as amended, which authorize the Corporation to assist and act on behalf of the Sponsors and to engage in activities in the furtherance of the purposes for its creation.

The Corporation is organized and is to be operated to aid, assist and act on behalf of the Sponsors: (a) to engage in coordinated planning with governmental entities and local communities concerning disaster mitigation and other projects or programs to protect residents, infrastructure, industry, businesses and housing within the boundaries of the Sponsors and watersheds impact areas within the boundaries of the sponsors. against flooding; (b) to apply for available financial assistance, funding and grants for the benefit of the Sponsors; (c) to design, develop, construct, operate, manage, repair, maintain, finance, equip, improve, enlarge, extend, acquire and improve integrated flood damage reduction systems within the boundaries of the Sponsors; and (d) to conduct any and all other lawful business and perform any other function or operation related to any of the foregoing. Flood damage reduction systems may include stormwater detention, drainage facilities, bulkheads,

levees, seawalls, berms, barriers, pumps, gates and other structural, nonstructural or nature-based systems to suppress flooding and storm surge or reduce rainfall and storm surge-related flood damage. Those systems may also include ancillary improvements, such as measures to protect and improve the quality of storm water or mitigate environmental effects; paved, macadamized or graveled roads; demolition of improvements or clearing of land; highway right-of-way improvements or beautification measures; utility relocation; hiking and cycling paths or sidewalks; beach replenishment measures; and parks or open space improvements.

The Corporation shall have all other powers of a like or different nature not prohibited by law which are available to nonprofit and local government corporations in Texas and which are necessary or useful to enable the Corporation to perform the purposes for which it is created.

The Corporation is created as a local government corporation pursuant to the Act and shall be a governmental unit within the meaning of Chapter 101, Texas Civil Practice and Remedies Code. The operations of the Corporation are governmental and not proprietary functions.

ARTICLE FIVE

MEMBERS

The Corporation shall have no members and no stock.

ARTICLE SIX

INITIAL REGISTERED OFFICE AND AGENT

The street address of the initial registered office of the Corporation is 1149 Pearl St., 4th Floor, Beaumont, Texas 77701. The name of the initial registered agent of the Corporation at that address is Judge Jeff Branick.

ARTICLE SEVEN

DIRECTORS AND VOTING

All powers of the Corporation shall be vested in a Board of Directors ("Board") consisting of eight (8) persons. Each Sponsor shall appoint one (1) Director. The initial Directors listed below shall serve for the term expiring three years from the date of filing of these Articles of Incorporation. Subsequent appointments shall be made by the Commissioners Court of each Sponsor, with each Director serving a three (3) year term. Any Director may be removed from office at any time, by the respective Commissioners Court who appointed them. Each Commissioners Court shall have the right to appoint a replacement for such removed Director. Any removal by a Commissioners Court shall be effective immediately and that Commissioners Court shall appoint a replacement within sixty (60) days following removal. In the event a Director is not appointed by the Commissioners Court, the County Judge shall serve as the Director for that Sponsor.

The Board may appoint non-voting "Ex Officio" members to the Board as provided in the Bylaws.

To be qualified to serve as a Director, a person must be at least eighteen (18) years old and reside within the boundaries of his appointing Sponsor.

All matters pertaining to the internal affairs of the Corporation shall be governed by the Bylaws of the Corporation, so long as such Bylaws are not inconsistent with these Articles of Incorporation and the laws of the State of Texas.

The names and addresses of the persons who are to serve as the initial Directors are as follows, each of whom resides within the boundaries of the Sponsors:

Jeff Branick
1149 Pearl Street, 4th Floor
Beaumont, Texas 77701
Jefferson County

Kenneth Weeks
110 Court Street, Room 125
Newton, Texas 75966
Newton County

Wayne McDaniel
300 West Monroe Street
Kountze, Texas 77625
Hardin County

Jimmy Sylvia
PO Box 939
Anahuac, Texas 77514
Chambers County

John Gothia
123 South 6th Street
Orange, Texas 77630
Orange County

Jacques L. Blanchette
100 W Bluff Street
Woodville Texas 75979
Tyler County

Mark Allen
121 N Austin Street, Room 106
Jasper, Texas 75951
Jasper County

Jay H. Knight
1923 Sam Houston Street
Liberty, Texas 77575
Liberty County

ARTICLE EIGHT

INDEMNIFICATION AND RELEASE

To the maximum extent authorized by applicable law, the Corporation shall indemnify each director, officer, former director, and former officer of the Corporation for expenses and costs, including attorney's fees, actually and necessarily incurred by the director or officer in connection with, and each such person is released by the Corporation from, a claim asserted against the director or officer, by action in court or other forum, because of the person's being or having been a director or officer.

ARTICLE NINE

NOT FOR PROFIT

No part of the Corporation's net earnings shall inure to the benefit of, or be distributable to, any director, officer, or other private person, but the Corporation may pay reasonable compensation for services rendered or property acquired. No part of the Corporation's net earnings remaining after payment of its liabilities and expenses in accomplishing its public purpose may benefit any person other than the Sponsors.

No substantial part of the Corporation's activities shall be carrying on propaganda or otherwise attempting to influence legislation. The Corporation shall not participate in, or intervene

(including by publishing or distributing of statements) in, any political campaign on behalf of or in opposition to any candidate for public office.

ARTICLE TEN

SPONSOR

The counties set forth below are the Sponsors of the Corporation. Each Sponsor has adopted a resolution approving the form of these Articles of Incorporation by a majority vote of its Commissioners Court, as follows:

Sponsor	Date of Adoption
Jefferson County	_____
Hardin County	_____
Orange County	_____
Jasper County	_____
Newton County	_____
Chambers County	_____
Tyler County	<u>2/24/20</u>
Liberty County	_____

ARTICLE ELEVEN

INCORPORATORS

The names and addresses of the incorporators, each of whom resides within the boundaries of the Corporation and the respective sponsor are:

Laurie Ardoin
8385 Edgar Park Dr
Orange TX 77630
Orange County

Jacques L. Blanchette
100 West Bluff St. 105
Woodville TX 75979
Tyler County

Ken Jobe
201 Veterans Way
Woodville TX 75979
Tyler County

Miranne Pruett
1400 Shadowdale St
Bridge City TX 77611
Orange County

Mike Marshall
205 N Charlton
Woodville TX 75979
Tyler County

Kenneth Weeks
110 E Court St
Newton TX 75966
Newton County

Jeannine Denman
7503 Circle 2
Orange TX 777632
Orange County

Charles "Buck" Hudson
202 N Charlton
Woodville TX 75979
Tyler County

Philip White
110 E Court St
Newton TX 75966
Newton County

William L. Fuller
110 E Court St.
Newton TX 75966
Newton County

Wayne McDaniel
300 W Monroe St
Kountze TX 77625
Hardin County

L.W. Cooper, Jr
PO Box 1757
Silsbee TX 77656
Hardin County

Chris Kirkendall
PO Box 1436
Kountze TX 77625
Hardin County

Ken Pelt
PO Box 550
Sour Lake TX 77659
Hardin County

Alvin Roberts
PO Box 8166
Lumberton TX 77657
Hardin County

Mark W. Allen
121 N Austin St, Room 106
Jasper TX 77951
Jasper County

Charles Shofner, Jr.
121 N Austin St, Room 106
Jasper TX 77951
Jasper County

Roy Parker
121 N Austin St, Room 106
Jasper TX 77951
Jasper County

Willie Stark
121 N Austin St, Room 106
Jasper TX 77951
Jasper County

Vance Moss
121 N Austin St, Room 106
Jasper TX 77951
Jasper County

Lauren VanDeventer
PO Box 939
Anahuac TX 77514
Chambers County

Aaron Thomas
PO Box 939
Anahuac TX 77514
Chambers County

Jimmy Sylvia
PO Box 939
Anahuac TX 77514
Chambers County

Jeff Branick
1149 Pearl St, 4th Floor
Beaumont TX 77701
Jefferson County

Eddie Arnold
1149 Pearl St, 4th Floor
Beaumont TX 77701
Jefferson County

Brent A. Weaver
1149 Pearl St, 4th Floor
Beaumont TX 77701
Jefferson County

Michael S. Sinegal
1149 Pearl St, 4th Floor
Beaumont TX 77701
Jefferson County

Everette "Bo" Alfred
1149 Pearl St, 4th Floor
Beaumont TX 77701
Jefferson County

Jay H. Knight
1923 Sam Houston St
Liberty TX 77575
Liberty County

Bruce Karbowski
1923 Sam Houston St
Liberty TX 77575
Liberty County

Greg Arthur
PO Box 77
Hardin TX 77561
Liberty County

James Reaves
119 Fenner Ave.
Cleveland TX 77327
Liberty County

Leon Wilson
PO Box 88
Dayton TX 77535
Liberty County

ARTICLE TWELVE

AMENDMENTS

These Articles of Incorporation may not be changed or amended unless approved by the Commissioners Court of each of the Sponsors.

ARTICLE THIRTEEN

DISSOLUTION

Subject to any restrictions in applicable state law, if each of the Sponsors considers and approves a resolution directing the Board to proceed with dissolution or if the Board determines by resolution that the purposes for which the Corporation was formed have been substantially met and all the obligations incurred by the Corporation or on behalf of the Corporation have been fully paid, the Board shall execute a certificate of dissolution to that effect and declare the Corporation dissolved in accordance with the requirements of Section 394.026 of the Texas Local Government Code, or with applicable law.

Upon dissolution of the Corporation:

A. the assets of the Corporation shall be distributed among the Sponsors in accordance with the percentage of each Sponsor's contribution to the purchase of the assets of the Corporation; and

B. any remaining liabilities of the Corporation shall be allocated as follows:

(1) if the liability was incurred for the benefit of fewer than all of the Sponsors, the liability shall be allocated to those Sponsors for whom the benefit was incurred based on the agreement of the benefitted Sponsors; and

(2) if the liability was incurred for the benefit of all the Sponsors, the liability shall be based on the percentage of the each Sponsor's contributions to the purchase of the assets of the Corporation.


Nothing in this Certificate shall prohibit the Sponsors from agreeing to an allocation of assets and liabilities contrary to this Article, provided such allocation is not contrary to state law.

EFFECTIVENESS OF FILING

This document becomes effective upon filing by the Secretary of State.

EXECUTION

The undersigned affirms that the person designated as registered agent has consented to the appointment. The undersigned signs this document subject to the penalties imposed by law for the submission of a materially false or fraudulent instrument and certifies under penalty of perjury that the undersigned is authorized to execute the filing instrument.



State and Local Fair Market Value Lease

Agreement Number														

Your Business Information

Full Legal Name of Lessee / DBA Name of Lessee TYLER COUNTY CLERK OFFICE	Tax ID # (FEIN/TIN) 746002576
--	---

Sold-To: Address
116 S CHARLTON ST, WOODVILLE, TX, 75979-5210, US

Sold-To: Contact Name Jackie Skinner	Sold-To: Contact Phone # (409) 283-3652	Sold-To: Account # 0012933208
--	---	---

Bill-To: Address
116 S CHARLTON ST, WOODVILLE, TX, 75979-5210, US

Bill-To: Contact Name Jackie Skinner	Bill-To: Contact Phone # (409) 283-3652	Bill-To: Account # 0012933208	Bill-To: Email jskinneraud@co.tyler.tx.us
--	---	---	---

Ship-To: Address
116 S CHARLTON ST, WOODVILLE, TX, 75979-5210, US

Ship-To: Contact Name Donece Gregory	Ship-To: Contact Phone # (409) 283-2281	Ship-To: Account # 0012933208
--	---	---

PO #

Your Business Needs

Qty	Item	Business Solution Description
1	DM400C	DM400C Digital Mailing System
1	1FAE	Basic Accounting -50 Accounts
1	1FY9	DM400 70 LPM
1	1GW5	5lb Integrated Weighing Feature
1	4CES	DM400C Base U.S. ES2
1	G900	Meter for DM300/DM400/475 Series
1	G9SS	USPS Tracking Services Activation
1	ME1B	Meter Equipment - DM400
1	MP9G	Integrated Weighing Platform
1	SBTA	DM400C Digital Meter System
1	SJ40	SoftGuard for DM400
1	STDSLA	Standard SLA-Equipment Service Agreement (for DM400C Digital Mailing System)

Your Payment Plan

Initial Term: 60 months	Initial Payment Amount:	
Number of Months	Monthly Amount	Billed Quarterly at*
60	\$ 156.35	\$ 469.05

*Does not include any applicable sales, use, or property taxes which will be billed separately.

- Tax Exempt Certificate Attached
- Tax Exempt Certificate Not Required
- Purchase Power® transaction fees included
- Purchase Power® transaction fees extra

Your Signature Below

Non-Appropriations. You warrant that you have funds available to make all payments until the end of your current fiscal period, and shall use your best efforts to obtain funds to make all payments in each subsequent fiscal period through the end of your Lease Term. If your appropriation request to your legislative body, or funding authority ("Governing Body") for funds to make the payments is denied, you may terminate this Lease on the last day of the fiscal period for which funds have been appropriated, upon (i) submission of documentation reasonably satisfactory to us evidencing the Governing Body's denial of an appropriation sufficient to continue this Lease for the next succeeding fiscal period, and (ii) satisfaction of all charges and obligations under this Lease incurred through the end of the fiscal period for which funds have been appropriated, including the return of the equipment at your expense.

By signing below, you agree to be bound by all the terms and conditions of your State's/Entity's/Cooperative's contract, including the Pitney Bowes Terms, which are available at <http://www.pb.com/states> and are incorporated by reference (collectively, this "Agreement"). The terms and conditions of this Agreement will govern this transaction and be binding on us after we have completed our credit and documentation approvals process and have signed below. The lease requires you either provide proof of insurance or participate in the ValueMAX® equipment protection program (see Section L9 of the Pitney Bowes Terms) for an additional fee. If software is included in the Order, additional terms apply which are available by clicking on the hyperlink for that software located at <http://www.pitneybowes.com/us/license-terms-of-use/software-and-subscription-terms-and-conditions.html>. Those additional terms are incorporated by reference.

576-18
 State/Entity's Contract#

Jacques L. Blanchette
 Lessee Signature
 Jacques L. Blanchette
 Print Name
 County Judge
 Title
 02-24-2020
 Date
 judge@co.tyler.tx.us
 Email Address

 Pitney Bowes Signature

 Print Name

 Title

 Date

Sales Information

Lori Damato	lori.damato@pb.com	
Account Rep Name	Email Address	PBGFS Acceptance



Customer Information		Selling Dealer Information	
Date	<u>2/18/2020</u>	Dealership	<u>Texas Document Solutions</u>
Account Name	<u>Tyler County</u>	Account #	<u></u>
Contact	<u>Jackie Skinner</u>	Address	<u>2003 Atkinson Drive</u>
Delivery Address	<u>100 West Bluff</u>	City, State Zip	<u>Lufkin, Texas 75901</u>
City State Zip	<u>Woodville, Texas 75979</u>	Phone	<u>936-699-2800</u>
Phone	<u>409-283-3652</u>	Email	<u>tmccoy@texdocsol.com</u>
Email	<u>jskinner.aud@co.tyler.tx.us</u>		

Purchase Order Information

CUSTOMER PO # _____ DEALER PO # _____
 (MUST be Included)

Model #	Unit Price	Qty	Price Extension
Sharp MX-M6071 B/W Copier		1	\$0.00
MX-DE28N Desk Unit		3	\$0.00
MX-FN30 Staple Finisher		1	\$0.00
MX-RB25N Paper Pass Unit		1	\$0.00
Sharp MX-2651 Color Copier		1	\$0.00
MX-DE25N Desk Unit		3	\$0.00
MX-TU16 Exit Tray		3	\$0.00
Sharp MX-5071 Color Copier		2	\$0.00
MX-FN27N Inner Finisher		2	\$0.00
MX-PN14B Hole Punch		1	\$0.00
MX-FX15 Fax Module		2	\$0.00
MX-TR19N Faxing Exit Tray		2	\$0.00
Sharp MX-M4051 B/W Copier		1	\$0.00
Sharp MX-3051 Color Copier		1	\$0.00
Total:			

DEALER & CUSTOMER SIGNATURE REQUIRED PRIOR TO ORDER PLACEMENT

<u>JACQUES L. BLANCHETTE</u> Customer Printed Name	<u>Tim McCoy</u> Dealer Printed Name
<u>Jacques L. Blanchette</u> Customer Signature & Date <u>2/25/20</u>	<u>X Tim McCoy</u> Dealer Signature & Date <u>2-18-2020</u>

ADDITIONAL INFORMATION

End User PO Attached YES NO
 (Customer signature required if PO isn't attached)

Payment (please select ONE)

Bill End User

Bill Dealer / Certified Channel Reseller

Financed Order

Financed Orders require copies of lease documents. If it is intended for the Lease Company to pay Sharp directly, a Pay Proceeds Document is required. Note that lender is subject to credit approval.

Dealer Ship To information (specify if different from above)

Ship to Dealer Texas Document Solutions City Lufkin State Texas

Acct # _____

Send to: SNAPCustomerService@sharpsec.com
 Questions regarding orders: (201) 529-8824 or bialosukniad@sharpsec.com

Maverick



Communications, Inc.

PO Box 2233 Beaumont TX 77704
 Office: (409) 840-5223 Fax (409)840-5205
 maverickinc.com

Firm Quote

Date:	Estimate Number:
2/7/2020	12502
	Maverick Job No:
	Customer PO No:
	Pending

Submitted To:

Tyler County Courthouse
 Attn: Accounts Payable
 100 West Bluff Street
 Woodville, TX 75979

File Name:	Customer Contact:	
Sheriffs Department Fiber	D. Calhoon	
Job Description:	Quantity:	Total:
<p>This Quote is based on Maverick Communications, Inc. installing a new 12 single-mode fiber cable from the Courthouse to the Sheriffs Department. This cable will be installed on an existing pole lead owned by Entergy with some poles possibly owned by the City. Permission must be obtained to install the new fiber cable on these poles before proceeding and is the responsibility of the customer to obtain. This cable will be to replace the existing multimode fiber cable that is damaged and only has two (2) working fiber strands. The existing messenger will be utilized for the new cable. This route runs along side Highway 69 and will require assistance from the Sheriffs Department when crossing the Highway 190 and Highway 69 intersection. After the new cable has been installed, both ends will be terminated, mounted, labeled, and OTDR tested. All existing mounting hardware will be used for the new cable except the existing panels which will need to be replaced with single-mode panels. All work is to be preformed during normal business hours at straight-time rates.</p>		
Corning 12SM Altos OSP Fiber Cable	3,200	1,484.80
3M Cold Shrink: 8426-9	2	54.06
Corning 12-Fiber Fan-Out Kit: FAN-BT25-12	2	48.43
Corning ST S/M Connector: 95-201-52-SP	24	278.40
Corning S/M ST 12-Port Panel: CCH-CP12-19T	2	195.17
Pole / Building Hardware	22	440.00
OTDR Test & Documentation	24	480.00
Consumables (misc. termination materials)	1	20.00
	Subtotal:	
* Material pricing is good for 30 days from date of estimate.	Sales Tax: (8.25%)	
Without regard to any other provision of this Agreement, Owner shall be liable to Contractor for additional costs incurred by Contractor as the result of any increase in the rate of an applicable state or local sales, excise or use tax that occurs after the effective date of this Agreement.	Total:	

Customer Signature: Janice L. Marchette
 Date of Acceptance: 2/24/20

Maverick



Communications, Inc.

PO Box 2233 Beaumont TX 77704
 Office: (409) 840-5223 Fax (409)840-5205
 maverickinc.com

Firm Quote

Date:	Estimate Number:
2/7/2020	12502
	Maverick Job No:
	Customer PO No:
	Pending

Submitted To:

Tyler County Courthouse
 Attn: Accounts Payable
 100 West Bluff Street
 Woodville, TX 75979

File Name:	Customer Contact:	
Sheriffs Department Fiber	D. Calhoon	
Job Description:	Quantity:	Total:
Miscellaneous Small Parts	1	150.00
Bucket Truck Charge	20	1,300.00
Labor Charge - Tech (S/T Rate) for Cable Installation	68	5,440.00
Acceptance of Estimate - The above prices, specifications, conditions and attachments are satisfactory and are hereby accepted. Maverick is authorized to do the work as specified.	Subtotal:	\$9,890.86
* Material pricing is good for 30 days from date of estimate.	Sales Tax: (8.25%)	\$0.00
Without regard to any other provision of this Agreement, Owner shall be liable to Contractor for additional costs incurred by Contractor as the result of any increase in the rate of an applicable state or local sales, excise or use tax that occurs after the effective date of this Agreement.	Total:	\$9,890.86

Customer Signature: *Juan G. Marchetti*
 Date of Acceptance: 2/24/20

COUNTY, TEXAS
SUBDIVISION REGULATIONS

TABLE OF CONTENTS

GENERAL PROVISIONS.....	4
ENFORCEMENT	5
VARIANCE	5
BOND REQUIREMENTS.....	6
Security/Construction Bond	6
Maintenance Bond.....	7
Bond Extension	8
Irrevocable Letter of Credit (in lieu of Bond)	8
Other Security.....	9
EXCLUDED TRANSACTIONS	9
PLATTING PROCEDURES	10
PRELIMINARY PLAT.....	10
RECORD PLAT.....	12
REVISION TO PLAT	14
WATER AVAILABILITY REGULATIONS	15
Provisions	15
Definitions	15
Applicability.....	16
Requirements for Subdivisions to be served by Private Water Wells.....	16
Requirements for Subdivisions to be served by Existing Public Water Supply System.....	17
Requirements for Subdivisions to be served by a New Public Water Supply System.....	18
Adoption of Model Rules under Chapter 16 of the Texas Water Code	19
Wastewater Disposal.....	20
DESIGN STANDARDS	22
Lots.....	22
INFRASTRUCTURE REQUIREMENTS.....	22
Definitions	22
Recreational Vehicle Park	23
Infrastructure Requirements	24
Recreational Vehicle Park Regulations.....	25
Other Regulations.....	28

Fees.....	29
Penalties.....	29
EASEMENTS	29
FLOOD PLAINS.....	31
ROADWAYS	31
FINAL INSPECTION.....	36
PENALTIES FOR VIOLATION.....	36
Appendix A	38
Appendix B.....	40
Appendix C (1).....	43
Appendix C (2).....	44
Appendix D	45
Appendix E.....	46
Appendix F	47
Appendix G	48
Appendix H	49
Appendix I.....	50
Appendix J.....	51
Appendix K	52
Appendix L.....	53
Appendix N	56
Appendix O	58
Appendix P.....	60
Appendix Q	63
Appendix R.....	64
Appendix S	65

GENERAL PROVISIONS

Every owner/subdivider/developer (hereinafter called "Owner/subdivider/developer") of any tract of land situated outside the corporate limits of any city in _____ County, Texas, who may hereafter divide the same in two (2) or more parts for laying out lots for the purpose of laying out streets, alleys, or parks or other portions intended for public use shall cause a plat to be made thereof which shall accurately describe all of said subdivision or addition by metes and bounds and locate the same with respect to an original corner of the original survey of which it is a part, giving the dimensions of all lots, streets, or other portions intended to be dedicated to public use or for the use of purchasers or owners of lots. Said map or plat, shall be prepared in compliance with these regulations and with the subdivision statutes of the State of Texas and shall be submitted to the Commissioners Court for approval prior to filing with County Clerk.

In areas within the City Limits and Extraterritorial Jurisdiction (ETJ) of the Cities of _____ County, the provisions are as follows:

- a. property located 100% within the City Limits and/or ETJ of the Cities of Bowie, Nocona and Saint Jo are under exclusive jurisdiction of said Cities in accordance with interlocal agreements signed with _____ County.
- b. property located both within the City Limits and/or ETJ of the Cities of Bowie, Nocona and Saint Jos, and also located in _____ County, are subject to separate Regulations; the property located in the ETJ is under jurisdiction of the City and the property located in the County is under jurisdiction of the County, with the more stringent regulations prevailing.

In the event that the proposed subdivision is a revision of a recorded plat, the Owner/subdivider/developer will be required to meet the requirements of these Regulations for revisions, as well as these specifications. An existing subdivision plat may be cancelled, revised, or Amended by the owner/subdivider/developers thereof in conformance with these Regulations and Sections 232.008, 232.0083, 232.0085, 232.009, 232.0095, 232.010, or 232.011 of the Texas Local Government Code and upon approval by the Commissioners Court.

With the inception of these Regulations, the installation of septic systems on any lot in a subdivision shall not occur until a final plat has been approved and filed for record, and all the standards contained herein or referred to herein have been complied with in full.

Water Availability Regulations apply to all applications for approval of a plat for a Subdivision wholly or partially within _____ County, Texas except when platting is exempt from the subdivision regulations (*see excluded transactions*).

_____ County shall not repair, maintain, install, or provide any streets or roads in any subdivision for which a final plat has not been approved and filed for record, nor in which the standards contained herein or referred to herein have not been complied with in full, nor shall _____ County repair, maintain, or install any streets or roads until such time as the roads or streets have been formally accepted for inclusion into the County maintenance inventory by an order separate and apart from approval of any plat for filing purposes only by the Commissioners Court. Approval of the subdivision plat for filing does not indicate any agreement or understanding that _____ County will assume responsibility for maintenance of roads, streets, alleys or other areas dedicated to public use on the plat.

ENFORCEMENT

The Commissioners Court of _____ County shall have the authority to refuse to approve or authorize any map or plat of any such subdivisions, unless such map or plat meets the full requirements as set forth in these Subdivision Regulations and there is submitted at the time of approval of such map or plat financial security as may be required by these Regulations. No lot in any subdivision shall be sold or transferred until the final plat is approved and recorded, and all the standards, specifications or requirements contained or referred to herein have been complied with in full. On behalf of _____ County, the County Attorney or other attorney may, when directed by the Commissioners Court, institute appropriate action in a court of competent jurisdiction to enforce the provisions of this Order or the standards referred to herein with respect to any violation thereon which occurs within _____ County's jurisdiction. The County reserves the right to seek all remedies, including injunction, prohibition, damages, and where appropriate, criminal penalties in the enforcement of these rules and regulations.

Conflicting Orders. If any other County Order is in conflict with this Order, the most stringent rules will apply. Nothing will be permitted under the provisions of this Order that is in violation with another valid Order of the County.

Severability Clause. If any provision of this Order or the application thereof, to any person or circumstance is held invalid, the remainder of the Order and the application of such provision to their persons or circumstances shall not be affected thereby.

Penalty for Violation. The Commissioners Court of _____ County will cause an employee of the Court or any other person or persons it so designates to review periodically those deeds or sales contracts being recorded in the County Clerk's Office to see that any subdivisions affected thereby shall comply with requirements of Chapters 232 and 233 of the Texas Local Government Code.

If deeds, contracts of sale, transfers of title, or other transactions do not comply with the plat requirements as set forth in this Order and in the State Statutes, the Commissioners Court of _____ County or its' representative can so notify the party selling or transferring title in whole or in part to comply with the said requirements.

In the event the said notified party refuses to comply with the requirements of the State Statutes, the Commissioners Court can take appropriate action to obtain compliance. Any party violating any provisions of this Order shall be guilty of a Class B misdemeanor and each act of the violation shall constitute a separate offense.

VARIANCE

The Commissioners Court may authorize a variance from the Subdivision Regulations when, in its opinion, undue hardship will result from requiring strict compliance. In approving a variance, the Commissioners Court shall prescribe only conditions that it deems necessary or desirable to the public interest. Any person who wishes to receive a variance shall apply to the Court with a list of, and a detailed justification, for each variance requested. The decision of the Court whether to grant or deny a variance is at its complete discretion and will be final.

In approving a variance, the Commissioners Court shall prescribe only conditions that it deems necessary or desirable to the public interest. In making their findings, the Commissioners Court shall take into account the nature of the proposed use of the land involved and existing uses of the proposed subdivision and the probable effect of such variances upon traffic conditions and upon the public health, safety, convenience, and welfare in the vicinity. No variance shall be granted unless the Commissioners Court finds:

1. That there are special circumstances or conditions affecting the land involved such that the strict application of this Order would deprive the applicant of the reasonable use of his land, and,
2. That the granting of the variance will not be detrimental to the public health, safety, or welfare, or injurious to other property in the area, and,
3. That the granting of the variance will not have the effect of preventing the orderly subdivision of other land in the area in accordance with the provisions of this Order.

Such findings of the Commissioners Court, together with the specified facts upon which such findings are based, shall be incorporated into the official minutes of the meeting at which the variance is granted. Variances may be granted only when in harmony with the general purposes of intent of the Order so that the public health, safety, and welfare may be secured and substantial justice done. Pecuniary hardship to the Owner/subdivider/developer, standing alone, shall not be deemed to constitute hardship. No Variance shall be granted as to required improvements.

BOND REQUIREMENTS

Security/Construction Bond:

1. All construction shall be complete with two (2) years after approval of final plat in a timely manner, and in accordance with the terms and specifications contained in this Court Order, the owner/subdivider/developer shall file a Construction Bonds, executed by a Surety Company authorized to do business in this state, and made payable to the County Judge of _____ County, Texas, or his successor in office.
2. The bond amount shall be equal to one-hundred percent (100%) of the estimated cost of construction of roads, streets, street signs, underground utilities, required drainage structure and all other construction.
3. The construction bonds shall remain in full force and in effect until all the roads, streets, street signs, underground utilities, required drainage structures and all other construction in the subdivision have been completed to the satisfaction of the County Engineer, and the construction bond has been released by a Court Order from the Commissioners Court.
4. In the event any or all of the streets, roads, drainage and drainage structures, as constructed by the owner/subdivider/developer, fail to meet the requirements of the foregoing specifications, and the said attention in writing by the County Engineer, the unfinished improvements shall be completed at the cost and expense of obligees as provided.
5. The plat shall not be approved or recorded unless the Owner/subdivider/developer has filed with the Commissioners Court a cash bond or other surety executed by a surety company holding a

license to do business in the State of Texas, made payable to the County Judge of _____ County, Texas, or his successor in office, and acceptable to the County, in an amount equal to the cost of the roads and drainage improvements, or other improvements where applicable, including but not limited to water and wastewater facilities, required by these Regulations as estimated by the Design Engineer and approved by the County, conditioned that the Owner/subdivider/developer will complete such improvements within two (2) years after approval of such plat, such bond to be approved by the County Commissioners Court.

6. Should there be any deficiency or variance from the requirements herein or should the work not be completed within the stated time, the County will notify the Owner/subdivider/developer of such departure by certified mail. Should the condition not be corrected within thirty (30) days following receipt of notice, the County may declare the bond or surety forfeited and order construction operations suspended. The County reserves the right to complete the work by means most advantageous to its organization and citizens, utilizing such portion of the bond or surety as may be necessary to accomplish such completion. In the event progress and final inspections indicate no departure from the requirements herein, the designated representative of the County will certify completion in accordance with the requirements of the Commissioners Court and the Court will consider release of the surety. The surety bond shall remain in effect until all roads, drainage improvements and other applicable improvements have been approved by the Commissioners Court, and the bond has been released by Order of the Commissioners Court. **It is the responsibility of the Owner/subdivider/developer to advise the County Commissioners Court of the status of construction prior to expiration of the two (2) year construction period as is stated above.**

Maintenance Bond:

- 1 To insure roads, streets, street signs, underground utilities, required drainage structures and all other construction are maintained to the satisfaction of the County Engineer, a maintenance bonds executed by a Surety Company authorized to do business in this state, and made payable to the County Judge of _____ County, Texas, or his successor in office, shall be substituted for the construction bond at the time of release of said construction bond.
- 2 The maintenance bond amount shall be equal to one-hundred percent (100%) of the estimated cost of roads, streets, street signs, underground utilities, required drainage structures and all other construction.
- 3 The conditions of the maintenance bond shall be that the owner/subdivider/developer shall guarantee to maintain, to the satisfaction of _____ County, all of the streets, roads, drainage structures and drainage ditches and channels which have been constructed to specification with construction security released by Court Order form Commissioners Court, in a good state of repair for a period of two (2) years from the date of official release of construction security.
- 4 Periodical inspection of roads, streets, street signs, underground utilities, required drainage structures and all other construction for which maintenance security is held, will be made by the County Engineer during the period of liability covered by the maintenance bond. In

the event any or all of the roads, streets, street signs, underground utilities, required drainage structures and all other construction are not being maintained in a good state of repair, the owner/subdivider/developer will be so advised in writing and, if after a reasonable time, he fails or refuses to repair said items, they shall be maintained at the cost and expense of obligees as in said orders provided.

- 5 The release of any bond shall be by order of the Commissioners Court. To request a release the owner/subdivider/developer who posted the bond in question shall present a written request to release said bond. The request shall contain a statement by the engineer responsible for the design of said work stating that he has made an inspection of such improvements and recommends their acceptance by the County. Attached to his letter shall be one (1) set of "as built" drawings showing the work to be accepted for use by the County. The written request of bond release shall be received by _____ County at least fourteen (14) days prior to the next regularly scheduled meeting of Commissioners Court.

_____ County shall not repair, maintain, install, or provide any streets or roads in any subdivision for which a final plat has not been approved and filed for record, nor in which the standards contained herein or referred to herein have not been complied with in full, nor shall _____ County repair, maintain, or install any streets or roads until such time as the roads or streets have been formally accepted for inclusion into the County maintenance inventory by an order separate and apart from approval of any plat for filing purposes only by the Commissioners Court. Approval of the subdivision plat for filing does not indicate any agreement or understanding that _____ County will assume responsibility for maintenance of roads, streets, alleys or other areas dedicated to public use on the plat.

The Commissioners Court shall not in any case accept such roads and improvements on behalf of the County for a period of at least two (2) years after such proper completion, and not then unless and until the Commissioner in whose precinct the proposed subdivision is located certifies that they have been maintained in good condition for said period of two (2) years and are in good condition at such time. The County shall reserve the right to reject or accept such roads and drainage improvements only upon motion duly passed at a regular or legally called special meeting of the Commissioners Court, and the Owner/subdivider/developer shall remain responsible for the maintenance of such improvements until legally accepted for county maintenance by separate order by the County. Maintenance of roads shall include such items as drainage by others, spilled concrete, mud and debris on roads, damage from unknown springs, pumping, unraveling, etc. Maintenance of the drainage improvements shall include removing debris; re-sodding eroded areas and the installation of additional concrete riprap where designated by the County to permanently prevent erosion.

Bond Extension: Where good cause exists, the County may extend the period of time for completion for an additional period of time not to exceed six (6) months if the Owner/subdivider/developer has not completed the required improvements or completed such improvements in compliance with these Regulations. No such extension shall be granted unless the Owner/subdivider/developer provides additional security to cover the extended period of time.

Irrevocable Letter of Credit (in lieu of Bond): An Irrevocable Letter of Credit may be submitted in lieu of bonds for the purpose of insuring an Owner/subdivider/developer's obligation to construct and maintain the roads, drainage improvements and other applicable improvements in a subdivision. Irrevocable Letters of Credit In lieu of Bonds are required under the same conditions as Security and Maintenance Bonds.

Other Security: Any type of security for construction and maintenance other than Bonds and Irrevocable Letters of Credit shall be by written request to _____ County, and must first be approved by Commissioners Court.

EXCLUDED TRANSACTIONS

The following types of transactions will not be considered a subdivision as defined in these Regulations, however, this list is not to be considered exclusive of similar transactions and it is in addition to the general rules set out in these Regulations, *to-wit*:

1. Intra family transfers.
2. Boundary line transaction.
3. Court ordered partitions.
4. Partitions between husband and wife, partners, stockholders of a corporation, and other types of joint tenants.
5. Tracts over ten (10) acres in size regardless of number of tracts created.
6. Transfer of rights-of-way or easements.
7. The owner/subdivider/developer of the land is a political subdivision of the state, the land is situated in a floodplain, and the lots are sold to adjacent landowner.
8. The tract is devised or given by a testator or donor to an individual who is related to the testator or donor within the third degree of consanguinity or affinity, and provided, however this exception does not apply if the division will change the boundary between two legally platted lots or subtract land from a legally platted subdivision.
9. The land being divided is inherited property between heirs or is land being divided between donees who have acquired title by gift deed, the property is being divided by agreement or by action in probate, and the heirs or donees are related to the testator or donor within the third degree of consanguinity or affinity; provided however, this exception does not apply if the division will change the boundary between two legally platted lots or subtract land from a legally platted subdivision.
10. A smaller tract is surveyed out of the parent tract solely for the purpose of obtaining financing of that part of the property, provided that possession and primary beneficial ownership of the entire parent tract are intended to remain unified.
11. The Owner/subdivider/developer does not lay out a part of the tract for streets, alleys, squares, parks, or other parts of the tract intended to be dedicated to public use or for the use of purchasers or owners of lots fronting on or adjacent to the streets, alleys, squares, parks or other parts, and the land is to be used primarily for agriculture use as defined by Section 1-d, Article VIII, Texas Constitution, or for farm, ranch, wildlife management or timber production uses within the meaning of Section 1-d-1, Article VIII, Texas Constitution.

12. Division of a tract into two or more parts and does not lay out a part of the tract as described in Section 232.001(a)(3), Texas Local Government Code, to be sold to veterans through the Veterans' Land Board Program.

PLATTING PROCEDURES

The following procedures shall be followed in the process of review and approval of all subdivision plats by the _____ County Commissioners Court:

Subdivision plats shall be submitted to the Commissioners Court for review and approval on two (2) separate readings (at least one month apart) before they may be recorded with the County Clerk. All subdivisions shall be submitted for Second Reading (Record Plat) within one (1) year after the date of First Reading (Preliminary Plat) approval.

It shall be required that the Owner/subdivider/developer meet with the Commissioner in whose precinct the proposed subdivision is located to review the plat prior to any consideration by the Commissioners Court. The request for said meeting shall be made of the Commissioner a minimum of thirty (30) days prior to the request for Commissioners Court action. Only the Commissioner in whose Precinct the proposed subdivision is located or the County Judge may request both readings be placed on the Commissioners Court meeting agenda for consideration.

All submissions of information required herein shall be made a minimum of thirty (30) calendar days prior to the date of the Commissioners Court meeting at which action is being requested. The Water Availability Studies are required with submission of the preliminary plat. The information will be deemed to have been submitted when it is delivered to the Office of the County Judge, who shall issue a receipt for the completed application and preliminary plat. Five (5) copies of the plat and one copy of all other required information shall be submitted.

All submissions shall be accompanied by a Letter of Transmittal which shall include the name, address, and telephone number of the person who will be representing the Owner/subdivider/developer's request before the Commissioners Court, and stating what action is being requested.

In accordance with Section 245.005 of the Local Government Code, approval of a Preliminary Plan shall expire and be of no further force and effect in the event a Final Plat for a portion of the Subdivision is not filed within twelve (12) months following the date of the Commissioners Court approval of the Preliminary Plan or in the event that no progress has been made towards completion of the project within the project activity period. For purposes of this section, the term "project activity period" means the later of:

- (A) Two (2) years from the date of approval of the Preliminary Plan; or,
- (B) Five (5) years from the date the first permit application was filed for the project.

PRELIMINARY PLAT (First Reading)

The Owner/subdivider/developer shall cause to have prepared a Preliminary Plat of the proposed subdivision which shall show (see Checklist, Appendix A):

1. Typical lot dimensions.
2. Street right-of-way widths.
3. Areas proposed for recreational use, *i.e., courses, parks, greenbelts, etc.*
4. Transfer of rights-of-way or easements, including any alleys and/or utility easements.
5. Proposed land use of all lots being subdivided.
6. Real Property Record volume and page reference and names of all current owner/subdivider/developers of contiguous property surrounding the proposed subdivision.
7. Land use of all contiguous tracts, *i.e., undeveloped, subdivided, etc.*
8. All major topographic features on or adjacent to the property as well as elevation contours at no greater than five-foot (5') intervals if in a floodplain, and no greater than twenty-foot (20') intervals if not in a floodplain. Areas of Special Flood Hazard as shown by the current Flood Hazard Boundary Maps as authorized by FEMA. Each tract shall be inspected and flood plain determination made on its own merits.
9. A comprehensive Flood Plain and Drainage assessment including a 100-year floodplain map and a complete assessment as required by the Texas Commission on Environmental Quality and all applicable state statutes.
10. Master Development Plans [*If the subdivision is a portion of a larger tract of land, the exterior boundary of the parent tract shall be shown on the Preliminary Plat with future plans for the remaining property noted. If the parent tract is larger than 320 acres, the Preliminary Plat may be prepared at a scale no smaller than one inch (1") equals one thousand feet (1000'), with the area proposed to be subdivided detailed at a scale no smaller than one-inch equals two hundred feet (1"=200').*]
11. North directional indication arrow.
12. Vicinity or Location map showing the proposed subdivision in relation to major roads, towns, cities, and topographic features.
13. Names and addresses of the current owner/subdivider/developers of the subdivision property, including Real Property Record volume and page references.
14. Name and address of the proposed owner/subdivider/developer.
15. Total acreage within the proposed subdivision.
16. Total number of lots.
17. Total area within road rights-of-way and length of roads.

18. Statement that streets within the subdivision may not be accepted into the county maintenance inventory and are the responsibility of the owner/subdivider/developer or Home Owners Association until formally accepted for maintenance by the County under separate Order.
19. Name of proposed subdivision, said name shall not conflict in spelling, pronunciation, or in any way with the name of any other subdivision within _____ County, unless the proposed subdivision is contiguous to an existing subdivision and is an additional phase of that development.
20. Names of roadways, said names shall not duplicate any other streets within _____ County unless they are extensions of said streets, and comply with requirements of 9-1-1 addressing regulations.
21. Location of all wells, water, oil, and natural gas, where applicable, and a statement that all unused wells are capped or plugged.

All fees related to the filing of a plat shall be paid to the County Clerk before submission of the Preliminary Plat to the County Judge's office for review. Fees are located on the final page of this Subdivision regulation:

RECORD PLAT
(Second Reading)

Upon a determination that the Preliminary Plat is suitable for consideration on Final Plat Second Reading, the Owner/subdivider/developer shall revise the plat in accordance with the recommendations or (requirements) of the Commissioners Court and shall cause to be prepared a Final Plat of the proposed subdivision, an original and five (5) copies of which shall be supplied to the Court for distribution, such plat having incorporated any and all changes.

These five copies consist of 3 Mylar printed in black ink on white material and 2 Blue Line. Distribution is as follows: one (1) fully signed mylar copy to the Clerk of the Court, one (1) fully signed mylar copy to the Central Appraisal District, and three (3) copies to the County Judge, who will deliver one (1) copy to each of the following: (a) one fully signed mylar copy to the 9-1-1 Coordinator, (b) the County Attorney, and the (c) Commissioner in whose Precinct the Subdivision lies.

The Final Plat shall contain all information required herein for the Preliminary Plat as well as the following: (see Checklist, Appendix B)

1. All information required for the Preliminary Plat.
2. Name of proposed subdivision.
3. Lot and block numbers.
4. Proposed street names, pre-approved by the 9-1-1 Coordinator. [Location for street address signage will be furnished by _____ County in accordance with applicable regulations.]

5. Acreage, to two decimal points, of all lots and tracts.
6. Name and address of the surveyor and/or engineer certifying the plat.
7. Location and size of all proposed drainage structures.
8. Location, size, and proposed use of all easements required for the proper drainage and/or utility service.
9. Boundaries of incorporated city limits and/or ETJs and a statement that “*This property is/is not located within the municipal limits or ETJ boundaries of any community*”.
10. Statement of how utilities will be provided to the development, including names of utility companies, and a written statement from the respective utility that it is able to provide such services to the development. *i.e. water, sewer, power, etc.* If none are available, a statement so indicating shall be placed on the plat.
11. Certification from a licensed professional engineer regarding the method for providing:
 - a. Connection to an existing public water or sewer system;
 - b. Creating a new public water or sewer utility that complies with requirements of the Texas Commission on Environmental Quality (TCEQ); or
 - c. Installing wells that meet public drinking water standards or septic systems that meet on-site sewerage facility requirements of the state;
 - d. A statement that the water and wastewater facilities will accommodate ultimate development of the tracts for a minimum of 30 years.
12. Description of monument used to mark all boundaries, lot, and block corners, and all points of curvature and tangency on street rights-of-way.
13. Acknowledgement and certificate of dedication by the Owner/subdivider/developer (see Appendix C).
14. Certificate of Recording (see Appendix D).
15. Water Supply Certification (see Appendix E).
16. Certificate of Surveyor (see Appendix F).
17. Certificate of Engineer (*Attendance may be required*) (see Appendix G)
18. Certificate of Road Maintenance (see Appendix I OR J).
19. Certificate of County Approval of Plat (see Appendix K).

20. County Permit to Construct Driveway if needed (See Appendix L)
21. Lienholder's Acknowledgement (See Appendix M)
22. Notice of Utility Line Installation in County RoW) See Appendix O)
23. Cattleguard specifications, if applicable (See Appendix P)
24. Typical County Road cross-section. (See Appendix Q)
25. Summary of County Road Standards (See Appendix R)
26. Development Fees (See Appendix S)

In addition, the Owner/subdivider/developer shall submit with the Final Plat the following:

1. Proposed restrictive covenants, if any.
2. Tax Certificate showing all taxes are currently paid on the property to be subdivided. These would include Rollback Tax Receipts, if applicable.
3. The proposed Articles of Incorporation and By-Laws of the Homeowner's Association or other entity responsible for road maintenance in the event the Owner/subdivider/developer proposes to use privately maintained roads.
4. Construction Plans of all required streets and drainage improvements.
5. Road Construction Security, as specified herein.
6. A receipt from the Clerk's Office, showing the Preliminary Plat fees have been paid.
7. A sign-off from the Texas Department of Transportation approving road access.
8. When lots equal or exceed 10 acres in size, the approval of Preliminary Plats and Final Plats may be excused; however, a plat containing a map of the Subdivision shall be filed with the County Clerk, along with applicable filing fees. All proposed street names must be approved by the 911 Coordinator **PRIOR** to such filing. Copies of the final plat must also be provided to the County Judge and the Appraisal District. The fee for filing an otherwise exempt plat is \$250.00 per plat up to 5 plat pages, each additional page being \$25.00 additional each. This plat shall be of Mylar, with black ink on white material. A copy of the Restrictive Covenants, if any, shall be attached.

REVISION TO PLAT

The owner of an existing lot or lots in a platted recorded subdivision may apply for cancellation, revision, or amendment by the owners thereof in conformance with these Regulations and Sections 232.008, 232.0083, 232.0085, 232.009, 232.0095, 232.010, or 232.011 of the Texas Local Government Code and upon approval by the Commissioners Court of the subdivision plat. Upon receipt of a written application for the change, the Commissioners Court will provide for notice of the requested change as set out in the applicable section

of the Texas Local Government Code. The application shall include a revised plat or part of a plat that indicates changes made to the original plat.

After all required notices have been given, the Commissioners Court may adopt an Order to permit the revision of the subdivision plat upon finding that:

1. the revision will not adversely affect the rights of any other subdivision owner/subdivider/developer, or
2. each owner/subdivider/developer whose rights may have been adversely affected has agreed to the revision.

Upon approval by the Commissioners Court, the revised plat shall be filed with the County Clerk to be recorded in the Real Property Records.

A Revision of Plat fee of \$50.00 per plat, plus \$5.00 per plat for Records Preservation fee, \$1.00 per plat for Courthouse Security Fee, and \$500.00 per plat Hydrological Study of Water Availability (unless waived by variance) shall be paid at the time of application. _____ County will assess an additional fee equal to the cost of notice for publication and/or certified letters. All fees shall be paid prior to Commissioners Court approval.

COUNTY WATER AVAILABILITY REGULATIONS

Provisions

These regulations are adopted pursuant to Chapters 16 and 35 of the Texas Water Code, and Section 232.0032 of the Local Government Code, Vernon's Annotated Statutes.

The _____ County Commissioners Court has determined that the adoption of Water Availability Regulations is necessary to prevent current and/or projected water use in _____ County from exceeding the safe sustainable yield of the County water supply.

THE _____ COUNTY COMMISSIONERS COURT MAKES NO REPRESENTATION OR WARRANTY, EITHER EXPRESS OR IMPLIED, THAT SUBDIVISIONS THAT COMPLY WITH THESE WATER AVAILABILITY REGULATIONS WILL MEET THE CURRENT AND/OR FUTURE WATER NEEDS OF PURCHASERS OF PROPERTY WITHIN THE SUBDIVISION.

Definitions

The following words and terms, when used in these Regulations, shall have the following meanings. Words defined in the main body of the _____ County Subdivision Regulations, and not defined here, shall have the meanings provided therein.

- a. "Groundwater" - has the meaning assigned to it by the regulations of the Texas Commission on Environmental Quality (TCEQ);

- b. "FEMA" – means the Federal Emergency Management Agency.
- c. **Flood Insurance Rate Map (FIRM):** An official map on which the FIA has delineated both the areas of special flood hazards and the risk premium zones applicable to flood insurance.
- d. "Full build-out" - means the final expected number of residences, business or dwellings in the proposed subdivision;
- e. "Public water supply system" - has the meaning assigned to it by the regulations of the Texas Commission on Environmental Quality (TCEQ);
- f. "Qualified expert" - means a Hydrologist, a registered professional engineer, or a registered professional geoscientist;
- g. "Surface water" - has the meaning assigned to it by the regulations of the Texas Commission on Environmental Quality (TCEQ);
- h. "TCEQ" - means the Texas Commission on Environmental Quality;
- i. "TDDLRL"- means Texas Department of Licensing and Regulation.
- j. "TWDB" - means the Texas Water Development Board.

Applicability

These Water Availability Regulations apply to all applications for approval of a plat for a Subdivision wholly or partially within _____ County, Texas, pursuant to the _____ County Subdivision Regulations, except as exempted hereafter.

Exemptions to Water Availability Regulations:

- a. Subdivision of property where platting is not required by the _____ County Subdivision Regulations;
- b. Subdivision of property in which all lots are 10 acres or greater.

Water Availability data shall be presented to the Commissioners upon submission of the Preliminary Plat.

_____ County shall have the Water Availability data review by a qualified expert on behalf of _____ County.

Requirements for Subdivisions to be served by Private Water Wells

The Preliminary Plat submission to the Commissioners Court for a proposed subdivision whose water supply will be private water wells shall include Water Availability data. This Water Availability data shall be derived from a minimum of two wells (one test well and one monitor well). There shall be one (1) set of test-monitor wells for each 100 acres. The use of existing wells is permitted if the existing well complies with these regulations.

The following Water Availability data is required:

1. Map of the proposed subdivision prepared by a qualified expert identifying:
 - a. geologic formations;
 - b. location of test and monitor wells by longitude and latitude (GPS located);
 - c. available information on wells identified in the files of the Texas Water Development Board and TCEQ and otherwise known to applicant within 1,000 feet of the boundaries of the proposed subdivision (including well depth, depth to water, yield, and estimated yield).
2. The static water level to the nearest 0.1 foot equated to the mean sea level elevation.
3. Data resulting from the performance of an aquifer pump test utilizing proven methods recommended by TWDB and TCEQ of the karst aquifer systems of the Texas Hill Country. The pump test shall be supervised by a qualified expert and shall be performed prior to any acidization or other flow capacity treatment of the well. The duration of the pump test shall be for a period of 24 hours or until the water level has stabilized (less than 0.1 fluctuation) in the test well for period exceeding two hours.
4. Statement by a qualified expert based on the pump test:
 - a. estimated yield of wells proposed for the subdivision;
 - b. determination of transmissivity of the water-bearing formation or strata from which the groundwater will be withdrawn;
5. Certification by a qualified expert that an adequate supply of water of sufficient quantity and quality to supply the subdivision at full build-out based on number of connections for a minimum of 30 years.
6. The following statement shall appear on the final plat for the approved subdivision: *“This subdivision will be served by individual groundwater wells. Information on the available supply of groundwater and its quality is available to prospective purchasers of lots in this subdivision in the office of the County Clerk of _____ County, Texas.”*

Requirements for Subdivisions to be served by Existing Public Water Supply System

The Preliminary Plat submission to the Commissioners Court for a proposed subdivision whose water supply will be an Existing Public Water Supply System shall include Water Availability data, as follows:

1. Map of the service area of the Existing Public Water Supply System, showing the location of the proposed subdivision in relationship to the service area of the Existing Public Water Supply System;

2. Name, address, phone number, authorized agent and TCEQ facility number of the Existing Public Water Supply System;
3. Certification by a qualified expert that an adequate supply of water of sufficient quantity and quality to supply the subdivision at full build-out based on water use standards recognized by TCEQ and TWDB.

The following statement shall appear on the final plat for an approved subdivision:

“This subdivision will be served by Name and address of Existing Public Water Supply System. Information on the available Existing Public Water Supply System is available to prospective purchasers of lots in this subdivision in the office of the County Clerk of _____ County, Texas and may be stated in the deed restrictions.”

Requirements for Subdivisions to be served by a New Public Water Supply System

The Preliminary Plat submission to the Commissioners Court for a proposed subdivision whose water supply will be a New Public Water Supply System relying wholly or partially on groundwater or surface water shall include Water Availability data. This Water Availability data shall be derived from a minimum of two wells (one test well and one monitor well). There shall be one set of Test Monitor wells for each 100 acres. The use of existing wells is permitted if the existing well complies with these Regulations.

The following Water Availability data is required:

1. Map of the proposed subdivision prepared by a qualified expert identifying:
 - a. geologic formations;
 - b. location of test and monitor wells by longitude and latitude (GPS located);
 - c. available information on wells identified in the files of the Texas Water Development Board and TCEQ and otherwise known to applicant within 1,000 feet of the boundaries of the proposed subdivision (including well depth, depth to water, yield, and estimated yield).
2. The static water level to the nearest 0.1 foot equated to the mean sea level elevation.
3. Data resulting from the performance of an aquifer pump test utilizing proven methods recommended by TWDB and TCEQ of the karst aquifer systems of the Texas Hill Country. The pump test shall be supervised by a qualified expert and shall be performed prior to any acidization or other flow capacity treatment of the well. The duration of the pump test shall be for a period of 36 hours or until the water level has stabilized (less than 0.1 fluctuation) in the test well for a period exceeding two hours.
4. Statement by a qualified expert based on the pump test;
 - a. estimated yield of wells proposed for the subdivision;

- b. determination of transmissivity of the water-bearing formation or strata from which the groundwater will be withdrawn;
 - c. source of surface water supply and estimated yield of surface water source and proof of compliance that withdrawal of surface water complies with state and federal laws.
5. Certification by a qualified expert that an adequate supply of water of sufficient quantity and quality to supply the subdivision at full build-out based on number of connections for a minimum of 30 years.

The following statement shall appear on the final plat for an approved subdivision:

“This subdivision will be served by Name and address of New Public Water Supply System. Information on the New Public Water Supply System is available to prospective purchasers of lots in this subdivision in the office of the County Clerk of _____ County, Texas and may be stated in the deed restrictions.”

Adoption of Model Rules under Chapter 16 of the Texas Water Code

General Platting Requirements apply when the provisions of the General Platting Requirements are equal to or more restrictive than the Model Rules. To the maximum extent possible, the Texas Model Subdivision Rules, Texas Administrative Code 364.1-364.2 are incorporated into this subdivision regulation, unless the General Platting Requirements exceed the requirements of the Model Subdivision Rules, in which case the more stringent rule shall apply.

The following information on lots is required in order to meet the requirements of the Texas Commission on Environmental Quality:

The type of development and use contemplated will determine the size, width, depth, shape, and orientation of tracts or lots. Tracts or lots shall be appropriate for the area of the County, and the type of development contemplated, as follows:

1. When a private water well and an approved on-site sewage facility is used, the tract size shall be a minimum of three (3) acres to lessen the accidental contamination of adjacent water wells.
2. When a TCEQ approved public ground water supply system and an approved on-site sewage facility is used, the lot or tract size shall be a minimum of two (2) acres in size, to limit the possible accidental contamination of public water supplies.
3. When an owner/subdivider/developer proposes to supply drinking water by connection to any existing public water system must provide a written agreement with the retail public utility, providing that the water utility will have the ability to supply the total flow anticipated from the ultimate development and occupancy of the proposed subdivision for a minimum of thirty (30) years. The agreement must reflect that the Owner/subdivider/developer has provided for the cost of any necessary connection equipment, membership fees, water rights acquisition costs, or other fees associated with connection to the public water system so that service is available to each lot upon completion of construction of the water facilities described on the final plat. Written proof

Commission on Environmental Quality in accordance with 30 TAC Chapter 305 and obtain approval of engineering planning materials for such systems under 30 TAC Chapter 317 from the Texas Commission on Environmental Quality.

- b. Owner/subdivider/developers who propose to dispose of wastewater by connecting to an existing permitted facility must execute a written agreement with the retail public utility. The agreement must provide that the retail public utility has or will have the ability to treat the total flow anticipated from the ultimate development and occupancy of the proposed subdivision for a minimum of 30 years. The agreement must reflect that the Owner/subdivider/developer has paid the cost of all fees associated with connection to the wastewater collection and treatment system have been paid so that service is available to each lot upon completion of construction of the wastewater facilities described on the final plat. Engineering plans, signed and sealed by a professional engineer registered in the State of Texas, for the proposed wastewater collection lines must comply with 30 TAC Chapter 317. Written proof that such an agreement has been executed and approved by the retail public utility shall be submitted with the plat application.
- c. Lot sizes for owner/subdivider/developers who provide an organized wastewater collection and treatment system under paragraphs (a) or (b) of this section shall be not less than one-half acre, within the wastewater disposal capacity, or no less than one-acre where capacity cannot be guaranteed for greater densities of population or construction.

2. **On-site Sewerage Facilities.**

- a. On-site sewerage facilities, which serve single family or multi-family residential dwellings with anticipated wastewater generations of no greater than five thousand (5,000) gallons per day, must comply with 30 TAC Chapter 285.
- b. Proposals for sewerage facilities for the disposal of sewage in the amount of five thousand (5,000) gallons per day or greater must comply with 30 TAC Chapter 317.
- c. The Texas Commission on Environmental Quality or its authorized agent shall review proposals for on-site sewage disposal systems and make inspections of such systems as necessary to assure that the system is in compliance with the Texas Health and Safety Code, Chapter 366 and rules in 30 TAC Chapter 285, and in particular §§ 285.4, 285.5 and 285.30-285.39 and the County OSSF Order. In addition to the unsatisfactory on-site disposal systems listed in 30 TAC § 285.3(b), pit privies and portable toilets are not acceptable waste disposal systems for lots platted under these rules.

3. **Greywater Systems for Reuse of Treated Wastewater.**

- a. Organized or municipal sewerage systems. Any proposal for sewage collection, treatment and disposal, which includes greywater reuse, shall meet minimum criteria of 30 TAC Chapter 210 promulgated and administered by the Texas Commission on Environmental Quality.
- b. On-site sewerage facilities. Any proposal for on-site sewage disposal, which includes provisions for greywater use, shall meet the minimum criteria of 30 TAC Chapter 285.

4. **Sludge Disposal**. The disposal of sludge from water treatment and sewerage facilities shall meet the criteria of 30 TAC Chapter 312 and Chapter 317.

DESIGN STANDARDS

LOTS

- a. **No Conveyance of Lots:** Conveyance of Lots depicted on a Preliminary Plan shall not be permitted until the Final Plat has been approved and the record plat filed with the County Clerk.
- b. **Setbacks.** Setbacks from roads and rights-of-way shall be a minimum of ten (10) feet, setbacks from adjacent property lines shall be a minimum of five (5) feet and shall not conflict with separation or setback distances required by rules governing public utilities, on-site sewerage facilities, or drinking water supplies. Setback lines required elsewhere in the Order or Rules of the County shall control to the extent greater setbacks are therein required.
- c. **Number of Single Family Dwellings per Lot.** No more than one (1) single family detached dwelling shall be located on each lot. A notation of this restriction shall be placed on the face of the final plat. This restriction shall be placed in all deeds and contracts for deeds for real estate sold within the subdivision. Proposals, which include multi-family residential, shall include adequate, detailed planning materials as required for determination of proper water and wastewater utility type and design.
- d. If the Owner/subdivider/developer selects to use a TCEQ approved public groundwater or a surface water system and/or a TCEQ approved sewage system, all infrastructure costs shall be the sole responsibility of the Owner/subdivider/developer and shall be included in the guarantee of performance bond to be posted with the County Judge.
- e. **Well and Septic Set Back Lines** shall be at least fifty (50) feet from the property lines on all sides and in every dimension. Any structures must be setback at least ten (10) feet from roads and rights-of-way and adjacent property lines.

**THE SET BACK LINES DENOTED ABOVE ARE A REQUIREMENT OF THE
COUNTY SEWAGE FACILITY REGULATIONS.**

COUNTY INFRASTRUCTURE REQUIREMENTS FOR RECREATIONAL VEHICLE PARKS

1. DEFINITIONS:

OPERATOR. Includes the person in charge of operating any recreational vehicle park, either under written or verbal (oral) lease, or any other arrangement whereby he or she exercises control over the premises.

OWNER. Includes the person in whose name the title to the lot, block, tract, or parcel of land is shown to be.

PERSON. Any natural individual, firm, trust, partnership, association, or corporation.

RECREATIONAL VEHICLE. Includes any of the following:

- (1) CAMPING TRAILER. A folding structure mounted on wheels and designed for travel, recreation, and vacation use.
- (2) MOTOR HOME. A portable, temporary dwelling to be used for travel, recreation and vacation, constructed as an integral part of a self-propelled vehicle.
- (3) PICKUP COACH. A structure designed to be mounted on a truck chassis for use as a temporary dwelling for travel, recreation, and vacation.
- (4) TRAVEL TRAILER. A vehicular structure built on a chassis with body width not to exceed eight feet and body length less than 46 feet, that structure designed to be transported and intended for human occupancy as a dwelling for short periods of time and containing limited or no kitchen or bathroom facilities.

RECREATIONAL VEHICLE PARK. Any lot or tract of land designed to accommodate two or more recreational vehicles, as defined, and which exist as a privately owned and operated enterprise with or without charges for the parking of recreational vehicles occupied or intended to be occupied for dwelling or sleeping purposes for any length of time. Hunting camps that are temporary are excluded.

RECREATIONAL VEHICLE SPACE. A plot of land within a recreational vehicle park designed for the accommodation of one recreational vehicle.

2. RECREATIONAL VEHICLE PARK:

- (1) The owner of land located in _____ County outside the limits of a municipality who intends to use the land for a Recreational Vehicle Park must have an infrastructure development plan prepared that complies with the minimum infrastructure standards that are set out below in Section 3.
- (2) Prior to beginning any construction, the owner must submit the plan to the _____ County Engineer for approval. Construction may not begin before the plan is approved.
- (3) Not later than the 60th day after the date the plan is submitted, the County Engineer shall approve or reject the plan in writing. If the plan is approved, construction may begin immediately. If the plan is rejected, the written rejection shall specify the reasons for the rejection and the actions required for approval of the plan. The failure to reject a plan within the period prescribed by this subsection constitutes approval of the plan.
- (4) The County Engineer, as well as any other person designated by either the County Engineer or the Commissioners' Court, may inspect the infrastructure at any reasonable time during construction, and the owner and his agents shall not hinder such inspections.
- (5) On completion of construction, the owner shall confirm in writing to the County Engineer that the infrastructure is complete, and a final inspection must be completed not later than the second business day after the notice is received by the County's inspector. If the inspector determines that

the infrastructure does not fully comply with the plan, the owner shall be given an opportunity to cure the defects. On completion of curative construction, the owner should request another inspection.

- (6) When the inspector determines that the infrastructure complies with the plan, the Commissioners' Court shall issue a Certificate of Compliance not later than the fifth business day after the final inspection is completed.
- (7) A utility may not provide utility services, including water, sewer, gas, and electric services, to a recreational vehicle park or to a recreational vehicle in the community unless the owner provides the utility with a copy of the Certificate of Compliance.

3. INFRASTRUCTURE REQUIREMENTS:

The infrastructure development plan for a Recreational Vehicle Park must include each of the following:

- (1) A survey identifying the proposed community's boundaries and any significant feature of the community, including the proposed location of lots or spaces, utility easements and dedication of rights-of-way. The survey may also contain features to help provide the additional information required by this order.
- (2) Reasonable specified plans to provide adequate drainage in accordance with standard engineering practices, including specifying necessary drainage culverts and identifying areas included in the 100-year flood plain. The placement of any structure within the regulatory floodplain shall be in accordance with the _____ County Floodplain regulations
- (3) Reasonable specified plans to provide an adequate public or community water supply, including specifying the location of supply lines, in accordance with Subchapter C, Chapter 341, Health and Safety Code. If water is to be provided by a utility, a certification by the utility that water is available for each of the planned spaces or lots must be attached to the plan.
- (4) Certification that adequate groundwater is available for the development. If ground-water is the source of water supply for the development, the developer is required to obtain certification, by a licensed professional engineer (or other professionals designated by State law) registered to practice in Texas, that adequate groundwater is available for the development, according to the certificate form and content as promulgated by the Texas Commission On Environmental Quality (Lack of certification that suitable and adequate groundwater is available is grounds for denial of plat approval, if groundwater is the proposed source of water). The certification document shall be recorded as part of the dedication instrument and a note shall be placed on the plat that groundwater is to be the source of water.
- (5) Either:
 - a. Reasonably specified plans to provide access to sanitary sewer lines, including specifying the location of sanitary sewer lines. If sewage treatment is to be provided by a utility, a certification by the utility that service for each of the planned spaces or lots is available must be attached to the plan. If the sewage is to be treated in some other way, approval by the

relevant government agency that is to license or inspect the treatment facilities must be attached; or

- b. Reasonably specified plans for providing on-site sewage facilities in accordance with Chapter 366, Texas Health and Safety Code if estimated sewage flow does not exceed 5,000 gallons per day (gpd). These plans must meet minimum standards established under Chapter 285.4 of the OSSF rules and _____ County Public Health District local order. Approval by the _____ County Public Health District-Environmental Health Division must be attached to the plan.
- c. Reasonably specified plans for providing sewage treatment and disposal under Chapter 26 of the Texas Water Code if estimated flow exceeds 5,000 gpd. approval by Texas Commission on Environmental Quality must be attached to the plan.
- d. Reasonably specified plans for streets or roads in the Recreational Vehicle Park to provide ingress and egress for fire and emergency vehicles.
 - i. Therefore, the Commissioners' Court finds that it is reasonably necessary that streets in these communities should be built to the same standards (but to no more stringent standard) than the requirements adopted by the Court for subdivisions.
 - ii. The road design and construction standards contained in the _____ County Subdivision Regulations, as amended from time to time, are therefore incorporated by reference into this order as fully and completely as if set out verbatim herein. The street or road specifications in the infrastructure development plan must comply with those standards to the maximum degree practicable.
 - iii. Building Set Backs shall be as specified in the _____ County Subdivision Regulations (Sect. 301.1)
 - iv. Drainage design for the development shall comply with the _____ County Subdivision Regulations (Sect. 307).
 - v. Commissioners' Court (but not the County Engineer) may grant a variance when strict application of these standards would work an unusual hardship. Variances for OSSF can only be granted by _____ County Public Health District.

4. RECREATIONAL VEHICLE PARK REGULATIONS:

(A) The regulations described herein govern the development, operation, and maintenance of recreational vehicle parks, as previously defined.

- (1) Park development requirements. Recreational vehicle parks shall be developed to conform to those requirements as herein delineated.
- (2) Recreational vehicle parks shall be designed so as not to exceed a maximum of 20 units per acre.

- (3) Parking facilities shall be provided at the park office as will accommodate five recreational vehicles.
- (4) Each recreational vehicle space shall afford parking and maneuvering space sufficient so that the parking, loading, and the like, of recreational vehicles shall not necessitate the use of any public right-of-way or privately-owned property which may abut the park.
- (5) Each recreational vehicle space provided with electrical service shall be so served through an underground distribution system. The park office and service buildings may receive electrical service as provided through overhead facilities
- (6) Each park shall provide recreational vehicle parking spaces and each such space shall be clearly defined. Twenty percent (20%) of the parking spaces shall be not less than eighteen (18) feet by fifty (50) feet. There must be at least a ten-foot clearance of space between adjacent rows of parking spaces.
 - (a) Be improved with compacted crushed road base material and asphalt or concrete adequate to support the weight of the recreational vehicle.
 - (b) Not heave, shift, or settle unevenly under the weight of the recreational vehicle due to frost action, inadequate drainage, vibration or other forces acting on the structure.
- (7) The entrance to the park shall be designed to minimize congestion and hazards and allow free movement of traffic on adjacent streets.
- (8) Hard surface private streets adequate to provide access to each recreational vehicle space shall be constructed and maintained in good condition by the licensee and the width of which shall be not less than twenty-four (24) feet.
- (9) The park shall comply with state and federal standards for accessible for the mobility impaired. The applicant shall show proof of compliance.

(B) Service buildings; laundry and sanitation facilities. Each recreation vehicle park shall provide one or more service buildings for the use of park patrons.

- (l) The service buildings shall provide for:
 - (a) One flush toilet for women;
 - (b) One flush toilet for men;
 - (c) One lavatory for each sex;
 - (d) One shower and dressing accommodation for each sex, provided in an individual compartment or stall;
 - (e) One washing machine; and
 - (f) One slop sink, not less than 14 by 14 inches square and 14 inches deep.

(2) The aforementioned amenities shall accommodate not more than 50 recreational vehicle spaces. For each additional 30 recreational vehicle spaces or fraction thereof one flush toilet, one shower with individual dressing accommodations, and one lavatory shall be provided for each sex, with laundry and slop sink facilities as described in divisions (B) (I) (e) and (B) (I) (f) to be provided for each additional 50 recreational vehicle spaces.

(3) All unisex bathrooms shall comply with the Americans with Disabilities Act. (ADA).

(C) Service building requirements. Service buildings providing the aforementioned facilities shall satisfy requirements as include:

(1) Service buildings housing sanitation or laundry facilities shall be permanent structure which comply with all applicable laws and ordinances regulating buildings, electrical installation, plumbing and sanitation systems;

(2) Service buildings shall afford appropriate illumination, shall be well ventilated with screened openings, shall be constructed of moisture-proof materials, to include painted woodwork, as shall permit frequent clearing and washing, and shall be maintained at a temperature of 68° F during the period October 1 through May 1. Floors shall be constructed of concrete or other equally impervious material, easily cleanable, and provided with floor drains which are connected to the sanitary sewer; If connected to On Site Sewage Facilities chemical cleaners should be used on a limited basis.

(3) The toilet and other sanitation facilities for males and females either shall be in separate buildings or shall be separated, if in the same building, by a soundproof wall;

(4) All service buildings and park grounds shall be maintained in a clean, slightly condition and kept free of any condition that will menace the health of any occupant or the public or constitute a nuisance; and

(6) Service buildings housing sanitation facilities shall be located not closer than 15 feet nor farther than 300 feet from any recreational vehicle space within the park.

(D) Garbage Receptacles

(1) Each recreational vehicle park shall provide a minimum of two (2) fly tight, water- tight, rodent proof dumpsters for the first one-hundred (100) sites with one (1) additional dumpster for each one-hundred (100) sites or fraction thereof.

(2) Refuse collection stands shall be provided for all refuse containers. Such container stands shall be so designed as to prevent containers from being tipped, to minimize spillage and container deterioration and to cleaning around them. Construction shall conform to 4A5 this section.

(3) The storage, collection and disposal of refuse in the recreational vehicle park shall be so conducted as to create no health hazards.

(4) The dumpster shall be screened from public view.

(E) FUEL

- (1) Bottled gas for cooking purposes shall not be used at individual recreational vehicle spaces unless the containers are properly connected by copper or other suitable metallic tubing.
- (2) Bottled gas cylinder shall be securely fastened in place.
- (3) No cylinders containing bottled gas shall be located in a recreational vehicle or within five (5) feet of a door thereof.
- (4) State and local regulations applicable to the handling of bottled gas and fuel oil shall apply.

(F) FIRE PROTECTION

- (1) Every park shall be equipped at all times with fire extinguishing equipment in good working order of such type, size, and number and so located within the park as to satisfy the fire code and other applicable regulations of the County.
- (2) No open fires shall be permitted, except that this shall not be construed to prevent barbecuing with charcoal in an approved pit or grill.
- (3) All sites and any part of a recreational vehicle shall not exceed one hundred fifty (150) feet from the hard surface streets.

(G) DRY VEGETATION

The park licensee or agent shall be responsible for maintaining the entire area of the park free of dry brush, leaves and weeds.

5. OTHER REGULATIONS:

Persons developing Recreational Vehicle Parks should be aware that this order is not the exclusive law or regulation controlling development in _____ County. The following is only a partial list of regulations that may apply.

- (a) Recreational Vehicle Parks are subject to _____ County Subdivision Regulations. All subdivision within the Extra Territorial Jurisdiction (E.T.J.) Of an incorporated city may also be subject to city subdivision regulations, or as per any mutually (County-City) agreed upon regulations as approved and accepted under an interlocal cooperation agreement.
- (b) All Recreational Vehicle Parks are subject to regulations of general applicability, including public health nuisances under Chapter 341 and 343 of the Texas Health and Safety Code. The developer must address solid waste disposal, rodent/insect harboring, fly breeding and improper water disposal in accordance with these Chapters.
- (c) Other agencies with regulatory authority that may apply to a Recreational Vehicle Park include, but are not limited to, several Emergency Services Districts, the Texas Commission on Environmental Quality, the Public Utilities Commission, the United States Parks and

Wildlife Service, the Environmental Protection Agency and the U.S. Army Corp. Of Engineers.

Issuance of a Certificate of Compliance under this order does not indicate compliance with any of these requirements.

6. FEES

Fees for permits, license and transfers, as established by the _____ County Board of Health, are payable to the _____ County Public Health District for public health regulatory purposes.

7. PENALTIES:

(a) Violations of this order will result in the denial of utility services,

(b) The requirements of this order have been established by and adopted by the _____ County Commissioners' Court under Chapter 232 of the Texas Local Government Code and all the civil and criminal penalties applicable under that chapter shall apply to violations of this order.

EASEMENTS

Utility Easements. In residential areas, easements shall be provided for installation of utilities. Any other requirements will be determined by the Commissioners Court.

- a. Utility easements shall be a minimum of ten feet (10') in width, and normally located along a property or lot line. It shall be the duty of the owner/subdivider/developer to ensure that all easements are of the proper width and location to serve the using utility companies.
- b. Utility lines crossing a road shall be installed a minimum of twenty-four inches (24") below the ditch line or a minimum of thirty-six inches (36") below the crown line of the road, whichever is greater. All lines carrying liquid products must be encased in metal or PVC schedule 40 a minimum length of five feet (5') from ditch line to ditch line.
- c. If new roads are constructed over existing petroleum pipe lines crossings, the pipe lines must meet the following requirements:
 1. encased pipe must be at least three feet (3') below the deepest proposed ditch grade.
 2. non-cased pipe (of extra wall thickness meeting Federal Regulations) must be at least four feet (4') below the deepest proposed ditch.
- d. No road will be accepted for maintenance by _____ County, which contains a petroleum pipeline within the right-of-way, other than crossing pipelines.

Drainage Easements. Where the subdivision is traversed by a water course, drainage way, channel or stream, there shall be provided a storm water easement or drainage right-of-way conforming substantially with the lines for such water course and of sufficient width to convey all storm and flood water flowing through as may be determined by the Commissioners Court through its authorized representative, to accommodate further width or construction and allow access for maintenance.

The County does not provide maintenance for drainage unrelated to road maintenance within the county road right-of-way.

Storm Water Discharge Permit

Under current regulation, construction activities including clearing, grading and excavation, must be permitted for storm water discharge unless the operations result in the disturbance of less than five acres total land area or areas which are not part of a larger common plan of development. Notice of Intent (NOI) for storm water discharges associated with industrial activity under the National Pollution Discharge Elimination System (NPDES) General Permit with the EPA shall be submitted by the owner/subdivider/developer at least two (2) days prior to commencement of construction. During construction a copy of the Storm Water Pollution Prevention Plan shall be available on site in accordance with EPA requirements.

- a. The area identified as drainage easement will be subtracted from the raw lot size in determination of acceptable lot size for construction.
- b. Culvert design shall be sized by a Registered Professional Engineer and a map or list containing the size of each pipe shall be attached to the plat. The owner/subdivider/developer will be held responsible for notifying builders and lot owners of this requirement and ensuring the property sized culvert is installed.
- c. Drainage easements shall generally be located along the existing drainage way, and shall meet the following standards:
 1. open channels with top widths from zero feet (0') to fifty feet (50') require top width plus twenty-five feet (25').
 2. open channels with top widths greater than fifty feet (50') require top widths plus twenty-five feet (25') each side.
 3. Enclosed pipes require twenty feet (20') minimum width.
 4. All easements shall be so designed to allow maintenance equipment to enter the easement and be able to perform the necessary work.

Generally, it is desired that surface drainage from private property be taken to roads and streets or drainage courses as quickly as possible, but the practice of using roads and streets as major drainage courses is prohibited.

Design of channels shall consider velocities and shall be shaped, graded, lined, or protected to minimize or prevent scour and erosion from excessive velocities. This requirement shall extend to roadside

drainage ditches, often called "borrow ditches." Seeding of native grasses or other plants as approved by the Commissioners Court shall be required to deter erosion.

All road culverts shall be of permanent type, either concrete or metal. Drainage calculations shall be made using Talbot's Formula or other methods satisfactory to the Commissioners Court. Drainage structures shall be designed using a ten (10) year flood frequency. The size of the culverts shall be subject to the approval of the Commissioners Court, but under no circumstances shall they be less than twenty-four inches (24") in diameter.

All roadways crossing streams or roadways subject to flooding must be riprapped on both sides as specified by the County. Concrete used as riprap must test 2500 psi.

FLOOD PLAINS

Subdivisions that are located in a flood zone as shown on the current Flood Insurance Rate Map (FIRM) for _____ County will have the following requirements:

1. permanent type bench marks shall be set in appropriate locations with the description and elevation shown on the plat. The elevation of the benchmark shall be tied to a bench mark shown on the FIRM panel.
2. a note on the plat stating, "a flood permit will be required from _____ County for any construction in the flood plain."
3. All subdivision proposals shall be consistent with _____ County's Flood Plain Regulations.
4. Contours at on foot (1') intervals shall be shown on the plat.
5. The finished floor elevation must be shown for each lot located in the flood plain.
6. The flood plain area of each lot shall be subtracted from the overall lot size to determine minimum lot size.
7. The provision of and maintenance of drainage for the purpose of flood damage reduction on individual private lots is not the responsibility of the County.
8. Any water well drilled in a flood plain will comply with TDLR standards for water well completion in a flood plain.

ROADWAYS

Approval of a subdivision plat by the _____ County Commissioners Court does not constitute acceptance of the roads shown thereon.

All roads, whether maintained by the County, by the individual property owner, or by a homeowner's association, shall be constructed at the owner/subdivider/developer's expense in accordance with these Regulations and shall be classified as one of the two following types of roads:

- a. Publicly dedicated, paved, and to be maintained by _____ County, after Commissioners Court acceptance for maintenance, with construction in accordance with the Specifications outlined in these Regulations.
- b. Private, paved, and to be maintained by a Homeowner’s Association or property owners in perpetuity (or until constructed to the then applicable County standards for acceptance of maintenance, and accepted for maintenance by the Commissioners Court) and constructed in accordance with the Specifications outlined in these Regulations.

_____ County reserves the right to deny an application for acceptance of any subdivision street or road for permanent public maintenance by the County. No roads or streets will receive consideration for final **acceptance** into the County Road System by the Commissioners Court until at least **two (2) years** after original construction of streets and roads are completed. In Subdivisions in which insufficient development or building has taken place after the two-year period and where there has been insufficient use of the streets and roads to insure their stability, then such streets and roads will not be accepted by the Commissioners Court until such time as there is sufficient development to insure street and road stability. Sufficient development shall be defined as fifty percent (50%) occupancy of the total lots or tracts within said subdivision. Upon final approval, title to all streets and roads shall be conveyed to the County for their maintenance by a Warranty Deed, or Grant of Right-of-Way, in a form which shall be acceptable to the Commissioners Court. Accompanying such deed shall be an adequate description of streets and roads, either by reference to the approved subdivision plat or by field notes prepared by a Registered Professional Engineer from a survey made on the ground. **From the date of adoption of this Order forward, all streets and roads in any subdivision for which a plat has been filed shall adhere to the Road Construction Specifications which follow, whether or not an eventual request for County maintenance is planned.**

In subdivisions that are developed as “gated communities,” it is the responsibility of the Owner/subdivider/developer, property/homeowner’s association and/or the individual property owners to provide a means of access to emergency responders.

Road Construction Specifications (see Appendix N and Bond Requirements)

- 1. Streets or roads as defined herein shall conform with the following:

Minimum right-of-way.....	60 feet
Minimum crown width of roadway.....	30 feet
Minimum width of base material.....	30 feet
Minimum depth of compacted base material at crown...	6 inches
Minimum height at crown.....	6 inches
Minimum height of base at shoulder.....	6 inches
Minimum width of surface.....	30 feet
Minimum width of curbed section, when curbed.....	36 feet

- 2. Residential streets shall have a minimum width of right-of-way of sixty feet (60') unless more is needed for drainage purposes. The base course of the roadway section shall be a minimum of twenty feet (20') Type A Grade 2 flexible base compacted to ninety-five percent (95%) standard proctor density at a depth of six inches (6"). The subgrade shall be stabilized to a

depth of six inches (6") and compacted to ninety-five percent (95%) proctor density.

3. All roads or streets more than one hundred feet (100') in length shall either be connected at both ends to a dedicated street or be provided with a turnaround having a minimum radius of forty feet (40') and a minimum right-of-way of sixty feet (60').
4. All roads or streets shall have a minimum grade of four-tenths percent (0.4%). Grades of more than ten percent (10%) shall only be allowed upon approval of the County.
5. A proposed subdivision that adjoins or encompasses an existing public street, that does not conform to minimum right-of-way requirements of these regulations, shall provide for the dedication of additional right-of-way along either or both sides of said street so that the minimum right-of-way required by these regulations can be established. If the proposed subdivision abuts only one side of said street, then a minimum of half of the right-of-way shall be dedicated by such subdivision.
6. Where any portion of a road or street has been dedicated in an adjoining subdivision, adjacent to and along the common property line of the two subdivisions, enough width of right-of-way must be dedicated in the new subdivision to provide the minimum width specified herein.
7. Roads or streets which are a continuation of any existing road or street shall take the name of the existing road or street.
8. A cul-de-sac shall have a minimum length of 600 linear feet. (Measured along the centerline).
9. All roads or streets preferably shall intersect at a ninety-degree angle. Where this is not possible, the intersection, on the side of the acute angle, shall be rounded with a curve or a cut-back, but in no case, shall the curve have less than a twenty-five-foot (25') radius.
10. New roads or street, which are a continuation of an existing road or street, shall be a continuation, without off-set, of the existing road or street.
11. Where roads or streets in an adjoining subdivision end at the property line of an existing subdivision, the said roads or streets shall be continued throughout the new subdivision. Where there are no adjacent connections platted, the roads in the new subdivision shall be a reasonable projection of the roads or streets in the nearest subdivisions.
12. No decorative squares, trees, "islands", ornamental entrances or any other obstruction to traffic shall be constructed or preserved within the right-of-way of a road dedicated to the public without written permission of the Commissioners Court. If landscaping and/or irrigation is proposed within the right-of-way, the owner/subdivider/developer shall create a body (municipal utility district, home owner's association, neighborhood association, etc.), that will be responsible for the maintenance and liability of the landscaping and/or irrigation system. This body shall have assessment authority to insure the proper funding for maintenance.
13. The entire right-of-way will be cleared of all timber, roots, brush, fences, boulders, or other obstructions, unless a variance is granted by the Commissioners Court. Upon completion of all

construction, the right-of-way shall be seeded with native grasses, or other plants as approved by the Commissioners Court.

14. Sub-grade. The sub-grade shall be compacted by ordinary compaction by any method, type, and size of equipment that will give the required compaction. The sub-grade must be inspected and approved either by the Commissioners Court, the individual Commissioner for that precinct, or a designated Court representative prior to any application of base material.

15. Base Material. Base Material shall be delivered in vehicles of uniform capacity and it shall be the responsibility of the Contractor that the required amount of the specified material shall be delivered in each 100 feet station. The material shall be scarified, thoroughly wetted, mixed, manipulated, and bladed so as to secure a uniformly wetted material and pulled in over the surface in courses and set under the action of blading and rolling. All irregularities, depressions, or weak spots which develop shall be corrected immediately by scarifying the area affected, adding suitable material as required, reshaping and re-compacting by sprinkling and rolling. The base must be inspected and approved by the Commissioner for that precinct or a designated Court representative prior to the application of any surface treatment.

**Set-Back Lines from roadways pursuant to Chapter 232 and 233,
Texas Local Government Code**

1. Side lot line should normally be at a ninety-degree angle to the street.
2. All straight lines shall clearly show the length of the line, and the plat shall show enough information to readily determine the bearing of all lot lines.
3. All curved lot lines shall clearly show the length of the arc and radius of the curve or show enough information on the plat to readily determine the radius of the curve.
4. Building and set-back lines shall be fifty feet (50') from the edge of the right-of-way on all state and federal roads, and twenty-five feet (25') on all other roads. Building and set-back lines shall be shown on both the preliminary and final plats. If the above set-backlines differ from those adopted by a municipality with extraterritorial jurisdiction, the set-back of the municipality shall apply.
5. Mailboxes shall be set a minimum of three feet (3') from the edge of the roadway driving surface or one foot (1') behind curbs. When placements of the mailbox outside the three-foot (3') minimum is not possible, a mail box of "breakaway design" should be used.
6. All mailboxes within the County right-of-way shall meet the current TXDOT standards.
7. Mailboxes in subdivisions must meet Post Office requirements and must be placed in a manner that does not interfere with the traffic's line of vision.

Cattle Guards. The Commissioner in whose precinct the subdivision is located may authorize the installation of cattle guards. When permitted, a cattle guard shall not be less than six (6) feet in length, measured along the centerline of the road, and of width not less than two (2) feet greater than the width of the pavement or a maximum width of twenty (20) feet. Units may be prefabricated or welded in place and

shall be built to support any and all traffic that may be encountered on said roadway. Attached hereto as Appendix Q are specifications for cattle guards that will be approved by the Commissioners Court.

Inspections. Proposed roads and drainage will be inspected by an authorized representative of the Commissioners Court and at reasonable intervals as directed by the Commissioners Court. The expense of these inspections will be the responsibility of the Owner/subdivider/developer.

Other Provisions. In a subdivision where water lines or other utilities are installed in rights-of-way, they shall be located off and away from the roadways (paved center portion and shoulders). Fire hydrants shall be equipped with connections compatible with local Fire Department equipment.

Should roads and streets be dedicated to and accepted by _____ County so that future maintenance responsibilities become a function under the _____ County Commissioners Court, the installation of any further water or utility lines, side roads, *etc.* on right-of-way shall be prohibited unless expressly permitted in writing by the Commissioners Court. (see Appendix J: Permit to Construct Within Right-of Way and Appendix M: Notice of Proposed Utility Line Installation)

Subdivisions must have control signs, guardrails, and other safety features installed at required locations on all subdivision rights-of-way dedicated for public use. Culverts and bridges shall be at least as wide as the roadway portions (pavement and shoulders) of the streets and roads. Bridge abutments or other drop-offs located at the edge of the shoulder portions of any road or street shall be indicated by installation of protective posts or other devices equipped with reflectorized markers.

Right-of-way dedicated to public use shall be kept clear of tall weeds and brush so that property lines, drainage ditches, and hazardous conditions shall be readily distinguishable. Large trees which lend natural beautification to an area may be left in place on a right-of-way provided that safety on the streets and roads is not impaired.

The installation of any traffic control sign, such as denoting speed limits, yield right-of-way, stop signs, stop ahead signs, *etc.*, on all roads, streets, and thoroughfares dedicated to public use in subdivisions in _____ County whose roads have been accepted by the County must be approved by the Commissioners Court and shall be coordinated with the precinct Commissioner concerned and with the _____ County Sheriff's Department, which shall have control of law enforcement activities on all roads, streets, and thoroughfares dedicated to public use in subdivisions in _____ County whose roads have been accepted by the County. Speed limit designations of public streets should be assigned in accordance with street and road conditions. Thoroughfares not dedicated to public usage shall be clearly marked as such.

In cases where the new roads and streets as platted intersect with established roads and streets, the new roads and streets shall be, if practicable, a continuation without offset of any intersecting road or street on the opposite side of said established road or street.

Adequate off-street parking space must be provided in business or commercial areas.

Rural Addressing Signage. The initial expense of street sign placement in new subdivisions shall be the responsibility of the Owner/subdivider/developer, with sign type and location in compliance with County standards and approved by the _____ County Commissioners Court as part of acceptance of the subdivision plat.

FINAL INSPECTION

The owner/subdivider/developer, upon completion of drainage, roads, streets or other facilities intended for the use of the public, or purchasers or owners of lots fronting or adjacent there to, shall request from the County a final inspection. The precinct Commissioner or their designee will inspect, within 10 days, the completed work for compliance. The owner/subdivider/developer will be notified in writing, within 10 days of the final inspection, of approval or any work not found in compliance with these Subdivision Regulations. If substantial patching is required during the two (2) year maintenance period, roads or streets must be resurfaced at owner/subdivider/developers' expense.

PENALTIES FOR VIOLATION

1. The Commissioners Court of _____ County will cause an employee of the court, or any other person or persons it so designates, to review periodically deeds or sales contracts being recorded in the County Clerk's office to see that any subdivision affected thereby shall comply with requirements of these regulations and state law.
2. If deeds, contracts of sale, transfers of title, or other transactions do not comply with the plat requirements as set forth in these regulations and state law, the Commissioners Court of _____ County or its representative can so notify the party selling or transferring title in whole or in part to comply with these regulations.
3. In the event the notified party refuses to comply with said requirements, the Commissioners Court of _____ County can take appropriate action to obtain compliance.
4. A person commits an offense if the person knowingly or intentionally violates a requirement of these Regulations, including the Road Design and Construction Specifications incorporated into these Regulations and any appendices attached to these regulations, and incorporating the _____ County for On-Site Sewage Facilities Regulations. An offense under this provision is a Class B misdemeanor punishable by fine or imprisonment or both.
5. At the request of the Commissioners Court, the County Attorney or legal counsel may file an action in a court of competent jurisdiction to:
 - a. Enjoin the violation or threatened violation of a requirement established by or adopted by the Commissioners Court under these Regulations; and/or
 - b. Recover damages in an amount adequate for the County to undertake any construction or other activity necessary to bring about compliance with a requirement established by or adopted by the Commissioners Court under these Regulations.
 - c. Where appropriate, criminal penalties may apply and the County will seek such penalties for knowing, willful or reckless violations of these rules and regulations.

Adoption Date:

County Judge, _____ County, Texas

County Clerk, _____ County, Texas

Appendix A

Name of Subdivision: _____

Contact Person: _____ Phone Number: _____

COUNTY
SUBDIVISION PLATTING CHECKLIST
FIRST READING
(PRELIMINARY)

- | YES | NO | N/A | |
|--------------------------|--------------------------|--------------------------|---|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Name of proposed subdivision. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Name and address of Owner/subdivider/developer. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Volume, page and reference names of adjoining owners. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Volume, page and reference land use of adjoining owners. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Master Development Plan (if subdivision is a portion of a larger tract). |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Location map. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Scale (not smaller than 1" =200'). <i>If parent tract is larger than 320 acres, scale may be 1" =1,000' w/proposed plat 1" =200'.</i> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | North directional arrow. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Contour information – rivers, creeks, bluffs, etc. (no greater than 20' intervals) |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Major topographic features. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Total acreage in subdivision. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Total number of lots in subdivision. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Typical lot dimensions. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Land use of lots, parks, greenbelts. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Total length of roads. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Width of right-of-way. |

PRELIMINARY CHECKLIST
(continued)

- Special flood hazard areas/note.
 - Road maintenance requested (County/Home Owner's Assn.).
 - Approval by TxDOT or County for driveway entrance(s).
 - Location of wells - water, gas, & oil, where applicable & unused capped statement.
 - Plat Filing Fees paid. (receipt from County Clerk required)
 - On-Site Sewage Facility Preliminary plan, Inspector's Approval
 - Acknowledgement of Rural Addressing / Signage.
 - Water Availability Study.
 - Tax Certificates and rollback receipts if required.
-

Signature of Reviewer

Date of Review

ADDITIONAL REQUIREMENTS:

ALL ITEMS ON THIS CHECKLIST MUST BE IN THE HANDS OF THE COUNTY JUDGE'S OFFICE NO LESS THAN THIRTY (30) DAYS PRIOR TO THE COMMISSIONERS COURT HEARING DATE.

Appendix B

**COUNTY SUBDIVISION PLATTING CHECKLIST
SECOND READING (FINAL)**

Subdivision name: _____

YES NO N/A

- | | | | |
|--------------------------|--------------------------|--------------------------|--|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | All information required for preliminary plat. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Lot and block numbers. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Street names, <i>must be pre-approved by 9-1-1 Coordinator.</i> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Acreage of each lot or parcel. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Name and address of Surveyor/Engineer. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Location and size of drainage structures. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Location, size, and proposed use of easements. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Incorporated City's Boundary/ETJ Note. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Servicing Utilities Note. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Certification from licensed professional engineer regarding utilities. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Restrictive covenants. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Tax certificates and rollback receipts if required. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Home Owner's Association Incorporation articles and by-laws (if applicable). |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Construction plans of roads and drainage improvements. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Receipt showing payment of preliminary plat fees. |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | Sign-off for TxDOT road access, if applicable. |

Appendices:

FINAL CHECKLIST
(continued)

Appendices:

YES	NO	N/A	
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix C (1) – Certificate of Dedication by Owner/subdivider/developer (when owner/subdivider/developer is an individual)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix C (2) – Certificate of Dedication by Owner/subdivider/developer (when owner/subdivider/developer is a corporation)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix D – Certificate of Recording (if applicable)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix E – Water Supply Certificate
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix F – Certificate of Surveyor
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix G – Certificate of Engineer
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix H – Certificate of OSSF Inspector’s Approval
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix I-Certificate of Road Maintenance (when roads are to be retained as private roads)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix J – Certificate of County Road Maintenance Disclaimer
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix K-Certificate of County Approval of Plat
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix L-Permit to Construct Driveway in County RoW
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix M-Lienholder’s Acknowledgement
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix N-Revision to Plat (if applicable)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix O-Notice of Utility Installation in County RoW
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix P-Plans and Specifications for Cattleguard (if applicable)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix Q-Cross Section Road Standards
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Appendix R-Summary of Road Standards

FINAL CHECKLIST
(continued)

Appendices:

YES NO N/A

 Appendix S-Development Fees

Signature of Reviewer

Date of Review

ADDITIONAL REQUIREMENTS:
ALL ITEMS ON THIS CHECKLIST MUST BE IN THE HANDS OF THE COUNTY
JUDGE'S OFFICE NO LESS THAN THIRTY (30) DAYS PRIOR TO THE
COMMISSIONERS COURT HEARING DATE.

Appendix C (1)

CERTIFICATE OF DEDICATION BY OWNER/SUBDIVIDER/developer
(When owner/subdivider/developer is an Individual)

THE STATE OF TEXAS §
 §
COUNTY OF _____ §

KNOW ALL MEN BY THESE PRESENT, that I, _____,
owner/subdivider/developer of _____ acres of land out of the
_____ Survey, _____ County, Texas as
conveyed to me by deed dated _____, and recorded in Volume _____, Page
_____, Real Property Records of _____ County, Texas, **DO**
HEREBY SUBDIVIDE _____ acres of land out of said Survey,

*(Note: if the subdivision lies in more than one survey, determine an acreage in
each survey and repeat for each original survey within the subdivision)*

to be known as the _____ Subdivision, in accordance with the plat
shown hereon, subject to any and all easements or restrictions heretofore granted and do hereby
dedicate to the public (or "owners of the property shown hereon" for private streets) the use of the
streets and easements shown hereon.

WITNESS MY HAND, this the ____ day of _____, A.D., 20__.

(Owner/subdivider/developer's name)

THE STATE OF TEXAS §
 §
COUNTY OF _____ §

BEFORE ME, the undersigned authority, on this day personally appeared
_____, known by me to be the person whose name is
subscribed to the foregoing instrument and acknowledged to me that (s)he executed the same for
the purposes and consideration of therein stated.

GIVEN UNDER MY HAND AND SEAL OF OFFICE this the _____ day of
_____, A.D., 20__.

Notary Public in and for
The State of Texas

Appendix D

CERTIFICATE OF RECORDING

THE STATE OF TEXAS §
 §
COUNTY OF _____ §

I, _____, County Clerk of _____ County, Texas, do hereby certify that the foregoing instrument of writing with its certificate of authentication was filed for record in my office on the _____ day of _____, 20____, at _____ o'clock __m., and duly recorded on the _____ day of _____, A.D., 20____, at _____ o'clock __m., in the Real Property Records of _____ County, Texas in Volume _____, Page _____.

WITNESS MY HAND AND SEAL OF OFFICE this the _____ day of _____, A.D., 20____.

COUNTY CLERK
_____ **COUNTY, TEXAS**

Appendix E

WATER SUPPLY CERTIFICATE

“No structure in this subdivision shall be occupied until connected to either: an individual water well, the location of which has been approved by the Hickory Underground Water Conservation District, a TCEQ approved public water supply system (described below), or other domestic water supply subject to approval by the _____ County Commissioners Court.”

Underground Water Conservation District Date

Name of Public Water Supply System Date

Signature & Title of Authorized Agent

Other Proposed Domestic Water Supply (Please specify): _____

Appendix F

CERTIFICATE OF SURVEYOR

THE STATE OF TEXAS X
 X
COUNTY OF _____ X

KNOW ALL MEN BY THESE PRESENT, that I, the undersigned, a Registered Professional / State Land Surveyor in the State of Texas, do hereby certify that this Plat complies with the survey related requirements of the _____ County Subdivision Regulations and I further certify that this plat is true and correctly made and is prepared from an actual survey of the property made under my supervision on the ground and that the corner monuments were properly placed under my supervision.

Registered Professional / State Land Surveyor Date

License No. _____

Seal:

Appendix G

CERTIFICATE OF ENGINEER

THE STATE OF TEXAS X
 X
COUNTY OF _____ X

KNOW ALL MEN BY THESE PRESENTS, that I, the undersigned, a Registered Professional Engineer in the State of Texas, hereby certify that this plat complies with the engineering related requirements of the _____ County Subdivision Regulations.

Registered Professional Engineer

Date

License No. _____

Seal:

[NOTE: *The engineer may be required to be present for questioning at the presentation of the plat to the Commissioners Court.*]

Appendix H

CERTIFICATE OF ON-SITE SEWAGE FACILITY INSPECTOR'S APPROVAL

THE STATE OF TEXAS §
COUNTY OF _____ §

KNOW ALL MEN BY THESE PRESENTS, that I, the undersigned, a Licensed On-Site Sewage Facility Inspector in the State of Texas, hereby certify that I have inspected the On-Site Sewage Facilities for this plat, and the same complies with the related requirements of the _____ County Subdivision Regulations and the TCEQ.

On Site Inspector

Date

License No. _____

Seal:

[NOTE: *The inspector may be required to be present for questioning at the presentation of the plat to the Commissioners Court.*]

Appendix I

CERTIFICATE OF ROAD MAINTENANCE
(When roads are to be maintained as Private Roads)

“In approving this plat by the Commissioners Court of _____
County, Texas, it is understood that all roads shown hereon are private roads and shall remain the
property of the Owner/subdivider/developer and/or subsequent owners of the property. The
construction, repair, and maintenance of these roads and any associated drainage improvements
will be the responsibility of the Owner/subdivider/developer and/or subsequent owners of the
subdivision and will not be the responsibility of _____ County.”

Owner/subdivider/developer or Representative

Date

Appendix J

CERTIFICATE OF ROAD MAINTENANCE

(When roads are to be dedicated to _____ County for maintenance)

“In approving this plat by the Commissioners Court of _____ County, Texas, it is understood that all roads shown hereon are private roads and shall remain the property of the Owner/subdivider/developer and/or subsequent owners of the property until such time as the Commissioners Court approves the dedication of the roads to the County for maintenance by way of a Warranty Deed. Acceptance of this plat does not constitute acceptance of the roads shown hereon by _____ County.”

Owner/subdivider/developer or Representative

Date

Appendix K

CERTIFICATE OF COUNTY APPROVAL OF PLAT

THE STATE OF TEXAS X
X
COUNTY OF _____ X

I, _____, County Clerk of _____ County, Texas, do hereby certify that on the _____ day of _____, A.D., 2____, the Commissioners Court of _____ County, Texas, passed an Order authorizing the filing for record of this Plat, and said Order has been duly entered in the minutes of the said Court in Book _____, Page _____.

WITNESS MY HAND AND SEAL OF OFFICE this the _____ day of _____, A.D., 20_____.

COUNTY CLERK

COUNTY, TEXAS

COUNTY JUDGE

COUNTY, TEXAS

Appendix L

COUNTY
PERMIT TO CONSTRUCT DRIVEWAY WITHIN
COUNTY ROAD RIGHT-OF-WAY

Applicant: _____

County Road Name _____

Address: _____ Permit # _____

_____ Phone No. () _____

I, Commissioner _____ of Precinct # _____
_____ County, Texas, authorize
_____, hereinafter called the Grantee, to (re)construct an
access driveway on the County road right-of way abutting County Road
_____ in _____ County, Texas, located
at _____;

SUBJECT TO THE FOLLOWING:

1. The Grantee is responsible for the culvert costs and installation.
2. Design of facilities shall be as shown on the sketch on page 2.
3. All construction and materials shall be subject to inspection and approval by the County.
4. The County reserves the right to require any changes, maintenance, or repairs as may be necessary to provide protection of life or property on or adjacent to the County road. Changes in design will be made only with approval of the County.
5. The Grantee shall hold harmless the County and its duly appointed agents and employees against any action for personal injury or property damage sustained by reason of the exercise of this permit.
6. The Grantee shall not erect any sign on, or extending over, any portion of the County road right-of-way.
7. Vehicle service fixtures such as fuel pumps, fuel tanks, vendor stands, etc., shall be located at least 12 (twelve) feet from the right-of-way line to ensure that vehicles being serviced from these fixtures will be off the County road.
8. Entrances must be constructed in such a way as to keep obstructions from being present in the right-of-way.

9. Mail boxes must be mounted on break away stands and be located so that boxes may be serviced and used from off the pavement.
10. This permit will become null and void if the above referenced driveway facilities are not constructed within six (6) months from the issuance date of this permit.
11. The Grantee will contact the Court's representative _____ at telephone number (325) _____ at least twenty-four (24) hours prior to beginning construction which is authorized by this permit.

DATE OF ISSUANCE: _____

ROAD ADMINISTRATOR: _____

The undersigned hereby agrees to comply with the terms and conditions set forth in this permit for construction of an access driveway on the County road right-of-way.

PRINTED NAME: _____

SIGNATURE: _____

DATE: _____

SKETCH OF INSTALLATION

Appendix M

LIENHOLDER'S ACKNOWLEDGEMENT

I (We), (Name of Lienholder(s)) _____,
owner/subdivider/developer(s) and holder(s) of a lien(s) against the property described within the
Revision to Plat, said lien(s) being evidenced by instrument of record in Volume _____, Page
_____, of the Real Property Records of _____ County, Texas, do
hereby in all things subordinate to said Revision of Plat said lien(s), and I (we) hereby confirm
that I am (we are) the present owner/subdivider/developer(s) of said lien(s) and have not assigned
the same nor any part thereof.

(Signature of Lienholder(s))

(Printed name(s))

THE STATE OF TEXAS X
COUNTY OF _____ X

SWORN TO AND SUBSCRIBED before me by _____
on the _____ day of _____, 20_____.

Notary Public in and for
The State of Texas

Appendix N
REVISION TO PLAT

Name of Subdivision: _____

Recorded in Volume _____, Page _____ of the Real Property Records of
_____ County, Texas

Commissioner Precinct No.: _____

Owner/subdivider/developer:

Owner/subdivider/developer's Mailing Address:

Owner/subdivider/developer's Phone Number(s):

Lots or Tracts to be revised (include Unit, Section or Phase # if applicable):

Resulting Lot Number to be Known As: _____

Lienholder: _____ Yes _____ No
If yes, Name of Lienholder: _____
(Attach Lienholder's Acknowledgement, Appendix K)

IF REVISED PLAT INCLUDES ANY CHANGES TO AN EXISTING UTILITY EASEMENT, RELEASE OF SAID EASEMENTS BY THE UTILITY PROVIDERS IS REQUIRED BEFORE APPROVAL OR FILING OF SAID PLAT.

The signature affixed below will certify that the owner/subdivider/developer of the described property does hereby request to revise the plat of the property. The owner/subdivider/developer certifies that any and all lienholders have acknowledged this revision as per the attached Lienholder's Acknowledgement, if applicable.

(Owner/subdivider/developer's Signature)

(Printed name)

THE STATE OF TEXAS

X
X

COUNTY OF _____

X

SWORN TO AND SUBSCRIBED before me by _____

_____ on the _____ day of _____, 20____.

Notary Public in and for
The State of Texas

APPROVED BY COMMISSIONERS COURT ON THE _____ DAY OF _____,
20____.

JUDGE

COUNTY

ATTEST: _____
_____ COUNTY CLERK

Appendix O

NOTICE OF PROPOSED UTILITY LINE INSTALLATION
COUNTY RIGHT OF WAY AND PERMIT

TO: Commissioner _____
Precinct No. _____
Address _____

Formal Notice is hereby given that _____ proposes to place a _____ line within the right of way of County Road _____ as follows: (list location, length, general design, etc.)

Installation will begin on or after the _____ day of _____, 20____.

The line will be constructed and maintained on the road right-of-way as directed by _____ County Commissioner Precinct No. _____.

The location and description of the proposed line is more fully shown on the attached drawings.

Applicant will insure that traffic control measures complying with applicable portions of the Texas Manual of Uniform Traffic Control Devices will be installed and maintained during the installation.

If the proposed installation is a parallel installation, the installation shall be located _____ feet within the edge of the right-of-way and at least _____ feet in depth, unless otherwise approved by the County.

_____ The installation shall not damage any portion of the road and adequate provisions must be made to cause minimum inconvenience to traffic and adjacent property owners during installation.

OR

_____ The installation shall damage a portion of the road. Applicant will return the road to its pre-installation condition at Applicant's expense within _____ days of installation. During installation adequate provisions must be made to cause minimum inconvenience to traffic and adjacent property owners during installation.

Applicant agrees that any damages sustained to the line installed under this proposal as a result of road construction and/or maintenance, including but not limited to mowing, ditch cleaning, culvert repair or replacement, roadway excavation, and base work shall be the sole burden and expense of the owner/subdivider/developer of the utility line.

Applicant agrees to give _____ County Commissioner Precinct No. _____ fifteen (15) days prior notice of any routine or periodic maintenance which requires

interruption of traffic and pruning of trees within the road right-of way. County may provide specifications for the extent and methods governing trimming, cropping, tree balance, type of cuts, painting cuts, and clean up.

Applicant agrees that _____ County does not purport to grant any right, claim, title, or easement in or upon this road, and Applicant further agrees that _____ County may require owner/subdivider/developer to relocate line, subject to provisions of governing laws, upon the giving of _____ day's written notice.

In the event Applicant fails to comply with any of the requirements as set forth above, _____ County may take such action as it deems appropriate to compel compliance

Additional Special Provisions:

By signing the below, I certify that I am Applicant or am authorized to represent Applicant and that Applicant agrees to be bound by the provisions of the Notice and Permit.

APPLICANT:

Name: _____
Authorized agent: _____
Address _____
Phone _____

_____ COUNTY:

Commissioner _____
Precinct No. _____
Address _____
Phone _____

Appendix P

IN THE COMMISSIONERS COURT
Of

_____ COUNTY, TEXAS

ESTABLISHMENT OF PLANS AND SPECIFICATIONS FOR
A STANDARD CATTLE GUARD TO BE USED
ON COUNTY ROADS WITHIN _____ COUNTY, TEXAS

WHEREAS, §251.003 (a)(1) of the Texas Transportation Code grants the _____ County Commissioners Court the authority to make and enforce all necessary rules and orders for the construction and maintenance of public roads; and

WHEREAS, cattle guards currently exist on County maintained roads; and

WHEREAS, _____ County anticipates requests from a property owner/subdivider/developer proposing to construct new cattle guards on an existing County maintained road; and

WHEREAS, Texas Transportation Code §251.009 (a) states that the _____ County Commissioners Court may authorize the construction of a cattle guards on a county road of any class; and

WHEREAS, §251.009 (b) of the Texas Transportation Code requires that the _____ County Commissioners Court establish plans and specifications for a standard cattle guard to be used on the county roads;

NOW, THEREFORE, IT IS ORDERED BY THE COMMISSIONERS COURT OF _____ COUNTY, that the standards herein attached, shall serve as the standard for construction of cattle guards on County maintained roads; and

IT IS FURTHER ORDERED BY THE COMMISSIONERS COURT OF _____ COUNTY, that a person proposing to construct a cattle guard on a County maintained road may submit a Permit to Construct Cattle Guard on _____ County Right of Way for consideration by the _____ County Commissioners Court.


IT IS FURTHER ORDERED BY THE COMMISSIONERS COURT OF _____ COUNTY, that a person proposing to construct a cattle guard on a County maintained road may submit an alternate cattle guard design, prepared by a Registered Engineer, for consideration by the _____ County Engineer, and the County Engineer's decision may be appealed to Commissioners Court.

Approved, this _____ day of _____, 20__ by the
_____ County Commissioners Court.


County Judge

County Commissioner Pct. 1


County Commissioner Pct. 2



PLAN VIEW




SECTION A-A



GENERAL NOTES
 QUANTITIES SHOWN ARE FOR CONTRACTOR'S INFORMATION ONLY.
 ALL DIMENSIONS RELATION TO REINFORCING STEEL, UNLESS TO THE CENTERLINE OF BARS.
 RECOVERY PIPE IS CONCRETE, LEASTING 110'-0" DIA. (1) AND REINFORCING ACCORDANCE WITH T&E 204, AS AN ALTERNATIVE, 1/2" DIA. AS SHOWN.
 IF HOOD IS ENCOUNTERED, DEPTH OF FOUNDATION MAY BE VARIED AS DIRECTED.
 RECOVERY PIPE CONFORMING TO ASTM A513 OR ASTM A513 TYPE 1 OR 2, OR 4, OR 5, STANDARD WEIGHT.
 HOT DIP GALVANIZED CATTLE GUARD IN ACCORDANCE WITH ASTM A133 AND A133.



SECTION B-B



BARS B1 BARS B2


BILL OF MATERIALS

NO.	DESCRIPTION	SIZE	LENGTH
1	3" PIPE	18'-0"	1
2	4" PIPE	21'-0"	1
3	1/2" DIA. X 12" GALV. BOLTS	12	1
4	1/2" DIA. X 12" GALV. BOLTS	12	1
5	4" DIA. X 12" GALV. BOLTS	12	1
6	4" DIA. X 12" GALV. BOLTS	12	1
7	4" DIA. X 12" GALV. BOLTS	12	1
8	4" DIA. X 12" GALV. BOLTS	12	1
9	4" DIA. X 12" GALV. BOLTS	12	1
10	4" DIA. X 12" GALV. BOLTS	12	1
11	4" DIA. X 12" GALV. BOLTS	12	1
12	4" DIA. X 12" GALV. BOLTS	12	1
13	4" DIA. X 12" GALV. BOLTS	12	1
14	4" DIA. X 12" GALV. BOLTS	12	1
15	4" DIA. X 12" GALV. BOLTS	12	1
16	4" DIA. X 12" GALV. BOLTS	12	1
17	4" DIA. X 12" GALV. BOLTS	12	1
18	4" DIA. X 12" GALV. BOLTS	12	1
19	4" DIA. X 12" GALV. BOLTS	12	1
20	4" DIA. X 12" GALV. BOLTS	12	1
21	4" DIA. X 12" GALV. BOLTS	12	1
22	4" DIA. X 12" GALV. BOLTS	12	1
23	4" DIA. X 12" GALV. BOLTS	12	1
24	4" DIA. X 12" GALV. BOLTS	12	1
25	4" DIA. X 12" GALV. BOLTS	12	1
26	4" DIA. X 12" GALV. BOLTS	12	1
27	4" DIA. X 12" GALV. BOLTS	12	1
28	4" DIA. X 12" GALV. BOLTS	12	1
29	4" DIA. X 12" GALV. BOLTS	12	1
30	4" DIA. X 12" GALV. BOLTS	12	1
31	4" DIA. X 12" GALV. BOLTS	12	1
32	4" DIA. X 12" GALV. BOLTS	12	1
33	4" DIA. X 12" GALV. BOLTS	12	1
34	4" DIA. X 12" GALV. BOLTS	12	1
35	4" DIA. X 12" GALV. BOLTS	12	1
36	4" DIA. X 12" GALV. BOLTS	12	1
37	4" DIA. X 12" GALV. BOLTS	12	1
38	4" DIA. X 12" GALV. BOLTS	12	1
39	4" DIA. X 12" GALV. BOLTS	12	1
40	4" DIA. X 12" GALV. BOLTS	12	1
41	4" DIA. X 12" GALV. BOLTS	12	1
42	4" DIA. X 12" GALV. BOLTS	12	1
43	4" DIA. X 12" GALV. BOLTS	12	1
44	4" DIA. X 12" GALV. BOLTS	12	1
45	4" DIA. X 12" GALV. BOLTS	12	1
46	4" DIA. X 12" GALV. BOLTS	12	1
47	4" DIA. X 12" GALV. BOLTS	12	1
48	4" DIA. X 12" GALV. BOLTS	12	1
49	4" DIA. X 12" GALV. BOLTS	12	1
50	4" DIA. X 12" GALV. BOLTS	12	1
51	4" DIA. X 12" GALV. BOLTS	12	1
52	4" DIA. X 12" GALV. BOLTS	12	1
53	4" DIA. X 12" GALV. BOLTS	12	1
54	4" DIA. X 12" GALV. BOLTS	12	1
55	4" DIA. X 12" GALV. BOLTS	12	1
56	4" DIA. X 12" GALV. BOLTS	12	1
57	4" DIA. X 12" GALV. BOLTS	12	1
58	4" DIA. X 12" GALV. BOLTS	12	1
59	4" DIA. X 12" GALV. BOLTS	12	1
60	4" DIA. X 12" GALV. BOLTS	12	1
61	4" DIA. X 12" GALV. BOLTS	12	1
62	4" DIA. X 12" GALV. BOLTS	12	1
63	4" DIA. X 12" GALV. BOLTS	12	1
64	4" DIA. X 12" GALV. BOLTS	12	1
65	4" DIA. X 12" GALV. BOLTS	12	1
66	4" DIA. X 12" GALV. BOLTS	12	1
67	4" DIA. X 12" GALV. BOLTS	12	1
68	4" DIA. X 12" GALV. BOLTS	12	1
69	4" DIA. X 12" GALV. BOLTS	12	1
70	4" DIA. X 12" GALV. BOLTS	12	1
71	4" DIA. X 12" GALV. BOLTS	12	1
72	4" DIA. X 12" GALV. BOLTS	12	1
73	4" DIA. X 12" GALV. BOLTS	12	1
74	4" DIA. X 12" GALV. BOLTS	12	1
75	4" DIA. X 12" GALV. BOLTS	12	1
76	4" DIA. X 12" GALV. BOLTS	12	1
77	4" DIA. X 12" GALV. BOLTS	12	1
78	4" DIA. X 12" GALV. BOLTS	12	1
79	4" DIA. X 12" GALV. BOLTS	12	1
80	4" DIA. X 12" GALV. BOLTS	12	1
81	4" DIA. X 12" GALV. BOLTS	12	1
82	4" DIA. X 12" GALV. BOLTS	12	1
83	4" DIA. X 12" GALV. BOLTS	12	1
84	4" DIA. X 12" GALV. BOLTS	12	1
85	4" DIA. X 12" GALV. BOLTS	12	1
86	4" DIA. X 12" GALV. BOLTS	12	1
87	4" DIA. X 12" GALV. BOLTS	12	1
88	4" DIA. X 12" GALV. BOLTS	12	1
89	4" DIA. X 12" GALV. BOLTS	12	1
90	4" DIA. X 12" GALV. BOLTS	12	1
91	4" DIA. X 12" GALV. BOLTS	12	1
92	4" DIA. X 12" GALV. BOLTS	12	1
93	4" DIA. X 12" GALV. BOLTS	12	1
94	4" DIA. X 12" GALV. BOLTS	12	1
95	4" DIA. X 12" GALV. BOLTS	12	1
96	4" DIA. X 12" GALV. BOLTS	12	1
97	4" DIA. X 12" GALV. BOLTS	12	1
98	4" DIA. X 12" GALV. BOLTS	12	1
99	4" DIA. X 12" GALV. BOLTS	12	1
100	4" DIA. X 12" GALV. BOLTS	12	1

CATTLE GUARD DETAILS (16' RECOVERY ZONE)

AUSTIN DISTRICT STANDARD

Project: _____
 Date: _____
 Scale: _____



Appendix R

SUMMARY OF _____ COUNTY ROAD STANDARDS

Average Daily Traffic (one-way trips) **	0-1000	1001-2500	2501-5000	5001-15000
Functional Classification	Local Street	Minor Collector	Major Collector	Minor Arterial
Design Speed	25 mph	35 mph	45 mph	55 mph
Number of Lanes	2	2	2	4
ROW Width	60'	60'	70'	100'
Width of Traveled Way	22'	22'	28'	48'
Width of Shoulders	4'	5'	6'	8'
Minimum Centerline Radius	175'	375'	675'	975'
Minimum Tangent Length between Reverse Curves Or Compound Curves	75'	150'	300'	500'
Minimum Radius for Edge of Pavement At intersections	25'	25'	25'	25'
Intersecting Street Angle	80-100	80-100	80-100	80-100
Maximum Grade *	11%	10%	9%	8%
Minimum Street Centerline Offset at Adjacent Intersections	125'	125'	125'	125'
Minimum Stopping Sight Distance	175'	250'	350'	550'
Minimum Intersection Sight Distance	250'	350'	450'	550'
Steepest Ditch Fore Slope Grade	4:1	4:1	4:1	6:1
Flood Design (year event)	10	15	25	25

- Any deviation from these standards must be the subject of an approved variance. *
- Lots that are restricted by plat note to one single-family residence shall be presumed to generate 10 one-way trips per day. Average daily traffic for all other lots shall be determined by the precinct commissioner of their designee. Factors to consider are lot size, other plat restrictions and the potential for future development. **
- The entire side ditch shall be totally contained within the road right-of-way or a dedicated drainage easement. Guardrails shall be required wherever the ditch depth exceeds 8' from the edge of the shoulder to the bottom of the ditch on local streets, 6' from the edge of the shoulder to bottom of the ditch on minor collectors and 4' from the edge of the shoulder to the bottom of the ditch on all others larger than a minor collector.
- Any development generating more than 15000 average daily traffic counts will be designed according to TxDot standards.

Appendix S
Development Fees

The following are a list of development fees for _____ County. These fees are subject to change.

Preliminary Plat without a designated floodplain:	\$1000.00 + \$10.00 per lot
Preliminary Plat in a designated floodplain:	\$1500.00 + \$10.00 per lot
Final Plat:	\$250.00

PASSED AND APPROVED THIS _____ DAY OF _____, 20____.

COUNTY JUDGE

Commissioner, Precinct 1

Commissioner, Precinct 2

Commissioner, Precinct 3

Commissioner, Precinct 4

ATTEST:

County Clerk



emb 103 - 10/24/20
7/19

Bruckner Truck Sales, Inc.
Retail Purchase Order


Date: February 6, 2020


CUSTOMER INFORMATION	
Name:	Tyler County #4
Address:	100 W Bluff St. Rm #203
CSZ:	Woodville, TX 75979
Phone:	409-283-7623 Cell: 409-429-4285
Fax:	Contact: Buck Hudson - Commission
Email:	bhudson@co.tyler.tx.gov

EQUIPMENT INFORMATION	
Stock #:	51215
Year:	2021
Make:	Mack
Model:	PI64T
VIN:	1M1PN4GYXMM007667
Salesman:	Josh Phillips

EQUIPMENT SPECIFICATIONS			
Engine Make:	Mack MP8-445C	Wheelbase:	219"
Horsepower:	445 w/ 1860 lb-ft Torque	Frame:	9.5mm Steel
Engine Brake:	Yes - Mack Powerleash for MP8	Interior Trim:	Standard Sierra Tan
Transmission:	Mack TMD12AFO-HD - mDrive 12-spd HD	Wheels Front:	Alcoa Clean Buff Polished Alum
Front Axle:	Mack - FXL14.6 - 14,600#	Wheels Rear:	Alcoa Clean Buff Polished Alum
Rear Axle:	Meritor - MT40-14X4D - 40,000#	Tire Size:	11R24.5
Rear Suspension:	Mack - Maxlite 40EZ - 40,000# Air-Ride	Tire Front:	Bridgestone R268 Ecopia
Ratio:	3.08	Tire Rear:	Bridgestone M726 EL A

Chassis Includes the Following Local Extras:		Amount
New Truck Prep		\$126,200.00
Chassis Tow 1yr/100k Extended Warranty		
Minimizer Poly 1/2 Fenders Installed		
Belly Dump Swithc Installed		
Electric Tarp Switch Installed		
HGAC Fee		
FOB: Tyler County #4		
Trade-In Information:		
Trade 1:	Trade 2:	
Allowances:		-
VIN:		
Year:		
Make:		
Model:		
Payoff:		-
OTHER CHARGES:		
Tax, Title, and License Fees (Estimated):		-
Purchase Coverage	Type: <u>EP2/EATS/HVAC - 5yr/300</u>	-
Insurance	Type: _____	-
Dealer Inventory Tax and Doc Fees		300.00
Cash Down Payment:		-
TOTAL:		\$126,500.00

Dealer Signature: 
Date: 2/6/2020

Customer Signature: 
Date: 02-24-20

A documentary fee is not an official fee. A documentary fee is not required by law, but may be charged to buyers for handling documents and performing services relating to the closing of a sale. A documentary fee may not exceed \$50 for a motor vehicle contract or a reasonable amount agreed to by the parties for a heavy commercial vehicle contract. This notice is required by law.

NOT AN INVOICE



**Bruckner Truck Sales, Inc.
Retail Purchase Order**

Date: February 6, 2020

CUSTOMER INFORMATION

Name: Tyler County #4

Address: 100 W Bluff St. Rm #203

CSZ: Woodville, TX 75979

Phone: 409-283-7623 Cell: 409-429-4285

Fax: Contact: Buck Hudson - Commission

Email: bhudson@co.tyler.tx.gov

EQUIPMENT INFORMATION

Stock #: 49939

Year: 2020

Make: CTS

Model: BDT40

VIN: 5TU114029LS000297


Salesman: Josh Phillips


EQUIPMENT SPECIFICATIONS

Type:	Belly Dump	X Members:	
Length:	40'	Floors:	
Width:	102"	Doors:	
Height:	10'	Posts:	
Front Wheel:	Powder Coated White Steel	GVWR:	
Rear Wheel:	Powder Coated White Steel	Tires:	11R24.5
Suspension:	Air-Ride	Add'l Specs:	Electric Tarp
Axle Capacity:	Tandem 25,000#	Add'l Specs:	Drop Legs Landing Gear

Chassis Includes the Following Local Extras:

	Amount
New Trailer Prep	\$37,900.00
FOB: Tyler County #4	
Federal Retail Excise Tax	
SALES PRICE BEFORE T T & L:	37,900.00
Trade-In Information: Trade 1: Trade 2:	
Allowances:	
VIN:	
Year:	
Make:	
Model:	
Payoff:	-
OTHER CHARGES:	
Tax, Title, and License Fees (Estimated):	-
Purchase Coverage Type: _____	-
Insurance Type: _____	-
Doc Fees:	300.00
Cash Down Payment:	-
TOTAL:	\$38,200.00

Dealer Signature: 
Date: 2/6/2020

Customer Signature: 
Date: 02/24/20

A documentary fee is not an official fee. A documentary fee is not required by law, but may be charged to buyers for handling documents and performing services relating to the closing of a sale. A documentary fee may not exceed \$50 for a motor vehicle contract or a reasonable amount agreed to by the parties for a heavy commercial vehicle contract. This notice is required by law.

NOT AN INVOICE



TYLER COUNTY VETERANS SERVICE OFFICE

201 Veterans Way, Ste 200 / Woodville, Texas

Veteran Service Officer Tina Cleberg

Office Manager Martha Kimbrough

VETERAN SERVICES:

- 164 Veterans have been provided service: 73 Calls, 58 follow-up and 33 Walk-in's for Feb 2020.
- A combined total of 320 Veterans have been provided service for 2020.

MONTHLY VAN REPORT:

- 10 days of transportation with 24 veterans taken to the Houston VA
- 5 volunteer drivers with a total of 77 hours and 2, 244 miles driven.
- 1 days where a volunteer escort rode with the driver

TRAINING:

- TRIPP Training completed on 02-11-2020.
Waiting on fingerprinting and background check
- UPCOMING: Regional Training, 28 -30 April 2020 Houston

EVENTS/PROJECT:

- Request for Volunteer Drivers in the Booster placed.
1 individual picked up an application

EVENT:

- Ceremony: Commissioners Court resolution, 02-10-2020
- Ceremony: Congressman Babin & Representative White
Flag, certificates provided to Mr. Randolph, 02-18-2020



14

TYLER COUNTY COMMISSIONERS COURT

County Courthouse, Room 101 / Woodville, Texas

Monday, February 24, 2020, 11:00 AM

MARTIN NASH
Commissioner, Pct. 1

STEVAN STURROCK
Commissioner, Pct. 2

MIKE MARSHALL
Commissioner, Pct. 3

CHARLES "BUCK" HUDSON
Commissioner, Pct. 4

DONECE GREGORY
County Clerk

JACQUES L. BLANCHETTE
County Judge

J. ERIC MAGEE
Legal Counsel

NOTICE Is hereby given that a **Regular Meeting** of the Tyler County Commissioners Court will be held on the date stated above, at which time the following subjects will be considered and/or discussed.

Bob
Jackie
Lynette
LeAnn

Amended Agenda

CALL TO ORDER

- Establish Quorum - Present
- Acknowledge Guests
- Invocation* - S. Sturrock
- Pledge of Allegiance* - S. Sturrock

* It is the practice of this governing body to exercise an invocation and pledge of allegiance. Anyone present offended by this practice is invited to step out of the courtroom and rejoin us upon completion.

I. PUBLIC COMMENTS

Members of the public are encouraged to speak to either their Commissioner or the County Judge regarding matters of their concern. The public is invited to attend all meetings of the Commissioners Court except Executive Sessions. Public participation is limited to that of an observer unless:

- 1) a member (or members) of the public is requested to address the Court on a particular issue(s); or
- 2) a member (or members) of the public completes a **Public Comment Participation Form** and submits it to the County Clerk **prior** to the CALL TO ORDER of the Court. **Public Comment Participation Forms** will be available prior to the start of Court from the County Clerk, County Judge's office, or on the county website. Each member of the public who appears before the Commissioners Court shall be limited to a maximum of five (5) minutes to make his/her remarks. Discussion on any specific topic will be restricted to 30 minutes total for all speakers on that topic to comment. Time for each speaker shall be maintained by the County Clerk or such other designated representative of the Commissioners Court.

II. CONSIDER/APPROVE/INFORMATIONAL

A. Minutes from previous meeting - J. Blanchette/Nonece Gregory, County Clerk

S.S.
B.H. ✓ 2-11-20 Minutes

B. Budget amendments/line item transfers - J. Blanchette/Jackie Skinner, County Auditor

✓ None

C. Accounts Payable/Paying County Bills - J. Blanchette/J. Skinner

S.S.
M.M. ✓ EVEREST: Will only pay the \$700.00 - radio Tower

S.S. / M.M. ✓ D. Monthly Report from District Clerk - J. Blanchette/Chyrl Pounds, District Clerk
accepted

M.M. / S.S. ✓ E. Bond for County Tax Assessor/Collector - J. Blanchette/Lynnette Cruse, County Tax Assessor/Collector
Approved Bond Get Chief Deputy Bonded.
Carried

J.B. / M.M. ✓ F. Suspending of Additional Architectural Services Pending Court Review of Construction Documents - J. Blanchette
→ Suspend Services
27th
Thursday Meeting 2 pm Workshop

J.A. / S.S. ✓ G. Approve as a Sponsor the Articles of Incorporation of the Southeast Texas Flood Control District and Appointing Directors for that Local Government Corporation - J. Blanchette
AMENDING Articles (wording)
Carries

J.B. / M.M. ✓ H. Appointments to 2020 Tyler County Census Complete Count Committee for the Intended Purpose of Assuring Efforts to have a Complete Count of all Tyler County Residents in the April 2020 Census - J. Blanchette
Steven's Pet. 2 Accept NAMES.
Carries

S.S. / M.M. ✓ I. Appointment of Cybersecurity Information Technology Administrator - J. Blanchette
Identify IT Person. DONALD CALHOON

~~BH~~ / M.M. ✓ J. Renewal of Postage Meters for Tyler County - J. Blanchette/J. Skinner
Co. clerk postage machine.
Carries. Renew Contract. w/P. Tney Bows

M.M. / A.H. ✓ K. Renewal of Sharp Copier Lease for Tyler County - J. Blanchette/J. Skinner
New Copiers will be changed out
Carries.

S.S. / M.M. ✓ L. Repair to Sheriff's Department Fiber Optic Line from Contingency - J. Blanchette/J. Skinner
Recommendation for a New line - \$9,890.86
Splice - \$5,889.17
Carries to replace the line

M.M. / B.H. ✓ M. County Subdivision Regulation, Including Standard Subdivisions, Manufactured Home Rental Communities, RV Parks and Related Matters, Including Establishing a Calendar for Further Hearings and/or Action on the Topic, Authorizing a Takings Impact Assessment, and Authorizing Publication of Notice for Public Hearings on the Topic - J. Blanchette

Tabled

J.B. / P.S. ✓ N. Purchase Air Conditioner for Nutrition Center - M. Nash

Carries

B.H. / M.M. ✓ O. Lease/Purchase of a 2021 Mack Haul Truck from Bruckner's Truck Sales to be Financed with First National Bank Leasing, Wichita Falls, TX - B. Hudson

1 New Dump Truck

Carries

B.H. / M.M. ✓ P. Purchase a 2021 Belly Dump Trailer from Bruckner's Truck Sales to be Financed with First National Bank Leasing, Wichita Falls, TX

Carries

J.B. III. JUDGE'S REPORT - Courthouse Remediation Update Suspending Add'l work

IV. EXECUTIVE SESSION

Consult with legal counsel for the Court in executive session held in accordance with Texas Government Codes 555.071(1)(A), (2) regarding pending and/or contemplated litigation, and/or 551.074, regarding personnel matters, and/or property acquisition.

➤ ADJOURN M.M./B.H. 11:34 Adjourned

I do hereby certify that the above Notice of Meeting of the Tyler County Commissioners Court is a true and correct copy of said Notice and that I posted a true and correct copy of said Notice in the Tyler County Courthouse at a place readily accessible to the general public at all times and that said Notice remained so posted continuously for at least 72 hours preceding the scheduled time of said meeting, as is required by Section 551.002 & 551.041.

Executed on _____ 2020 Time _____
Donece Gregory, County Clerk/Ex Officio Member of Commissioners Court

By: _____ (Deputy)