



DATE: 4/30/2024
TO: Lidia Solano – Jeff Leavins
FOR: Woodville, TX (Tyler County Rodeo Arena)

WE ARE TRANSMITTING (2) PAGES TO YOU, INCLUDING THIS PAGE. IF YOU DO NOT RECEIVE ALL OF THE PAGES, PLEASE CALL 1-800-433-3116.

BUYBOARD CONTRACT #679-22

(NON-ELEVATED) I-Beam Grandstands

(2) 10 row x 87'-0" BC-2CL (NON-ELEVATED) I-Beam Grandstands

Materials Delivered & Installed _____ \$284,075.00

Price does NOT include any concrete foundation work

Grandstands Include: (Elevated I-Beam Grandstands)

1. Aluminum (2x10) clear anodized seat boards
2. Two (2) Aluminum (2x10) (**CLEAR ANODIZED**) footboards at each row, standard full deck ("semi-closed") system
3. Aluminum clear anodized risers at each row
4. Aisles 48" wide with mid-rails
5. Galvanized steel columns, cross bracing, stringers, bracing, seat brackets and guardrail posts
 - a. Seat brackets & guardrail posts to be a galvanized steel angle
6. W/C seat spaces to meet ADA requirements
7. Two (2) line aluminum pipe rail system w/ 9 ga. chain link fence infill guardrail
8. 8" rise w/ 24" tread
9. **Foundation requirements: Owner to furnish Sturdisteel with a "site-specific" Geotech report to be used in the designing of the grandstand foundations. Sturdisteel will coordinate with a third party engineering firm to assist in this design. FOUNDATION TO BE INSTALLED BY OTHERS – Sturdisteel to provide Anchor Bolts**

Sturdisteel Notes:

1. **Sturdisteel Excludes:** Any site preparatory work (i.e. leveling, grading, over-excavation, compaction or concrete work), fence or rails not attached to the grandstand or fences below the grandstand), any concrete work or flatwork for grandstands or grandstand egress to sit on, **any city or state sales tax, permits, on site inspections, third party inspections, bonds or fees**, any plan approval time, any testing fees, *Any item not specifically mentioned as included*
2. Sturdisteel is AISC Certified.
3. **Sturdisteel excludes:** Any concrete foundation work needed for grandstands or grandstand egress, any demo or removal of existing material on site, any site grading, site leveling, over-excavation, or compaction, any fencing or railing not attached to the grandstand
4. **PLEASE NOTE:** Sturdisteel will require direct access with equipment to unload and stage grandstand material adjacent to area of installation (access by others), any site remedial work is excluded (this includes, but is not limited to: new sod, dirt work, rutting)
5. **PLEASE NOTE:** Sturdisteel installation price does not include any prevailing wage rates or union labor
6. **Mill finish** footboards are quoted and being provided. **Mill finish** Aluminum can be discolored or stained prior to delivery & installation. This does not damage the structural integrity of the Aluminum. The footboards are the walking surfaces and will have liquids spilled on them and



trash and dirt will collect on them. The staining is caused by condensation or moisture during extrusion, packaging, transport and or storage. The stains will be white, brown or black in color. The stains will fade over time, however most customers are unaware of the possibility of mill finish aluminum staining.

- a. *Add for Clear anodized footboards in lieu of mill finish footboards is shown above. Please note all comments on mill finish aluminum shown above. It is not the responsibility of Sturdisteel to educate the owner on the potential staining that may occur prior to installation. Mill finish aluminum is the specified product, and as such will not be permitted on any punch list.*
7. Project duration is 60-75 days for submittals after receipt of order, 90-120 days for materials fabrication after receipt of approved drawings, installation would be 21-28 days once on site with material (subject to crew availability)
 - a. PLEASE NOTE: At this time, STURDISTEEL can NOT commit to a 10/1/2024 completion – therefore, they will work off an installation period starting after the Tyler County Rodeo event that takes place in early October.
8. ***Foundation requirements: Owner to furnish Sturdisteel with a “site-specific” Geotech report to be used in the designing of the grandstand foundations. Sturdisteel will coordinate with a third party engineering firm to assist in this design. FOUNDATION TO BE INSTALLED BY OTHERS – Sturdisteel to provide Anchor Bolts***
9. Payment is Net 30 days.
10. This quote is good for 30 days.
11. ***This scope sheet is to become part of any purchase order or contract for this project.***

If you have any questions please contact me via email at tglaesmann@sturdisteel.net or at 800-433-3116. Please see our new website for more information such as specifications and previous projects by Sturdisteel at www.sturdisteel.com.

Todd Glaesmann, Sales