

Signature Seal & Stripe LLC
PO Box 517
Livingston, TX 77351
281-761-8141



Mike Marshall
Tyler County Airport 09R
100 W Bluff St #A003
Woodville, TX 75979

Proposal Number 25010
Proposal Date 08/17/2025
Reference Main Ramp 49,810 sqft

Pricing

Description	Rate	Qty	Line Total
Crack Fill Use a wire wheel to grind out approx 4,400 linear feet of asphalt cracks. This will remove any vegetation and dirt within the cracks. Spray weed killer into the cleaned out cracks as an extra precaution. Then we will use a commercial grade crack filler heated to 350 degrees to fill the cracks and bond to the existing asphalt. Liquid Sealer will be used on small hairline cracks.	\$6,811.00	1	\$6,811.00
Sealcoating Apply two coats of Polymer Modified Coal Tar Sealer on the main ramp area that covers approx 49,800 sqft. The sealer will not be diluted and will be installed extra thick.	\$16,399.75	1	\$16,399.75
Line Striping We will use a high quality Thermoplastic traffic paint to stripe four airplane parking areas. Stripe one helicopter landing spot. Stripe one 6" X 210' stripe down the center of the ramp from the hold short area.	\$1,060.00	1	\$1,060.00
Subtotal			24,270.75
Tax			0.00
Proposal Total (USD)			\$24,270.75

Notes

Work will be completed after normal business hours or on the weekend.

Terms

Payment Terms NET15

Main Ramp2.jpg



Main Ramp3.jpg



Main Ramp4.jpg



Main Ramp5.jpg



Main Ramp6.jpg



Main Ramp7.jpg



Main Ramp1.jpg



09R Main Ramp 49,810 sqft.png

