Legefy Roofing, LLC
PO Box 806
Springtown, TX 76082-3846
+18179015475
dana@legefyroofing.com

Estimate

ADDRESS
Tyler County Tyler County Sheriff's Office 702 Magnolia Woodville, TX

ESTIMATE #	DATE
1166	09/01/2026

PRODUCT/SERVICE	SCOPE OF WORK	AMOUNT
Silicone Membrane Installation	TYLER COUNTY SHERIFF'S OFFICE (Approx. 20,500sf) TPO APPLICATION Pre-roof inspection (core sample, pull test, thermal scans) performed, as required by manufacturer. Pressure wash existing substrate to a clean, dry, workable surface, as required by manufacturer. Apply Progressive Materials P-151 Single Ply Primer, as required by manufacturer. Apply Progressive Materials Flashing Grade Mastic to all penetrations, fasteners and seams, as required by manufacturer. Apply Progressive Materials HS 3201 High Solids Silicone Roofing System to entire roof surface area (2.7 gal/sq minimum), as required by manufacturer. Progressive Materials manufacturer inspection of completed roof and all details. 20yr Labor Warranty and 50yr Material Warranty included.	66,525.00

You are a valued customer, and we thank you for your business!

We accept ACH payments, or you can mail a check made out to Legefy Roofing LLC and mailed to:
PO Box 806, Springtown, TX 76082
50% due at contract initiation.
50% due at project completion.

SUBTOTAL	66,525.00
TAX	0.00
TOTAL	**$66,525.00**

Accepted By

Accepted Date

Thank you for considering us for your roofing needs.